DRAFT STORMWATER MANAGEMENT PLAN

Small Municipal Separate Stormwater Systems (MS4)

33 Broad Street | One Weybosset Hill
Floor 7
Providence, Rhode Island 02903

woodardcurran.com
COMMITMENT & INTEGRITY DRIVE RESULTS

229618
West Haven, CT Veterans Administration Medical Campus
July 2017

TABLE OF CONTENTS

SECTION **PAGE NO.**

EXECUTIVE SUMMARY ES-1

1. INTRODUCTION 1-1

1.1 Regulatory Background 1-1
1.2 Eligibility 1-1
1.3 Applicability 1-1

2. MS4 GENERAL PERMIT ORGANIZATION 2-1

2.1 Public Education and Outreach 2-1
2.2 Public Participation and Involvement 2-1
2.3 Illicit Discharge Detection and Elimination 2-1
2.4 Construction Site Stormwater Runoff Control 2-1
2.5 Post-Construction Stormwater Runoff Control 2-1
2.6 Good Housekeeping and Pollution Prevention 2-1

3. WEST HAVEN CAMPUS PHYSICAL SETTING 3-1

3.1 Water Quality 3-1
3.2 Endangered and Threatened Species 3-3
3.3 Aquifer Protection Area 3-3
3.4 Historic Properties 3-3
3.5 New Discharges to Impaired Waters 3-3

4. MCM #1: PUBLIC EDUCATION AND OUTREACH 4-1

4.1 Implement Public Education Program 4-1
4.1.1 BMP Implementation: Public Education Program 4-1
4.2 Address Education and Outreach for Pollutants of Concern 4-1
4.2.1 BMP Implementation: Education Outreach 4-2

5. MCM #2: PUBLIC INVOLVEMENT AND PARTICIPATION 5-1

5.1 Comply with Public Notice Requirements for the Stormwater Management Report and Annual Reports 5-1
5.1.1 BMP Implementation: Public Participation and Involvement 5-1

6. MCM #3: ILLICIT DISCHARGE DETECTION AND ELIMINATION 6-1

6.1 Prepare Written IDDE Program 6-1
6.1.1 BMP Implementation: Written IDDE Program 6-1
6.2 MS4 Outfall and Interconnection Mapping 6-1
6.2.1 BMP Implementation: MS4 Outfall and Interconnection Mapping 6-2
6.3 Illicit Discharge Reporting Program 6-2
6.3.1 BMP Implementation: Illicit Discharge Reporting Program 6-2
6.4 Authority to Prohibit Illicit Discharges 6-2
6.4.1 BMP Implementation: Legal Authority to Prohibit Illicit Discharges 6-3
6.5 Development of a Record Keeping System for IDDE Tracking 6-3
6.5.1 BMP Implementation: Development of a Record Keeping System for IDDE Tracking 6-3
6.6 Addressing IDDE in Areas with Pollutants of Concern 6-3
6.6.1 BMP Implementation: Addressing IDDE in Areas with Pollutants of Concern 6-4

7. MCM #4: CONSTRUCTION SITE STORMWATER RUNOFF CONTROLS 7-1

7.1 Implement, Upgrade and Enforce Land Use Regulations or Other Legal Authorities to Meet Requirements of the MS4 General Permit 7-1
7.1.1 BMP Implementation: Land Use Regulations 7-1
7.2 Interdepartmental Coordination 7-1
7.2.1 BMP Implementation: Interdepartmental Coordination 7-2
7.3 Site Review and Inspection 7-2
7.3.1 BMP Implementation: Site Review and Inspection 7-2
7.4 Implement Public Comment Procedures on Site Development 7-2
7.4.1 BMP Implementation: Site Development Public Comment Procedures 7-2
7.5 CT DEEP Permit Notification 7-2
7.5.1 BMP Implementation: CT DEEP Permit Notification 7-3

8. MCM #5: POST CONSTRUCTION MANAGEMENT IN NEW DEVELOPMENT OR REDEVELOPMENT 8-1

8.1 Establish and/or Update Authority Regarding Low Impact Development and Runoff Reduction in Site Development Planning 8-1
8.1.1 BMP Implementation: Low Impact Development and Runoff Reduction in Site Development Planning 8-1
8.2 Enforce Low Impact Development/Runoff Reduction Requirements for Development and Redevelopment Projects 8-1
8.2.1 BMP Implementation: Enforcement of LID/Runoff Reduction Requirements for Development and Redevelopment Projects 8-1
8.3 Implement Long-Term Maintenance Plan for Stormwater Basins and Treatment Structures 8-2
8.3.1 BMP Implementation: Long-Term Maintenance Plan for Stormwater Basins and Treatment Structures 8-2
8.4 Directly Connected Impervious Area Mapping 8-2
8.4.1 BMP Implementation: Directly Connected Impervious Area Mapping 8-2
8.5 Address Post-Construction Issues in Areas with Pollutants of Concern 8-2
8.5.1 BMP Implementation: Addressing Post-Construction Issues in Areas with Pollutants of Concern 8-3

9. MCM #6: POLLUTION PREVENTION AND GOOD HOUSEKEEPING 9-1

9.1 Development and/or Implementation of a Formal Employee Training Program 9-1
9.1.1 BMP Implementation: Formal Employee Training Program 9-1
9.2 MS4 Property Management 9-1
9.2.1 Parks and Open Space 9-1
9.2.2 Buildings and Facilities 9-1
9.2.3 Vehicles and Equipment 9-2
9.2.4 Leaf Management 9-2
9.2.4.1 BMP Implementation: MS4 Property Management 9-2
9.2.5 Implement Coordination with Interconnected MS4s 9-2
9.2.5.1 BMP Implementation: Interconnected MS4 Coordination 9-2
9.2.6 Develop/Implement Program to Control Other Sources of Pollutants to the MS4 9-3
9.2.6.1 BMP Implementation: Control Other Sources of Pollutants to the MS4 9-3
9.2.7 Evaluation of Additional Measures for Discharges to Impaired Waters 9-3
9.2.7.1 BMP Implementation: Additional Measures for Discharges to Impaired Waters 9-3
9.2.8 Tracking of Projects that Disconnect Directly Connected Impervious Area 9-3
9.2.8.1 BMP Implementation: Tracking DCIA Projects 9-4
9.2.9 Develop and/or Implement an Infrastructure Repair and/or Rehabilitation Program 9-4

9.2.9.1 BMP Implementation: Infrastructure Repair/Rehabilitation Program 9-4
9.2.10 Develop/Implement a Plan to Identify/Prioritize Retrofit Projects 9-4
9.2.10.1 BMP Implementation: Identification/Prioritization of Retrofit Projects 9-4
9.2.11 Street Sweeping 9-4
9.2.11.1 BMP Implementation: Street Sweeping 9-5
9.2.12 Catch Basin Cleaning 9-5
9.2.12.1 BMP Implementation: Catch Basin Cleaning 9-6
9.2.13 Snow Management Procedures 9-6
9.2.13.1 BMP Implementation: Snow Management Procedures 9-6

10. MONITORING REQUIREMENTS 10-1

10.1 Inventory and Mapping of Discharges to Impaired Waters 10-1
10.1.1 BMP Implementation: Inventory and Mapping of Discharges to Impaired Waters 10-1
10.2 Outfall and Interconnection Screening 10-1
10.2.1 BMP Implementation: Outfall/Interconnection Screening 10-2
10.3 Follow-Up Investigations of Drainage Areas 10-2
10.3.1 BMP Implementation: Follow-Up Investigations of Drainage Areas 10-2
10.4 Annual Monitoring of Priority Interconnections 10-2
10.4.1 BMP Implementation: Annual Monitoring of Priority Interconnections 10-2

11. ADDITIONAL INFORMATION 11-1

11.1 Qualifying State or Federal Program 11-1
11.2 Coordination of Permit Responsibilities 11-1
11.3 Retention of Records 11-1
11.4 Reporting Requirements 11-1

12. PERMITTEE CERTIFICATION 12-1

13. QUALIFIED PROFESSIONAL ENGINEER CERTIFICATION 13-1

TABLES

Table 1: West Haven Campus CT DEEP Drainage Basin
Table 2: Impaired Waterbodies Receiving West Haven Campus Outfall Discharges
Table 3: TMDL Strategies Applying to the West Haven Campus

APPENDICES

Appendix A: CT DEEP MS4 General Permit
Appendix B: Natural Diversity Data Base Areas Map

1. INTRODUCTION

1.1 Regulatory Background

In 1990, the United States Environmental Protection Agency (EPA), as authorized by the Clean Water Act (CWA), promulgated Phase I stormwater regulations addressing the management of stormwater discharges from large and medium municipal separate storm sewer systems (MS4s). During Phase I, municipalities with MS4s serving populations of 100,000 or more were required to obtain National Pollutant Discharge Elimination System (NPDES) permit coverage for their stormwater discharges.

In 1999, EPA promulgated the "Stormwater Phase II Final Rule", which extended NPDES permit coverage requirements to "small MS4s". This extended coverage was designed to capture stormwater discharges from smaller municipalities and state or federally operated MS4s with at least 1,000 residents and/or average daily population that are in the Urbanized Area, as defined by the 2000 or 2010 census.

To satisfy EPA's requirements, the Connecticut Department of Energy and Environmental Protection (CT DEEP) developed the "General Permit for the Discharge of Stormwater Municipal Separate Storm Sewer Systems" ("MS4 General Permit", "Permit"). The intent of the Permit is to reduce the discharge of pollutants from MS4s to the maximum extent practicable to protect water quality, in accordance with the CWA. CT DEEP's first MS4 General Permit became effective on January 1, 2004, expiring January 1, 2009. The Permit was subsequently reissued without modification until the June 30, 2017 expiration. CT DEEP has issued a new MS4 General Permit, effective July 1, 2017. The information contained in this Stormwater Management Plan (SMP) aligns with the requirements presented in the recently reissued Permit.

The goal of the MS4 program is accomplished through a variety of pollution prevention management practices and proactive actions that rely on education and participation of the owners and operators of the MS4s, as well as the implementation of best management practices (BMPs) and good housekeeping measures by the owners and operators within the MS4.

The MS4 General Permit is a self-administered stormwater management program that relies on the Permittee to be aware of compliance with Permit requirements, which are broadly outlined in this SMP. For a comprehensive understanding of Permit requirements, refer to the copy of the complete MS4 General Permit provided as **Appendix A**.

1.2 Eligibility

The United States Department of Veterans Affairs West Haven Medical Campus ("VA West Haven Medical Campus"/ "West Haven Campus") is eligible for coverage under the MS4 General Permit due to its classification as a federally operated MS4 located within the "Urbanized Area", as defined by the 2010 United States Census. The Permit further defines a "Federal Institution" as:

"A facility (including, but not limited to, state and federal prisons, office complexes, hospitals; university campuses, public housing authorities, schools, or other special districts) consisting of more than one building that is owned by an agency or department of the State of Connecticut (except the Department of Transportation) or a federal agency and has an average daily population of 1,000 people or more."

Based on this definition, the West Haven Campus is subject to the MS4 General Permit requirements.

1.3 Applicability

The actions and methods described in this SMP apply within the boundaries of the West Haven Campus, except as otherwise noted. Any stormwater discharges subject to the CT DEEP Industrial Stormwater General Permit, such as

discharges originating from maintenance garages and salt storage sheds, will be subject to the requirements of that permit, if applicable, at the West Haven Campus.

2. MS4 GENERAL PERMIT ORGANIZATION

It is the responsibility of the Permittee to implement and comply with the Permit conditions. The Permit is organized around six minimum control measures (MCMs), which, when combined, provide the framework of a MS4's stormwater management program. Implementation of the regulatory requirements of each MCM are embedded within BMPs, which contain describe specific actions related to the goals of each MCM and are designed to facilitate compliance with the Permit. A brief overview of each MCM is provided below, and BMPs associated with each MCM, along with the party responsible for implementation, implementation deadline (as prescribed in the Permit), and measurable goal to determine BMP success as it relates to Permit requirements, are summarized in their respective sections of this SMP.

2.1 Public Education and Outreach

The primary purpose of this MCM is to educate the public about the impacts of polluted stormwater runoff discharges to water quality, as well as motivate the public to use best management practices (BMPs) to reduce polluted stormwater runoff. In the case of the Veterans Administration, the public is loosely defined as employees, patients, visitors, and contractors working at the campus.

2.2 Public Participation and Involvement

Public participation and involvement is an extension of public education and outreach; in that it relies on an informed community to participate in the planning and implementation of processes that improve water quality through the reduction of polluted stormwater runoff.

2.3 Illicit Discharge Detection and Elimination

The Illicit discharge detection and elimination (IDDE) MCM provides the MS4 with the legal authority and methodology to find and eliminate illicit discharges to the storm sewer system, such as interconnected sanitary sewer tie-ins or illegal discharges to the MS4 due to improper disposal of waste.

2.4 Construction Site Stormwater Runoff Control

This MCM focuses on developing, implementing and enforcing an erosion and sediment control program for construction activities that disturb 1 or more acres.

2.5 Post-Construction Stormwater Runoff Control

Once construction activities described in Section 2.4 are completed, this MCM requires the development, implementation and enforcement of a program to address discharges of post-construction stormwater runoff from new and redevelopment areas through the implementation of low impact development (LID) and other stormwater runoff reduction methods.

2.6 Good Housekeeping and Pollution Prevention

MS4 Permittee staff are often responsible for implementing many of the practices that prevent or reduce pollutant runoff within the permitted area, such as street sweeping, reduction in the use of pesticides or street salt, or catch-basin cleaning. This MCM describes requirements the MS4 permittee must enact to develop and implement a program designed to prevent or reduce potential pollutants generated from permittee operations from entering stormwater runoff.

3. WEST HAVEN CAMPUS PHYSICAL SETTING

The VA West Haven Campus is an approximately 47-acre parcel with the physical address of 950 Campbell Avenue located in the City of West Haven, New Haven County, Connecticut. The West Haven Campus contains approximately 40 buildings consisting of medical facilities, offices, maintenance and utility structures, storage buildings, aboveground and underground utilities, and related parking and landscaped areas. The primary function of the West Haven Campus is to provide inpatient and outpatient medical services to the Veteran community. The following sections describe physical information pertaining to requirements for authorization provided in the Permit.

3.1 Water Quality

The CWA requires each state to monitor water quality, assess the monitoring results against designated waterbodies, and report on water quality of waterbodies in an integrated report that is submitted to the United States Environmental Protection Agency (EPA) every two years. This report, known as the "Integrated Water Quality Report", identifies waterbodies impaired by pollutants and the pollutant causing the impairment, when known. If a waterbody is not meeting water quality standards, each state is required to develop a total maximum daily load (TMDL), which is a management strategy to restore impaired waterbodies to a condition meeting water quality standards. TMDLs for waterbodies, where established, are included in the "Integrated Water Quality Report".

The West Haven Campus is located within the West River regional basin, which is located within the South Central Coast watershed. Outfalls and/or interconnections located on the western portion of the campus discharge to the Cove River, located within the South Central Shoreline subregional watershed, which is also a part of the South Central Coast watershed. Outfalls and/or interconnections located on the eastern portion of the campus ultimately discharge to the West River, located within the South Central Coast subregional watershed, which is also a part of the South Central Coast watershed.

Based on Connecticut's most recent "Integrated Water Quality Report", 2014, the segment of the West River receiving outfall discharges from the West Haven Campus has been assessed in accordance with Section 305(b) of the CWA. The table below summarizes the results of this assessment. The segment of the Cove River receiving outfall discharges from the West Haven Campus has not been assessed. As such, minimal information is available for this waterbody, but is summarized in the table below.

Table 1: West Haven Campus CT DEEP Drainage Basin

Watercourse	Drainage Basin	Location	Miles	Surface Water Quality Class	Description
LIS CB Inner – West River (Lower), West Haven Waterbody Segment ID CT-C1_015-SB	Sub-regional Basin: West River Regional Basin: South Central Western Complex Major Basin: South Central Coast Basin ID Number: 5305-00	Central portion of Long Island Sound, Inner Estuary, from mouth just DS of I95 crossing (City Point, New Haven Harbor), US to SA/SB water quality line at Route 1 crossing, West Haven	0.065	SB	Aquatic Life: Not Supporting Recreation: Not Supporting Fish Consumption: Fully Supporting Shellfish Consumption: Unassessed Shellfish Classification: Commercial Harvesting

Under Section 303(d) of the CWA waterbodies assessed for impairments that are determined to not meet minimum water quality standards for their designated uses are identified as impaired. The table below summarizes identified impairments for the assessed waterbodies receiving discharge from the West Haven Campus outfalls. No TMDLs have been set for this segment of the West River to date. As discussed above, the segment of the Cove River receiving outfall discharges from the West Haven Campus has not been assessed. There is no information regarding impairment status for this portion of the Cove River.

Table 2: Impaired Waterbodies Receiving West Haven Campus Outfall Discharges

Waterbody	Cause	Potential Source	Impaired Designated Use
LIS CB Inner – West River (Lower), West Haven	Fecal Coliform	Not listed	Commercial shellfish harvesting, where authorized
	Dissolved Oxygen Saturation	Landfills, municipal discharges, illicit discharge, remediation sites, groundwater contamination, combined sewer overflow	Habitat for marine fish, other aquatic wildlife and wildlife
	Nutrient/Eutrophication Biological Indicators	Landfills, municipal discharges, illicit discharges, remediation sites, groundwater contamination, combined sewer overflow	Habitat for marine fish, other aquatic wildlife and wildlife
	Oil and Grease	Landfills, illicit discharge, remediation sites, groundwater contamination, combined sewer overflow	Habitat for marine fish, other aquatic wildlife and wildlife
	Dissolved Oxygen	Landfills, municipal discharges, illicit discharge, remediation sites, groundwater contamination, combined sewer overflow	Habitat for marine fish, other aquatic wildlife and wildlife
	Polychlorinated biphenyls	Landfills, illicit discharges, remediation sites, groundwater contamination, combined sewer overflow	Habitat for marine fish, other aquatic wildlife and wildlife
	Enterococcus	Not listed	Recreation

In addition to the impairments identified above for the West River, the CT DEEP has established TMDL and/or management strategies for waterbodies statewide, and select waterbodies located within Long Island Sound contributing watersheds. TMDLs are established to calculate the amount of a pollutant a waterbody can assimilate without exceeding water quality standards or impairing designated uses such as swimming, shellfishing, or providing drinking water. Since the West Haven Campus is located within a Long Island Sound contributing watershed, the

DRAFT

conditions of these TMDLs apply. A description of each TMDL and associated pollutant is summarized in the table below.

Table 3: TMDL Strategies Applying to the West Haven Campus

TMDL Name	Pollutant	Waterbody Name	Relevant Regulatory Link
A TMDL Analysis to Achieve Water Quality Standards for Dissolved Oxygen in Long Island Sound	Nitrogen	Long Island Sound & Contributing Watersheds	http://www.ct.gov/deep/lib/deep/water/lis_water_quality/nitrogen_control_program/tmdl.pdf
Northeast Regional Mercury TMDL	Mercury	All CT Inland Waters	http://www.ct.gov/deep/lib/deep/water/tmdl/tmdl_final/ne_hg_tmdl.pdf

3.2 Endangered and Threatened Species

The CT DEEP Natural Diversity Data Base Areas (NDDB) map for West Haven, CT, dated December 2016, does not depict any State and/or Federal listed species and significant natural communities within the property boundary or outfall and/or interconnection discharge locations of the West Haven Campus. A copy of the NDDB map is provided in **Appendix B**.

3.3 Aquifer Protection Area

The West Haven Campus and outfall and/or interconnection discharge locations are not located within an aquifer protection area. This determination was made via consultation with the CT Environmental Conditions Online Simple Viewer map on June 1, 2017, http://cteco.uconn.edu/viewer/index.html?viewer=simple.

3.4 Historic Properties

No specific stormwater related activities are proposed in this plan that have the potential to impact historic properties. If new discharges are proposed during the current MS4 General Permit, their potential effects to any historic properties will be evaluated and addressed under applicable historic preservation statutes.

3.5 New Discharges to Impaired Waters

No new discharges to impaired waters are planned as part of stormwater related activities being conducted at the West Haven Campus. If new discharges to impaired waters are proposed as part of future activities, the VA will verify that the new discharges will not result in a net increase of pollutant loading of the specific pollutant that the waterbody is impaired by to the impaired waterbody.

DRAFT

4. MCM #1: PUBLIC EDUCATION AND OUTREACH

The West Haven Campus is not a traditional MS4 in that the "public" served at the site is comprised of employees, patients, visitors, and contractors instead of residents and commercial and/or industrial entities. Because of this, public education and outreach efforts will focus on engaging and educating these audiences about the environmental concerns associated with stormwater runoff, as well as ways that they can minimize the contribution of pollutants to stormwater runoff.

4.1 Implement Public Education Program

The West Haven Campus will collect and distribute stormwater educational materials that, at a minimum, address the impacts of the following sources/actions on water quality:

- Pet waste
- Impervious cover
- Fertilizer application
- Pesticide and herbicide usage
- Illicit discharges and improper waste disposal into the MS4.

Educational outreach resources have been developed by the University of Connecticut's Nonpoint Education for Municipal Officials (UCONN NEMO) program, the CT DEEP, and EPA. These educational materials, as well as other identified educational materials, can be used, as applicable, to provide educational outreach information to the public. Educational materials will be made available to the public using the best available means to reach appropriate audiences and maximize impact of the messages provided in the materials and may include fact sheets, brochures, website links, internal internet postings, and/or signage.

4.1.1 BMP Implementation: Public Education Program

Permit Regulatory Reference:	Section 6(a)(1)(A)-(B)
Primary Responsible Party:	Green Environmental Management System (GEMS) Program Manager, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Development and distribution of appropriate and topical educational outreach materials to relevant audiences

4.2 Address Education and Outreach for Pollutants of Concern

Based on a review of the water quality of waterbodies receiving MS4 outfall discharge from the campus, as described in Section 3.1, targeted measures for specific impairments are required per Section (6)(a)(1)(C) of the Permit. Specifically, the following impairments have been identified for receiving waters and/or as part of State-wide TMDLs or strategies to reduce impacts to water quality. Educational materials will be specifically tailored and targeted to educate the public on the sources, impacts, and available pollution reduction practices from the following campus-specific sources:

Impairment	Educational Topics for Pollutants of Concern
Bacteria	• Septic systems* • Sanitary cross connections • Waterfowl* • Pet waste • Manure piles associated with livestock and horses*
Mercury	• Thermometers • Thermostats • Fluorescent lights • Button cell batteries
Nitrogen	• Septic systems* • Fertilizer use • Grass clippings and leaf management • Discharge of sediment from construction sites and other erosive surfaces
Phosphorus	• Septic systems* • Fertilizer usage • Grass clippings and leaf management • Detergent use • Discharge of sediment from construction sites and other erosive surfaces.

NOTE: "*" denotes sources to be targeted in the Permit, but are not considered relevant to campus operations. As such, these sources are provided for information purposes but are not expected to be part of education and outreach efforts.

4.2.1 BMP Implementation: Education Outreach

Permit Regulatory Reference:	Section 6(a)(1)(A)-(D)
Primary Responsible Party:	GEMS Program Manager, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Development and distribution of appropriate and topical educational outreach materials to relevant audiences

DRAFT

5. MCM #2: PUBLIC INVOLVEMENT AND PARTICIPATION

This MCM is designed to provide the public with the opportunity to participate in the West Haven Campus's stormwater management efforts, through review of documents relevant to the stormwater management planning process such as this SMP, as well as Annual Reports summarizing previous stormwater management activities implemented at the campus during the previous regulatory reporting period.

5.1 Comply with Public Notice Requirements for the Stormwater Management Report and Annual Reports

The West Haven Campus will publish a public notice on its website, www.connecticut.va.gov, notifying the public of the availability of the SMP and/or Annual Report for review and comment. In the case of the SMP, the public notice will allow for a 90-day comment period prior to finalization of this draft report. In the event of a substantial edit to the SMP, a 30-day comment period will be provided. Public notice for Annual Report availability will be 30 days, at a minimum.

Each public notice will provide a contact name, phone number, address, and email that the public can send comments regarding the SMP and/or Annual Report, as well as the location the report for public review.

5.1.1 BMP Implementation: Public Participation and Involvement

Permit Regulatory Reference:	Section 6(a)(2)(A)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	Public notice of draft SMP availability for 30-day public comment period published by 4/03/2017
	Public notice of draft Annual Report availability for 30-day public comment period published by January 31 each year
Measurable Goal:	Public draft SMP public notice prior to 4/03/2017, provide draft SMP for public review and comment
	Publish draft Annual Report public notice annually, provide draft reports to public for review and comment

DRAFT

6. MCM #3: ILLICIT DISCHARGE DETECTION AND ELIMINATION

Illicit discharge detection and elimination (IDDE) is an important part of preventing pollutants from entering MS4s and ultimately discharging to waterbodies. The term "illicit discharge" refers to any unpermitted discharge to waters of the State that does not consist entirely of stormwater or uncontaminated groundwater, except those discharges identified in Section 3(a)(2) of the Permit:

- Uncontaminated ground water discharges including, but not limited to, pumped ground water, foundation drains, water from crawl space pumps and footing drains;
- Irrigation water including, but not limited to, landscape irrigation and lawn watering runoff;
- Residual street wash water associated with sweeping;
- Discharges or flows from firefighting activities (except training); and
- Naturally occurring discharges such as rising groundwaters, uncontaminated ground water infiltration, springs, diverted stream flows, and flows from riparian habitats and wetlands.

The West Haven Campus is serviced by municipal sewer, provided by the City of West Haven. There are no septic systems located on the site.

6.1 Prepare Written IDDE Program

In accordance with the Permit, the West Haven Campus will prepare a written IDDE program that addresses areas within the campus that have been identified as contributing MS4 discharges to impaired waters and/or areas of the campus containing greater than 11% of directly connected impervious area (DCIA). The purpose of the IDDE program is to provide the framework to investigate, find, and eliminate sources of illicit discharges to the West Haven Campus's MS4. The IDDE program will address, at a minimum, the following elements

- Methodology to correct existing illicit discharges;
- A citizen reporting and tracking system;
- Inventory of MS4 outfalls and/or interconnections the campus discharges to, screening and sampling program, and methods for prioritization of outfalls and/or interconnections;
- Methodology to record activities conducted to resolve illicit discharges.

6.1.1 BMP Implementation: Written IDDE Program

Permit Regulatory Reference:	Section 6(a)(3)(A)(i)
Primary Responsible Party:	GEMS Program Manager, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Development of a written IDDE Program containing the required elements by the second year of the Permit effective date

6.2 MS4 Outfall and Interconnection Mapping

The West Haven Campus will create a database and associated map of all stormwater discharges from a pipe or conduit located within and owned or operated by the campus, and all interconnections with other MS4s. The database will include:

- The type, material, size, shape, and location (identified using latitude and longitude) of each conveyance, outfall/interconnection or channelized flow;
- The name, waterbody identification, and surface water classification of the immediate surface waterbody or wetland receiving stormwater discharge. If the outfall/interconnection does not discharge directly to a named waterbody, the name and waterbody identification of the nearest named waterbody to which the outfall/interconnection ultimately discharges will be used;
- The name of the watershed, including the subregional drainage basin number (available from CT ECO at www.cteco.uconn.edu) in which the discharge is located;
- The date of the most recent outfall inspection, condition of the outfall and/or interconnection, and any indicators of potential non-stormwater discharges at the most recent inspection.

The database should, if possible, be prepared in a format compatible with Microsoft Excel. The map should, if possible, be developed in a GIS format.

6.2.1 BMP Implementation: MS4 Outfall and Interconnection Mapping

Permit Regulatory Reference:	Section 6(a)(3)(C)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Development of an outfall/interconnection database and map containing the required elements by the third year of the Permit effective date

6.3 Illicit Discharge Reporting Program

The West Haven Campus will develop a program for citizen reporting of illicit discharges that clearly describes how citizens can submit an illicit discharge report. The program will provide an email address and/or phone number for receipt of reports. Upon receipt of a report, the West Haven Campus will investigate and eliminate reported illicit discharges, if the report of the illicit discharge contains at least a time and location of an observed discharge. Investigations will occur promptly upon receipt, and all reports and responses to the reports will be included in the Annual Report.

6.3.1 BMP Implementation: Illicit Discharge Reporting Program

Permit Regulatory Reference:	Section 6(a)(3)(A)(iii)
Primary Responsible Party:	GEMS Program Manager, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Documentation and maintenance of a record of illicit discharge abatement activities including the required elements.

6.4 Authority to Prohibit Illicit Discharges

Illicit discharges to the storm sewer system will be prohibited by an authority such as a written procedure, or other similar authority. The authority will include the following components:

- Prohibition of illicit discharges to the MS4, and removal of discharges consistent with the schedule provided in the Permit;

- Authorization of the investigation of suspected illicit discharges and elimination of illicit discharges, including from properties not owned or controlled by the MS4 that discharge to the MS4 (i.e. interconnections, CT DOT); and

- Control the discharge of spills and prohibit the dumping or disposal of materials including, but not limited to, residential, industrial, and commercial wastes, trash, used motor vehicle fluids, pesticides, fertilizers, food preparation waste, leaf litter, grass clippings, and animal wastes into the MS4;

For state and federal institutions, which includes the West Haven Campus, where this provision may conflict with existing rules, regulations, policies, chain of command or other circumstances, alternate provisions for enforcement may be utilized and will be considered during development of this authority.

6.4.1 BMP Implementation: Legal Authority to Prohibit Illicit Discharges

Permit Regulatory Reference:	Section 6(a)(3)(B)(i)-(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Establishment of a legal authority or similar mechanism to prohibit illicit discharges

6.5 Development of a Record Keeping System for IDDE Tracking

The West Haven Campus will develop a spreadsheet or similar mechanism to record and track illicit discharge abatement activities. This document will include the location (latitude/longitude and/or address), description, date, and time of the abatement activities, as well as any sampling data (if applicable), action(s) taken, date of removal or repair, and party responsible for the abatement actions.

Information recorded in the IDDE tracking system will be reported each year in the Annual Report.

6.5.1 BMP Implementation: Development of a Record Keeping System for IDDE Tracking

Permit Regulatory Reference:	Section 6(a)(3)(A)(v)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Documentation and recording applicable information regarding illicit discharge abatement related activities.

6.6 Addressing IDDE in Areas with Pollutants of Concern

The West Haven Campus will identify which areas of the campus are most likely to contribute nitrogen, phosphorus, and bacteria to the MS4. This assessment will consider proximity to bacteria impaired waters, low infiltrative soils (where data is available), and shallow groundwater. Septic system failures will not be considered as part of this assessment because the campus is connected to municipal sewer. Should the assessment identify potential contributors, outfall/interconnection screening and IDDE protocol will be implemented as described in the written IDDE program summarized in Section 6.1.

Information obtained during implementation of this Permit requirement will be reported each year in the Annual Report.

DRAFT

6.6.1 BMP Implementation: Addressing IDDE in Areas with Pollutants of Concern

Permit Regulatory Reference:	Section 6(a)(3)(D)(i)
Primary Responsible Party:	GEMS Program Manager, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Documentation and recording applicable information regarding addressing IDDE in areas with pollutants of concern.

DRAFT

7. MCM #4: CONSTRUCTION SITE STORMWATER RUNOFF CONTROLS

Construction site stormwater runoff controls are part of the MCM developed to implement a program to control stormwater discharges associated with land disturbances and development, including redevelopment activities. The focus of this MCM is on construction projects involving one or more acres of land disturbance, whether the project is individual or part of a common development plan, which fall under the eligibility requirements of the CT DEEP "General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities" (Construction General Permit).

7.1 Implement, Upgrade and Enforce Land Use Regulations or Other Legal Authorities to Meet Requirements of the MS4 General Permit

The West Haven Campus will establish the following measures through procedures or other appropriate mechanism for applicable (>1 acre) construction and redevelopment projects occurring at the campus:

- Require developers, contractors, and construction site operators to maintain consistency with the 2002 "Guidelines for Soil Erosion and Sediment Control", as amended, the "Connecticut Stormwater Quality Manual", and all stormwater discharge permits issued by the CT DEEP within the campus property boundary;
- Implement additional measures to improve and/or protect water quality as deemed necessary by the West Haven Campus;
- Implement long term maintenance planning to ensure the performance of retention ponds, detention ponds, and other stormwater management structures installed on the campus that discharge into the MS4, including inspection and maintenance requirements; and
- Control the contribution of pollutants between the West Haven Campus and MS4s owned and operated by others, such as the City of West Haven.

7.1.1 BMP Implementation: Land Use Regulations

Permit Regulatory Reference:	Section 6(a)(4)(A)(i)-(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Requirement of developers, construction site operators, or contractors to maintain consistency with the 2002 "Guidelines for Soil Erosion and Sediment Control", as amended, the "Connecticut Stormwater Quality Manual", and all stormwater discharge permits issued by CT DEEP within the West Haven Campus boundary.

7.2 Interdepartmental Coordination

Where applicable, the West Haven Campus will develop and implement a plan coordinating formal site plan review with internal departments responsible for plan approvals.

DRAFT

7.2.1 BMP Implementation: Interdepartmental Coordination

Permit Regulatory Reference:	Section 6(a)(4)(B)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Establish interdepartmental coordination, where applicable, for site plan review and approval processes.

7.3 Site Review and Inspection

The West Haven Campus reviews site plans for conformance with the VA's requirements related to stormwater control. Additionally, the West Haven Campus is authorized to inspect, surveille, and monitor construction activities to determine compliance related to the management of the MS4. Additionally, the West Haven Campus will take enforcement actions if necessary to confirm stormwater management measures are adequately installed, maintained, operated, and repaired, as required.

Site plan reviews and inspections will be generally documented in Annual Report submittals.

7.3.1 BMP Implementation: Site Review and Inspection

Permit Regulatory Reference:	Section 6(a)(4)(C)(i)-(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Review and revise, or develop, methods to verify applicable construction projects are compliant with MS4 General Permit requirements through inspection processes. Review and revise, or develop, inspection documentation and recordkeeping methods.

7.4 Implement Public Comment Procedures on Site Development

The West Haven Campus will implement a procedure for receipt and consideration of information submitted by the public concerning proposed and ongoing land disturbance and development activities.

7.4.1 BMP Implementation: Site Development Public Comment Procedures

Permit Regulatory Reference:	Section 6(a)(4)(D)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Review and refine, if necessary, procedures to collect, review, and record public comment on land disturbance activities.

7.5 CT DEEP Permit Notification

Developers or contractors working at the West Haven Campus will be notified of their potential obligation to obtain authorization for applicable construction activities under the CT DEEP Construction General Permit if the project disturbs one or more acres of land, either individually or as part of a common plan of development. The notification will

DRAFT

include a provision informing the developer/contractor of their obligation to provide a copy of the Construction General Permit required Stormwater Pollution Control Plan upon request.

7.5.1 BMP Implementation: CT DEEP Permit Notification

Permit Regulatory Reference:	Section 6(a)(4)(E)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Review and refine, or develop, the process designed to notify contractors of potential obligations to obtain CT DEEP Construction General Permit coverage.

DRAFT

8. MCM #5: POST CONSTRUCTION MANAGEMENT IN NEW DEVELOPMENT OR REDEVELOPMENT

Post-construction stormwater management is an important component of minimizing potential pollutant loadings to waterbodies via stormwater runoff. This MCM involves establishing requirements within MS4s to implement mitigation options to prevent the generation of stormwater runoff often generated because of the creation of impervious surfaces (e.g. parking lots, driveways, rooftops, etc.) during the development and redevelopment process.

8.1 Establish and/or Update Authority Regarding Low Impact Development and Runoff Reduction in Site Development Planning

The West Haven Campus will establish a procedure that requires, to the maximum extent practicable, that development within the MS4 will consider the use of low impact development (LID) and runoff reduction site planning prior to consideration of other practices during development. The procedure will include the following standards:

- Redevelopment of sites currently developed with directly connected impervious area (DCIA) of 40% or more will retain onsite half of the water quality volume of the site; or
- New development and redevelopment of sites with less than 40% DCIA will retain the water quality volume of the site; or
- An alternative retention/treatment standard will be used in accordance with Permit conditions.

8.1.1 BMP Implementation: Low Impact Development and Runoff Reduction in Site Development Planning

Permit Regulatory Reference:	Section 6(a)(5)(A)(i)-(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2022
Measurable Goal:	Review and refine, or develop, procedures to be compliant with MS4 General Permit requirements. Update procedures as necessary.

8.2 Enforce Low Impact Development/Runoff Reduction Requirements for Development and Redevelopment Projects

As part of the implementation of procedures presented in Section 8.1, the West Haven Campus will incorporate language to enforce LID/runoff reduction requirements for development and redevelopment projects.

8.2.1 BMP Implementation: Enforcement of LID/Runoff Reduction Requirements for Development and Redevelopment Projects

Permit Regulatory Reference:	Section 6(a)(5)(B)(i)-(vii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Require developers and/or construction site operators of development/redevelopment projects to implement runoff reduction and/or LID measures required by the MS4 General Permit.

DRAFT

8.3 Implement Long-Term Maintenance Plan for Stormwater Basins and Treatment Structures

In conjunction with the process described in Section 7.1, the West Haven Campus will require operations and maintenance plans for stormwater structures installed at the site, and, as the owner of these structures, will perform and document maintenance and operations related activities conducted in accordance with that plan. Inspection and maintenance related activities will be documented and maintained by the West Haven Campus.

8.3.1 BMP Implementation: Long-Term Maintenance Plan for Stormwater Basins and Treatment Structures

Permit Regulatory Reference:	Section 6(a)(5)(D)(i)-(iv)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Develop and implement long term maintenance plans for retention/detention ponds and other stormwater treatment structures located at the West Haven Campus, as applicable.

8.4 Directly Connected Impervious Area Mapping

The West Haven Campus will calculate the DCIA that contributes stormwater runoff to each of its MS4 outfalls/interconnections using mapping and data provided by the UCONN CLEAR website, CT DEEP, or similarly available information.

8.4.1 BMP Implementation: Directly Connected Impervious Area Mapping

Permit Regulatory Reference:	Section 6(a)(5)(C)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Calculation of the DCIA that contributes stormwater runoff to each MS4 outfall/interconnection, update calculations as DCIA is added or removed within the Town.

8.5 Address Post-Construction Issues in Areas with Pollutants of Concern

For waterbodies where nitrogen, phosphorus, or bacteria has been identified as a pollutant of concern, the West Haven Campus will develop, fund, implement, and prioritize solutions to any erosion and sedimentation problems identified during inspections or otherwise noted as part of a Retrofit Program. The Retrofit Program will be established to correct identified problems within a specific timeframe and establish short- and long-term maintenance related to the identified problem. The West Haven Campus will document problem areas that were retrofitted, the cost of the retrofit, and the anticipated pollutant reduction in their Annual Report.

DRAFT

8.5.1 BMP Implementation: Addressing Post-Construction Issues in Areas with Pollutants of Concern

Permit Regulatory Reference:	Section 6(a)(5)(E)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Evaluate outfall/interconnection screening results and/or observations recorded during maintenance activities. Prioritize and correct identified problems to be consistent with the Retrofit Plan.

DRAFT

9. MCM #6: POLLUTION PREVENTION AND GOOD HOUSEKEEPING

Pollution prevention and good housekeeping measures represent a key element of the MS4 program. Each measure requires the MS4 operator to evaluate and modify, when necessary, operational actions to reduce the quantity and types of pollutants that may enter stormwater runoff and ultimately discharge to a waterbody through the MS4. Each of these measures work to manage the amount of pollutants that collect on streets, parking lots, open spaces, and storage and vehicle maintenance areas to reduce pollutant loading in waterbodies.

9.1 Development and/or Implementation of a Formal Employee Training Program

The West Haven Campus will continue to provide on-the-job instruction and training opportunities to employees involving stormwater management related topics. Opportunities for relevant trainings will be periodically evaluated and implemented, where feasible.

9.1.1 BMP Implementation: Formal Employee Training Program

Permit Regulatory Reference:	Section 6(a)(6)(A)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Continue providing on-the-job training to new and existing employees related to stormwater management topics relevant to West Haven Campus operations.

9.2 MS4 Property Management

The following practices will be considered and implemented to minimize the discharge of pollutants originating from the site into the MS4.

9.2.1 Parks and Open Space

The West Haven Campus will optimize the application of fertilizers on their property, including consideration of proper storage and application practices, application schedule, and disposal of pesticides and herbicides in compliance with applicable State and Federals laws.

9.2.2 Buildings and Facilities

The West Haven Campus will evaluate the use, storage, and disposal of petroleum and non-petroleum products in their facilities, and confirm that employees responsible for handling these types of products are aware of and implement proper procedures. Spill Prevention Plans are in place and/or will be prepared for applicable facilities, including coordination with the local fire department, as necessary. In addition, the following measures will be applied:

- Develop and/or implement procedures to confirm the proper management of dumpsters and other waste management equipment;
- Sweeping of parking lots and maintenance of areas around facilities to minimize runoff of pollutants;
- Verify interior floor drains, where present, are not connected to the MS4.

DRAFT

9.2.3 Vehicles and Equipment

Vehicles and equipment owned and operated by the West Haven Campus exhibiting fluid leaks will be stored indoors or contained areas until repaired.

9.2.4 Leaf Management

Procedures to minimize or prevent leaf deposition to catch basins, streets, parking lots, driveways, sidewalks, or other paved surfaces that discharge to the MS4 will be enacted throughout the West Haven Campus.

9.2.4.1 BMP Implementation: MS4 Property Management

Permit Regulatory Reference:	Section 6(a)(6)(C)-(D)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Develop and/or implement fertilizer application optimization practices; standard operating procedures for handling, storage, and application of fertilizers, pesticides, and herbicides; and establish proper disposal practices for grass clippings to minimize the potential for these materials to enter the MS4; Identify pollutants of concern, petroleum, and non-petroleum products located on West Haven Campus facilities and develop a strategy to evaluate and address proper use, storage, and disposal; Develop and/or implement procedures for waste management equipment, including dumpsters, and plans to sweep parking lots and facility adjacent areas to minimize pollutant runoff; Implement procedures to minimize or prevent leaf deposition to surfaces or conduits that discharge to the MS4; Verify and document that interior floor drains are not connected to the MS4.

9.2.5 Implement Coordination with Interconnected MS4s

The West Haven Campus will coordinate with operators of interconnected MS4s such as the City of West Haven regarding the contribution of potential pollutants from the MS4 to that interconnected MS4.

9.2.5.1 BMP Implementation: Interconnected MS4 Coordination

Permit Regulatory Reference:	Section 6(a)(6)(F)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Identify and coordinate with operators of interconnected MS4s to identify and reduce contribution of pollutants to the MS4.

DRAFT

9.2.6 Develop/Implement Program to Control Other Sources of Pollutants to the MS4

The West Haven Campus will evaluate the need to develop and implement a program to control the contribution of pollutants to its MS4 from commercial, industrial, municipal, institutional, or other facilities not otherwise authorized by this Permit. Related actions are contingent upon identification of identification of other sources of pollutants to the West Haven Campus MS4.

9.2.6.1 BMP Implementation: Control Other Sources of Pollutants to the MS4

Permit Regulatory Reference:	Section 6(a)(6)(G)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Conduct an annual review of the list of stormwater general permit registrants and identify non-permitted locations that may be contributing pollutants based on screening and monitoring results.

9.2.7 Evaluation of Additional Measures for Discharges to Impaired Waters

The segment of the West River receiving stormwater discharges that originate from the West Haven Campus has been identified as impaired for nitrogen/phosphorus/bacteria. Additional measures to mitigate potential contributions of these impairing pollutants will be implemented at the West Haven Campus and include:

- Proper fertilizer application and planting of native plants to lessen the amount of turf area requiring fertilization and/or mowing; and
- Implementation of a Retrofit Program, as discussed in Section 8.5.

9.2.7.1 BMP Implementation: Additional Measures for Discharges to Impaired Waters

Permit Regulatory Reference:	Section 6(a)(6)(H)(i)-(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017 (fertilizer management); 7/01/2020 (retrofit program)
Measurable Goal:	Develop, fund (as available), and implement fertilizer management practices and retrofit or source management program to address the contribution of pollutants via stormwater discharge to impaired waters.

9.2.8 Tracking of Projects that Disconnect Directly Connected Impervious Area

The West Haven Campus will annually track the amount of total acreage of DCIA that is disconnected because of retrofit or redevelopment projects within the MS4. Tracking may include disconnections of DCIA within the MS4 that has occurred within the previous 5 years of this Permit effective date (i.e. 2012). The total acreage of disconnected DCIA in each year will be included in the Annual Report.

DRAFT

9.2.8.1 BMP Implementation: Tracking DCIA Projects

Permit Regulatory Reference:	Section 6(a)(6)(B)(ii)(a)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Develop and implement a procedure to annually track DCIA.

9.2.9 Develop and/or Implement an Infrastructure Repair and/or Rehabilitation Program

Sites within the West Haven Campus will be evaluated and identified for retrofit suitability using the following criteria:

- Outfall catchment areas discharging to impaired waters;
- Catchment areas with >11% DCIA.

By 2020, the West Haven Campus will report in its Annual Report on the identification and prioritization process for these locations, the selection of projects to be implemented along with selection rationale, and the total DCIA to be disconnected resultant of project implementation. The overall goal of this program will be the disconnecting of at least 1% of the DCIA during the fourth and fifth years of this Permit, or a total of 2% DCIA during the Permit term, to the maximum extent practicable.

9.2.9.1 BMP Implementation: Infrastructure Repair/Rehabilitation Program

Permit Regulatory Reference:	Section 6(a)(6)(B)(ii)(b)-(c)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Develop an infrastructure repair/rehabilitation program to be consistent with the MS4 General Permit requirements.

9.2.10 Develop/Implement a Plan to Identify/Prioritize Retrofit Projects

The West Haven Campus will review the total amount of DCIA within the MS4 and identify and prioritize suitable retrofit projects in conjunction with implementing an infrastructure repair and/or rehabilitation program, as discussed in Section 9.2.9.

9.2.10.1 BMP Implementation: Identification/Prioritization of Retrofit Projects

Permit Regulatory Reference:	Section 6(a)(6)(B)(ii)(b)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Identification and prioritization of suitable retrofit projects within the MS4.

9.2.11 Street Sweeping

All streets and parking lots located within the MS4 will be swept and/or cleaned at a minimum once per year in the spring upon completion of winter-related maintenance activities. Areas that are more likely to have an increased pollutant load due to the presence of construction activities or other potential pollutant sources will be periodically inspected and swept if necessary. Street sweepings will be properly disposed in accordance with the CT DEEP's

DRAFT

"Guidelines for Municipal Management Practices for Street Sweepings & Catch Basin Cleanings", dated August 2007 (http://www.ct.gov/deep/lib/deep/waste_management_and_disposal/solid_waste/street_sweepings.pdf).

The following information will be recorded and documented in the Annual Report:

- A summary of inspection results;
- Curb miles swept;
- Dates of cleaning;
- Volume or mass of material collected; and
- Methods of reuse or disposal.

9.2.11.1 BMP Implementation: Street Sweeping

Permit Regulatory Reference:	Section 6(a)(6)(D)(i)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Implement street sweeping and parking lot sweeping within the West Haven Campus at least once per year during the spring. Document street sweeping results, including dates of sweeping, curb miles swept, volume of material collected, and method of reuse or disposal in Annual Reports

9.2.12 Catch Basin Cleaning

Catch basins will be routinely inspected and cleaned as necessary, at a minimum of once by the end of the third year of the Permit effective date (2020). Inspection and maintenance of catch basins that discharge to impaired waterbodies and/or are located near construction activities will be prioritized. No catch basin will be more than 50% full at any given time. Procedures for catch basin inspections and cleanings will be documented in a plan, and the West Haven Campus will keep a log of catch basins cleaned or inspected throughout the duration of the Permit.

The following information will be recorded and reported in each Annual Report:

- Total number of catch basins located in the MS4
- Number of catch basins inspected;
- Number of catch basins cleaned; and
- Total volume or mass of material removed from catch basins.

Catch basin spoils will be managed in accordance with CT DEEP's "Guidelines for Municipal Management Practices for Street Sweepings & Catch Basin Cleanings", dated August 2007 (http://www.ct.gov/deep/lib/deep/waste_management_and_disposal/solid_waste/street_sweepings.pdf).

DRAFT

9.2.12.1 BMP Implementation: Catch Basin Cleaning

Permit Regulatory Reference:	Section 6(a)(6)(D)(ii)
Primary Responsible Party:	Facilities Services Management Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Update catch basin cleaning program to document current procedures, tabulate volumes for annual reporting in accordance with MS4 General Permit requirements.

9.2.13 Snow Management Procedures

Standard operating procedures (SOPs) for the use, handling, application, and disposal of deicing products such as salt and sand will be developed and/or modified to minimize exposure to stormwater. Snow and ice control practices will be evaluated and modified to minimize the discharge of sand, anti-icing, or de-icing chemicals to the MS4. Records containing the application of sand, de-icing and/or anti-icing chemicals will be maintained to document the reduction of chemicals to meet goals. Employees will be trained in deicing application, as necessary, in accordance with Permit requirements described in Section 9.1.

9.2.13.1 BMP Implementation: Snow Management Procedures

Permit Regulatory Reference:	Section 6(a)(6)(E)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2017
Measurable Goal:	Review and refine snow and ice management practices; update program as necessary to provide Annual Report documentation.

DRAFT

10. MONITORING REQUIREMENTS

Monitoring of West Haven Campus MS4 interconnections provides valuable and relevant information to assess the quality of stormwater discharges originating from the site. Where increased pollutant loading is identified, monitoring data is a valuable tool that can be used to modify existing BMPs and/or identify illicit discharges to improve the quality of stormwater leaving the site.

10.1 Inventory and Mapping of Discharges to Impaired Waters

MS4s discharging to impaired waters are required to create an inventory of all outfalls discharging to those impaired waters utilizing the information and map discussed in Section 6.2. For the West Haven Campus, stormwater is conveyed to the MS4, which is connected to the City of West Haven MS4, with the exception of one outfall located on the western portion of the site that discharges to a stream ultimately draining to the Cove River. Outfalls and interconnection locations present on the campus will be mapped in accordance with Permit requirements, along with ultimate outfall discharge locations.

10.1.1 BMP Implementation: Inventory and Mapping of Discharges to Impaired Waters

Permit Regulatory Reference:	Section 6(b)(3)(i)(1)(A)-(C)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2019

10.2 Outfall and Interconnection Screening

Outfalls and/or interconnections not discharging to impaired waters will be screened as a baseline during dry weather conditions, in accordance with illicit discharge detection and elimination (IDDE) Program requirements outlined in Appendix B of the Permit. If flow is observed during the dry weather screening, a sample will be collected and analyzed for ammonia, chlorine, conductivity, salinity, E. coli (freshwater) or enterococcus (brackish/saline water), surfactants, and temperature, and the pollutant causing any impairment to a waterbody at the point of discharge from that outfall/interconnection. Depending on observed flow conditions and/or detected concentrations, wet weather screening and sampling may be required.

Based on an assessment of impaired waters receiving outfall discharge that may originate from the campus, the West Haven Campus will also screen outfalls/interconnections in accordance the Permit required procedure for that impairment, as summarized in the table below. Samples will be collected from each interconnection at least once during the Permit cycle during a precipitation event that results in a discharge from that interconnection.

Impairment	Criteria for Follow-Up Investigation
Nitrogen	Total Nitrogen > 2.5 mg/L
Phosphorus	Total Phosphorus > 0.3 mg/L
Bacteria (Fecal coliform)	Fecal coliform > 31 col/100 mL
Bacteria (Enterococci)	Enterococci > 104 col/100 mL for swimming areas; > 500 col/100 mL for all others

DRAFT

10.2.1 BMP Implementation: Outfall/Interconnection Screening

Permit Regulatory Reference:	Section 6(b)(3)(i)(1)(A)-(C)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2019
Measurable Goal:	Establishment of screening procedures consistent with Monitoring Requirements for Pollutants of Concern. Initiate screening within two years of the MS4 General Permit effective date; complete screening of at least 50% of the outfalls/interconnections by 2021. Complete all outfall/interconnection screenings by 2022.

10.3 Follow-Up Investigations of Drainage Areas

If interconnection screening results indicate concentrations of pollutants above the criteria for follow-up investigation, as presented in Section 10.2, a follow-up investigation will be conducted to determine potential contributions resulting in an impairment. Investigations may include, but are not limited to, land use or development patterns, DCIA, natural contributors, and potential MS4 maintenance issues.

10.3.1 BMP Implementation: Follow-Up Investigations of Drainage Areas

Permit Regulatory Reference:	Section 6(b)(3)(i)(1)(D)(i)-(ii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2020
Measurable Goal:	Evaluate interconnections to determine potential contribution to identified impairments. Performance of catchment investigations, implementation of BMPs related to the pollutant concern, and use of collected information to prioritize interconnections for further monitoring.

10.4 Annual Monitoring of Priority Interconnections

Upon screening of at least half of the interconnections at the West Haven Campus, the VA will use the screening results to select six of the highest contributors of any of the pollutants of concern. These six interconnections will be sampled annually for the appropriate pollutant of concern in accordance with the schedule provided below. If fewer than six interconnections were identified for follow-up investigation, all the interconnections will be monitored, not to exceed six interconnections.

10.4.1 BMP Implementation: Annual Monitoring of Priority Interconnections

Permit Regulatory Reference:	Section 6(b)(3)(i)(D)(iii)
Primary Responsible Party:	Facilities Management Services Chief, West Haven Campus
Implementation Deadline:	7/01/2022
Measurable Goal:	Identify the six largest contributors of pollutants of concern and implement annual monitoring of these interconnections. Revise the list as new information becomes available that may affect the ranking of the largest six contributors.

DRAFT

11. ADDITIONAL INFORMATION

The West Haven Campus, in accordance with the Permit, may use the efforts of a third party (qualifying State or Federal Program) performed under another NPDES stormwater permit to fulfill the requirements of each of the MCMs described in the preceding sections. If the third party fails to implement the required regulatory actions, the West Haven Campus will remain responsible for that MCM implementation.

11.1 Qualifying State or Federal Program

Under Section 6(b)(2) of the Permit, a Qualifying State or Federal Program can be used if a BMP is performed by a third party under another NPDES stormwater permit. If this is the case, the third party's program must be referenced within this SMP. As of the issuance of this SMP, no Qualifying State or Federal Program has been identified where a BMP is performed by a third party under another NPDES stormwater permit.

11.2 Coordination of Permit Responsibilities

In the absence of the identification of a Qualifying State or Federal Program, the West Haven Campus will be responsible for compliance and implementation of Permit conditions. This section may be modified if new information is identified that affects the coordination of Permit responsibilities.

11.3 Retention of Records

The West Haven Campus will keep records required by the Permit for a period of at least 5 years following the Permit expiration, or longer if requested by the CT DEEP. This SMP and related records must be readily available to the public upon request during regular business hours.

11.4 Reporting Requirements

The West Haven is required to submit an Annual Report by April 1st of the second Permit year (2018), and April 1st annually thereafter, for the duration of the Permit. The Annual Report submittal must include the following:

- A plan review fee of $375.00;
- The status of compliance with the Permit;
- An assessment of the appropriateness of the BMPs identified in this SMP;
- Progress toward achieving implementation dates and measurable goals for each MCM, including implementation scheduled for the year that was not completed as scheduled;
- All stormwater monitoring data;
- All illicit discharge detection information obtained during the previous year;
- A summary of the activities the West Haven Campus plans to undertake during the next year; and
- A change in any identified BMPs, measurable goals, or implementation dates that apply to the program elements.

DRAFT

12. PERMITTEE CERTIFICATION

I hereby certify that I am making this certification in connection with a registration under the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems, submitted to the Commissioner by The United States Department of Veterans Affairs for an activity located at or within the United States Department of Veterans Affairs West Haven Medical Campus located at 950 Campbell Avenue in West Haven, Connecticut and that all terms and conditions of the general permit are being met for all discharges which have been created, initiated or maintained and such activity is eligible for authorization under such permit. I further certify that a system is in place to ensure that all terms and conditions of this general permit will continue to be met for all discharges authorized by this general permit at the site. I certify that I have personally examined and am familiar with the information that provides the basis for this certification, including but not limited to all information described in Section 3(b)(8)(A) of such general permit, and I certify, based on reasonable investigation, including my inquiry of those individual s responsible for obtaining such information, that the information upon which this certification is based is true, accurate and complete to the best of my knowledge and belief. I certify that I have made an affirmative determination in accordance with Section 3 (b)(8)(B) of this general permit. I understand that the registration filed in connection with such general permit is submitted in accordance with and shall comply with the requirements of Section 22a-430b of Connecticut General Statutes, as amended by Public Act 12-172. I also understand that knowingly making any false statement made in the submitted information and in this certification may be punishable as a criminal offense, including the possibility of fine and imprisonment, under section 53a-157b of the Connecticut General Statutes and any other applicable law.

_____ _____

Alexander M. Moore, Facilities Management Services Chief Date

DRAFT

13. QUALIFIED PROFESSIONAL ENGINEER CERTIFICATION

I hereby certify that I am a qualified professional engineer, as defined in the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems. I am making this certification in connection with a registration under such general permit, submitted to the Commissioner by the United States Department of Veterans Affairs for an activity located at or within the West Haven Medical Campus located at 950 Campbell Avenue in West Haven, Connecticut. I have personally examined and am familiar with the information that provides the basis for this certification, including but not limited to all information described in Section 3(b)(9)(A) of such general permit, and I certify, based on reasonable investigation, including my inquiry of those individuals responsible for obtaining such information, that the information upon which this certification is based is true, accurate and complete to the best of my knowledge and belief. I certify based on my review of all information described in Section 3(b)(9)(B) of such general permit and on the standard of care for such projects, that I have made an affirmative determination in accordance with Section 3(b)(9)(B) of this general permit. I understand that this certification is part of a registration submitted in accordance with Section 22a-430b of Connecticut General Statutes and is subject to the requirements and responsibilities for a qualified professional in such statute. I also understand that knowingly making any false statement in this certification may be punishable as a criminal offense, including possibility of fine and imprisonment, under section 53a-157b of the Connecticut General Statutes and any other applicable law.

_____ _____

Jeffrey Stearns, P.E. Date

DRAFT

APPENDIX A: CT DEEP MS4 GENERAL PERMIT

DRAFT

Connecticut Department of
Energy & Environmental Protection
Bureau of Materials Management & Compliance Assurance
Water Permitting & Enforcement Division



General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems

Issued: January 20, 2016

Effective: July 1, 2017

Expires: June 30, 2022

General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems

Table of Contents

Section 1. Authority **4**

Section 2. Definitions **4**

Section 3. Authorization Under This General Permit **8**

- ***(a) Eligible Activities*** **8**
- ***(b) Requirements for Authorization*** **8**
- ***(c) Registration*** **12**
- ***(d) Geographic Area*** **12**
- ***(e) Effective Date and Expiration Date of this General Permit*** **12**
- ***(f) Effective Date of Authorization*** **12**

Section 4. Registration Requirements **12**

- ***(a) Who Must File a Registration*** **12**
- ***(b) Scope of Registration*** **12**
- ***(c) Contents of Registration*** **13**
- ***(d) Availability of Registrations, Stormwater Management Plan, and Annual Reports*** **15**
- ***(e) Where to File a Registration*** **16**
- ***(f) Additional Information*** **16**
- ***(g) Additional Notification*** **16**
- ***(h) Action by Commissioner*** **17**

Section 5. Requirements of this General Permit **17**

- ***(a) Conditions Applicable for Certain Discharges*** **17**
- ***(b) Stormwater Management Plan*** **18**

Section 6. Development of Stormwater Management Plan (Plan) **18**

- ***(a) Minimum Control Measures*** **19**
- ***(b) Sharing Responsibility*** **39**
- ***(c) Proper Operation and Maintenance*** **40**
- ***(d) Signature Requirements*** **40**
- ***(e) Plan Review Fee*** **40**
- ***(f) Keeping Plans Current*** **40**
- ***(g) Failure to Prepare or Amend Plan*** **41**
- ***(h) Plan Review Certification*** **41**
- ***(i) Monitoring Requirements*** **41**
- ***(j) Reporting & Record Keeping Requirements*** **45**

(k) Discharges to Impaired Waters or Water bodies subject to a Pollutant Load Reduction within a TMDL 47

Section 7. Additional Requirements of this General Permit 48

(a) Regulations of Connecticut State Agencies Incorporated into this General Permit 48
(b) Reliance on Registration 48
(c) Duty to Correct and Report Violations 48
(d) Duty to Provide Information 49
(e) Certification of Documents 49
(f) Date of Filing 49
(g) False Statements 49
(h) Correction of Inaccuracies 49
(i) Other Applicable Law 50
(j) Other Rights 50

Section 8. Commissioner's Powers 50

(a) Abatement of Violations 50
(b) General Permit Revocation, Suspension, or Modification 50
(c) Filing of an Individual Application 50

Appendix A Small MS4 Municipalities

Appendix B Illicit Discharge Detection and Elimination (IDDE) Program Protocol

Appendix C Aquifer Protection Areas and Other Groundwater Drinking Supply Areas Guidance

Appendix D Impaired Waters Guidance

Section 1. Authority

This general permit is issued under the authority of Section 22a-430b of the Connecticut General Statutes.

Section 2. Definitions

The definitions of terms used in this general permit shall be the same as the definitions contained in Sections 22a-423 of the Connecticut General Statutes and Section 22a-430-3(a) of the Regulations of Connecticut State Agencies. As used in this general permit, the following definitions shall apply:

"x-year, 24-hour rainfall event" means the maximum 24-hour precipitation event with a probable recurrence interval of once in the given number of years (i.e. x=2, 25 or 100), as defined by the National Weather Service in Technical Paper Number 40, "Rainfall Frequency Atlas of the United States," May 1961, and subsequent amendments, or equivalent regional or state rainfall probability information developed therefrom.

"Aquifer protection area" means aquifer protection area as defined in section 22a-354h of the Connecticut General Statutes.

"Best engineering practices" means the design of engineered control measures to control pollution to the maximum extent achievable using measures that are technologically available and economically practicable.

"Best Management Practices (*BMP*)" means schedules of activities, practices (and prohibitions of practices), structures, vegetation, maintenance procedures, and other management practices to prevent or reduce the discharge of pollutants to waters of the state consistent with state, federal or other equivalent and technically supported guidance. BMPs also include treatment requirements, operating procedures, and practices to control site runoff, spillage or leaks, sludge or waste disposal, or drainage from material storage.

"Catchment area" means the land area from which stormwater runoff is collected by a permittee's MS4 and discharges through a single outfall to surface water.

"Coastal Jurisdiction Line" means the location of the topographical elevation of the highest predicted tide as defined in Section 22a-359(c) of the Connecticut General Statutes.

"Coastal waters" means coastal waters as defined in Section 22a-93(5) of the Connecticut General Statutes.

"Commissioner" means Commissioner as defined in section 22a-423 of the Connecticut General Statutes.

"Control Measures" means any BMPs or other methods (including effluent limitations) used to prevent or reduce the discharge of pollutants to waters of the state.

"Department" means the Department of Energy & Environmental Protection.

"Directly Connected Impervious Area (DCIA)" means that impervious area from which stormwater runoff discharges *directly* to waters of the state or *directly* to a storm sewer system that discharges to waters of the state. Impervious areas that discharge through a system designed to retain the

appropriate portion of the Water Quality Volume (pursuant to Section 6(a)(5)(b)(i) or (ii) of this general permit) are not considered DCIA.

"Fresh-tidal wetland" means a tidal wetland located outside of coastal waters.

"Grab sample" means an individual sample collected in less than fifteen minutes.

"Guidelines" means the 2002 Connecticut Guidelines for Soil Erosion and Sediment Control, as amended, established pursuant to Section 22a-328 of the Connecticut General Statutes.

"High Quality Waters" means those waters defined as high quality waters in the Connecticut Water Quality Standards pursuant to Section 22a-426-1(36) of the Regulations of Connecticut State Agencies.

"Illicit Discharge" means any unpermitted discharge to waters of the state that does not consist entirely of stormwater or uncontaminated ground water except those discharges identified in Section 3(*a*)(2) of this general permit when such non-stormwater discharges are not significant contributors of pollution to a discharge from an identified MS4.

"Impaired water(s)" means those surface waters of the state designated by the Commissioner as impaired pursuant to Section 303(d) of the federal Clean Water Act and as identified in the most recent State of Connecticut Integrated Water Quality Report within Categories 4 or 5, including any subdivisions of these categories.

"Individual permit" means a permit issued to a named permittee under Section 22a-430 of the Connecticut General Statutes.

"Inland wetland" means wetlands as that term is defined in Section 22a-38 of the Connecticut General Statutes.

"Low Impact Development" or *"LID"* means a site design strategy that maintains, mimics or replicates pre-development hydrology through the use of numerous site design principles and small-scale treatment practices distributed throughout a site to manage runoff volume and water quality at the source.

"Minimize", for purposes of implementing the minimum control measures in Section 6 of this general permit, means to reduce and/or eliminate to the Maximum Extent Practicable (MEP) as described in Section 5(*b*).

"Municipal separate storm sewer system" or *"MS4"* means conveyances for stormwater (including roads with drainage systems, streets, catch basins, curbs, gutters, ditches, man-made channels or storm drains) owned or operated by any municipality or by any state or federal institution and discharging to surface waters of the state.

"Municipality" means a city, town or borough of the state as defined in section 22a-423 of the Connecticut General Statutes.

"New or Increased Discharge" means new discharge or activity as defined in section 22a-426-8(b)(3) and increased discharge or activity as defined in section 22a-426-8(b)(2), as referenced to the Regulations of Connecticut State Agencies.

"Permittee" means any municipality or any state or federal institution that initiates, creates, originates or maintains a discharge authorized by this general permit and that has filed a registration pursuant to Section 4 of this permit.

"Point Source" means any discernible, confined and discrete conveyance, including but not limited to, any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, landfill leachate collection system, vessel or other floating craft from which pollutants are or may be discharged.

"Qualified professional engineer" means a professional engineer who: (1) has, for a minimum of eight (8) years, engaged in the planning and designing of engineered stormwater management systems for (i) municipal separate storm sewer systems and (ii) residential and commercial construction projects in accordance with the Guidelines and the Stormwater Quality Manual including, but not limited to, a minimum of four (4) years in responsible charge of the planning and designing of engineered stormwater management systems for such projects; or (2) is currently certified as a Professional in MS4 Stormwater Compliance as designated by EnviroCert International, Incorporated, or other certifying organization acceptable to the Commissioner, and for a minimum of six (6) years, has engaged in the planning and designing of engineered stormwater management systems for (i) municipal separate storm sewer systems and (ii) residential and commercial construction projects in accordance with the Guidelines and the Stormwater Quality Manual including, but not limited to, a minimum of two (2) years in responsible charge of the planning and designing of engineered stormwater management systems for such projects; or (3) currently provides engineering services for the Permittee by employ (e.g. Town Engineer) or by contract.

"Registrant" means a municipality or institution which files a registration pursuant to Section 4 of this general permit.

"Redevelopment" means any construction activity (including, but not limited to, clearing and grubbing, grading, excavation, and dewatering) within existing drainage infrastructure or at an existing site to modify or expand or add onto existing buildings or structures, grounds, or infrastructure.

"Registration" means a registration form filed with the Commissioner pursuant to Section 4 of this general permit.

"Retain" means to hold runoff on-site to promote vegetative uptake and groundwater recharge through the use of runoff reduction or LID practices or other measures. In addition, it means there shall be no subsequent point source release to surface waters from a storm event defined in this general permit or as approved by the Commissioner.

"Runoff reduction practices" means those post-construction stormwater management practices used to reduce post-development runoff volume delivered to the receiving water, as defined by retaining the volume of runoff from a storm up to the first half inch or one inch of rainfall in accordance with Sections 6(*a*)(5)(B)(i) or (ii), respectively. Runoff reduction is quantified as the total annual post-development runoff volume reduced through canopy interception, soil amendments, evaporation, rainfall harvesting, engineered infiltration, extended filtration or evapotranspiration.

"Sanitary Sewer Overflow" or *"SSO"* means a discharge of untreated sanitary wastewater from a municipal sanitary sewer.

"Small MS4" means any municipally-owned or -operated MS4 (as defined above) including all those located partially or entirely within an Urbanized Area that have at least 1,000 residents in the Urbanized Area (as determined by the 2000 or 2010 census) and all state- and federally-operated MS4s (except DOT) and any other MS4s located outside an Urbanized Area as may be designated by the Commissioner. (Note: A list of Small MS4 municipalities is included in Appendix A of this general permit. DOT will be authorized under a separate permit.)

"Standard of care", as used in Section 3(*b*)(9), means to endeavor to perform in a manner consistent with that degree of care and skill ordinarily exercised by members of the same profession currently practicing under similar circumstances.

"State or Federal Institution" or "*institution"* means any facility (including, but not limited to, state and federal prisons, office complexes, hospitals; university campuses, public housing authorities, schools, or other special districts) consisting of more than one building that is owned by an agency or department of the State of Connecticut (except the Department of Transportation) or a federal agency and has an average daily population of 1,000 people or more.

"Stormwater" means waters consisting of rainfall runoff, including snow or ice melt during a rain event.

"Stormwater Quality Manual" means the Connecticut Stormwater Quality Manual published by the Connecticut Department of Energy & Environmental Protection in 2004, as amended and maintained at http://www.ct.gov/deep/stormwaterqualitymanual.

"Surface water" means those waters as defined in Section 22a-426-1(60) of the Regulations of Connecticut State Agencies.

"Tidal wetland" means a wetland as that term is defined in Section 22a-29(2) of the Connecticut General Statutes.

"Total Maximum Daily Load (*TMDL*)" means a water quality implementation plan established pursuant to Section 303 of the federal Clean Water Act.

"Urbanized Area (*UA*)" means the areas of the State of Connecticut so defined by the U.S. Census Bureau for the 2000 or 2010 census.

"Water Quality Standards or Classifications" means those water quality standards or classifications contained in Sections 22a-426 -1 through 22a-426-9, inclusive, of the Regulations of Connecticut State Agencies and the Classification Maps adopted pursuant to Section 22a-426 of the Connecticut General Statutes, which together constitute the Connecticut Water Quality Standards., as may be amended.

"Water Quality Volume" or *"WQV"* means the volume of runoff generated by one inch of rainfall on a site as defined in the Connecticut Stormwater Quality Manual.

Section 3. Authorization Under This General Permit

(a) Eligible Activities

(1) This general permit authorizes the discharge of stormwater from or associated with a Small MS4, provided the requirements of subsection (*b*) of this section are satisfied and the activity is conducted in accordance with the conditions listed in Section 5 of this general permit to the Maximum Extent Practicable (as defined in Section 5(b)).

(2) This permit authorizes the following non-stormwater discharges provided: the permittee controls such non-stormwater discharges to the Maximum Extent Practicable (MEP), as required by this general permit; such non-stormwater discharges do not contribute to a violation of water quality standards; and such non-stormwater discharges are documented in the Stormwater Management Plan and are not significant contributors of pollutants to any identified MS4:

- uncontaminated ground water discharges including, but not limited to, pumped ground water, foundation drains, water from crawl space pumps and footing drains;
- irrigation water including, but not limited to, landscape irrigation and lawn watering runoff;
- residual street wash water associated with sweeping;
- discharges or flows from firefighting activities (except training); and
- naturally occurring discharges such as rising ground waters, uncontaminated ground water infiltration (as defined at 40 CFR 35.2005(20)), springs, diverted stream flows and flows from riparian habitats and wetlands.

(3) Any non-stormwater discharge to the MS4 authorized by a permit issued pursuant to Section 22a-430 or 22a-430b of the Connecticut General Statutes is also authorized under this general permit.

(b) Requirements for Authorization

This general permit authorizes the activity listed in the "Eligible Activities" section (Section 3(*a*)) of this general permit provided:

(1) Coastal Management Act

Such activity is consistent with all applicable goals and policies in Section 22a-92 of the Connecticut General Statutes, and must not cause adverse impacts to coastal resources as defined in Section 22a-93(15) of the Connecticut General Statutes.

(2) Endangered and Threatened Species

Implementation of the permittee's Stormwater Management Plan shall not threaten the continued existence of any species listed pursuant to section 26-306 of the Connecticut General Statutes as endangered or threatened and must not result in the destruction or adverse modification of habitat designated as essential to such species unless otherwise exempted by Federal statute.

(3) Aquifer Protection Areas

Such activity, if it is located within an aquifer protection area as mapped under section 22a-354b of the Connecticut General Statutes, must comply with regulations adopted pursuant to section 22a-354i of the Connecticut General Statutes.

(4) Discharge to POTW

The stormwater is *not* discharged to a Publicly Owned Treatment Works (POTW).

(5) Discharge to Groundwater

The stormwater is *not* discharged entirely to groundwater, meaning a stormwater discharge to a surface water will not occur up to a 100-year, 24-hour rainfall event.

(6) New or Increased Discharges to High Quality Waters

On or before thirty (30) days prior to the commencement of a new or increased discharge to a High Quality Waters from its MS4, the permittee must document compliance with the Connecticut Anti-Degradation Implementation Policy in the Water Quality Standards, as amended. Before commencing any new or increased discharge, the permittee shall identify in its Stormwater Management Plan ("Plan"), the control measures it will implement to ensure compliance with anti-degradation provisions and the terms of this Permit. At a minimum, the permittee shall evaluate and implement to the Maximum Extent Practicable practices which will prevent the discharge of the Water Quality Volume to a surface water body or other practices necessary to protect and maintain designated uses and meet standards and criteria contained in the Water Quality Standards.

(7) New or Increased Discharges to Impaired Waters

There shall be no increased discharges from the MS4 to impaired waters listed in categories 5 or 4b of the most recent Connecticut Integrated Water Quality Report of waters listed pursuant to Clean Water Act section 303(d) and 305(b) unless the permittee demonstrates that there is no net increase in loading by the MS4 to the impaired water of the pollutant(s) for which the waterbody is impaired. The permittee may demonstrate no net increase by either:

(A) Documenting that the pollutant(s) for which the waterbody is impaired is not present in the MS4's discharge and retain documentation of this finding with the Plan; or

(B) Documenting that the total load of the pollutant(s) of concern from the MS4 to any impaired portion of the receiving water will not increase as a result of the activity and retain documentation of this finding in the Plan. Compliance with the requirements for Runoff Reduction and Low Impact Development measures for new development and redevelopment in Sections 6(a)(5)(A) and (B) shall be considered as demonstrating no net increase. Requirements for discharges to impaired waters are included in Section 6(k) of this general permit.

(8) Certification Requirements for Registrants and other Individuals

As part of the registration for this general permit, the registrant and any other individual or individuals principally responsible for preparing the registration submits to the Commissioner a written certification which, at a minimum, complies with the following requirements:

(A) The registrant and any other individual or individuals responsible for preparing the registration and signing the certification has completely and thoroughly reviewed, at a minimum, this general permit and the following regarding the activities to be authorized under such general permit: (i) all registration information provided in accordance with Section 4(*c*)(2) of such general permit, (ii) the Stormwater Management Plan, and (iii) any plans and specifications and any Department approvals regarding such Stormwater Management Plan;

(B) The registrant and any other individual or individuals responsible for preparing the registration and signing the certification pursuant to this general permit has, based on the review described in section 3(*b*)(8)(A) of this general permit, made an affirmative determination to: (i) comply with the terms and conditions of this general permit; (ii) maintain compliance with all plans and documents prepared pursuant to this general permit including, but not limited to, the Stormwater Management Plan; (iii) properly implement and maintain the elements of the Stormwater Management Plan; and (iv) properly operate and maintain all stormwater management measures and systems in compliance with the terms and conditions of this general permit to protect the waters of the state from pollution;

(C) Such registrant and any other individual or individuals responsible for preparing the registration certifies to the following statement:

"I hereby certify that I am making this certification in connection with a registration under the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems, submitted to the Commissioner by [INSERT NAME OF REGISTRANT] for an activity located at or within [NAME OF MUNICIPALITY OR ADDRESS OF THE REGISTERED ACTIVITY] and that all terms and conditions of the general permit are being met for all discharges which have been created, initiated or maintained and such activity is eligible for authorization under such permit. I further certify that a system is in place to ensure that all terms and conditions of this general permit will continue to be met for all discharges authorized by this general permit at the site. I certify that I have personally examined and am familiar with the information that provides the basis for this certification, including but not limited to all information described in Section 3(*b*)(8)(A) of such general permit, and I certify, based on reasonable investigation, including my inquiry of those individuals responsible for obtaining such information, that the information upon which this certification is based is true, accurate and complete to the best of my knowledge and belief. I certify that I have made an affirmative determination in accordance with Section 3(*b*)(8)(B) of this general permit. I understand that the registration filed in connection with such general permit is submitted in accordance with and shall comply with the requirements of Section 22a-430b of Connecticut General Statutes, as amended by Public Act 12-172. I also understand that knowingly making any false statement made in the submitted information and in this certification may be punishable as a criminal offense, including

the possibility of fine and imprisonment, under section 53a-157b of the Connecticut General Statutes and any other applicable law."

(9) Stormwater Management Plan Certification

As part of the registration for this general permit, the registrant submits to the Commissioner a written certification by a qualified professional engineer who has reviewed the Stormwater Management Plan (Plan) in accordance with the following requirements:

(A) The qualified professional engineer has, at a minimum, completely and thoroughly reviewed this general permit and the following regarding the discharges to be authorized under such general permit: (i) all registration information provided in accordance with Section 4(*c*)(2) of such general permit, (ii) the Stormwater Management Plan, and (iii) all non-engineered and engineered stormwater management measures and systems, including any plans and specifications and any Department approvals regarding such stormwater management measures and systems.

(B) Affirmative Determination

A qualified professional engineer signing the certification must have made an affirmative determination, based on the review described in section 3(*b*)(9)(A) of this general permit and on best engineering practices, that the Plan and control measures therein are adequate to assure that the activity authorized under this general permit will comply with the terms and conditions of such general permit and all non-engineered and engineered stormwater management measures and systems: (i) have been designed in accordance with best engineering practices; (ii) will function properly as designed; (iii) are adequate to ensure compliance with the terms and conditions of this general permit; and (iv) will protect the waters of the state from pollution.

(C) The qualified professional engineer, as specified in section 3(*b*)(9)(A), above, shall certify to the following statement:

"I hereby certify that I am a qualified professional engineer, as defined in the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems. I am making this certification in connection with a registration under such general permit, submitted to the Commissioner by [INSERT NAME OF REGISTRANT] for an activity located at or within [NAME OF MUNICIPALITY OR ADDRESS OF THE REGISTERED ACTIVITY]. I have personally examined and am familiar with the information that provides the basis for this certification, including but not limited to all information described in Section 3(*b*)(9)(A) of such general permit, and I certify, based on reasonable investigation, including my inquiry of those individuals responsible for obtaining such information, that the information upon which this certification is based is true, accurate and complete to the best of my knowledge and belief. I certify, based on my review of all information described in Section 3(*b*)(9)(A) of such general permit and on the standard of care for such projects, that I have made an affirmative determination in accordance with Section 3(*b*)(9)(B) of this general permit. I understand that this certification is part of a registration submitted in accordance with Section 22a-430b of Connecticut General Statutes and is subject to the requirements and responsibilities for a qualified professional in such statute. I also understand that knowingly making any false statement in this certification may be punishable as a criminal offense, including the possibility of fine and imprisonment,

under section 53a-157b of the Connecticut General Statutes and any other applicable law."

(D) Nothing in this subsection shall be construed to authorize or require a qualified professional engineer to engage in any profession or occupation requiring a license under any other provision of the Connecticut General Statutes without such license.

(c) Registration

Pursuant to the "Registration Requirements" section (Section 4) of this permit, a Small MS4 shall submit a Registration Form (accessible from the DEEP website) to the Commissioner at least ninety (90) days prior to the effective date of this general permit. The form will guide the registrant to submit the appropriate information.

Include any additional forms and information regarding compliance and/or consistency with the Coastal Management Act, High Quality Waters, Impaired Waters (including TMDL requirements), Endangered and Threatened Species, and Aquifer Protection Areas that may be required pursuant to the "Requirements of Authorization" section (Section 3(*b*)).

(d) Geographic Area

This general permit applies throughout the State of Connecticut.

(e) Effective Date and Expiration Date of this General Permit

This general permit is effective July 1, 2017 and expires on June 30, 2022.

(f) Effective Date of Authorization

An activity is authorized by this general permit: on the date the general permit becomes effective; on the date a complete registration meeting the requirements of Section 4(*c*) is submitted; for registrants that did not register as required by Section 3(*c*), on the date the authorized activity is initiated; or on another date approved by the Commissioner, whichever is latest.

Section 4. Registration Requirements

(a) Who Must File a Registration

Any municipality or state or federal institution that initiates, creates, originates or maintains a discharge of stormwater from or associated with a Small MS4 shall file with the Commissioner a registration form that meets the requirements of this section of this general permit. Such form shall be submitted along with the applicable fee within the timeframes and in the amounts specified in Sections 3(*c*) and 4(*c*)(1)(A), respectively.

(b) Scope of Registration

A registrant must register on one registration form by the date indicated in Section 3(*c*) for all discharges that are operated by the registering municipality or institution. A registrant may not submit more than one registration under this general permit.

(c) Contents of Registration

(1) Fees

(A) The registration fee for a Small MS4 shall be $625 to be submitted with the registration form.

(B) The fees for municipalities shall be half of those indicated in subsection (A) above pursuant to section 22a-6(b) of the Connecticut General Statutes. State and Federal agencies shall pay the full fees specified in this subsection.

(C) The registration fee shall be paid electronically or by check or money order payable to the **Department of Energy & Environmental Protection**.

(D) No activity shall be authorized by this general permit until the registration fee has been paid in full.

(E) The registration fee is non-refundable.

(2) Registration Form

The registration shall be filed in a form prescribed and provided by the Commissioner (available on the DEEP website) and shall include the following:

(A) Name of the permittee and the name, title, address, telephone number, permit number (for existing 2004 MS4 permittees) and email address of the chief elected official or principal executive officer.

(B) Name, address, telephone number, and email address of the primary contact person for the permittee.

(C) Name, primary contact, address, telephone number, and email address of any consultant(s) or engineer(s) retained by the permittee to prepare the registration,

(D) Name of receiving stream(s), watershed(s) or waterbody(s) (including waterbody ID number which can be identified at *www.**cteco**.uconn.edu*) to which the MS4 discharges and indication of whether or not a receiving stream is listed as an impaired water, with or without a TMDL, and including identification of the impairment in the most recent State of Connecticut Integrated Water Quality Report or identification of the receiving stream as a high quality water by the Commissioner as defined in the Connecticut Water Quality Standards.

(E) An electronic map or a paper copy of the relevant portion or a full-sized original of a United States Geological Survey (USGS) quadrangle map with a scale of 1:24,000, showing the permittee's boundaries and limits of its separate storm sewer system. If a paper copy of a map is submitted, identify the quadrangle name on the map and be sure to include the name of the permittee.

(F) Assurance that the Stormwater Management Plan for the MS4 is consistent with the following provisions of state statutes and regulations, as appropriate:

(i) For sites within the Coastal Boundary, the permittee must address all applicable goals and policies in Section 22a-92 of the Connecticut General Statutes, and must not cause adverse impacts to coastal resources as defined in Section 22a-93(15) of the Connecticut General Statutes.

(ii) The permittee's Stormwater Management Plan will not threaten the continued existence of any species listed pursuant to section 26-306 of the Connecticut General Statutes as endangered or threatened and will not result in the destruction or adverse modification of habitat designated as essential to such species.

(iii) The implementation of the permittee's Stormwater Management Plan for any part of the MS4 located within an aquifer protection area (see Appendix C) as mapped under section 22a-354b of the Connecticut General Statutes will comply with regulations adopted pursuant to section 22a-354i of the Connecticut General Statutes. For any activity regulated pursuant to sections 8(c) and 9(b) of the Aquifer Protection Regulations (section 22a-354i(1)-(10) of the Regulations of Connecticut State Agencies), the Stormwater Management Plan must assure that stormwater run-off generated from the MS4 is managed in a manner so as to prevent pollution of groundwater.

(iv) The Stormwater Management Plan has been reviewed for consistency with state Historic Preservation statutes, regulations, and policies including identification of any potential impacts on property listed or eligible for listing on the Connecticut Register of Historic Places. A review conducted for an Army Corps of Engineers Section 404 wetland permit would meet this qualification.

(v) The Stormwater Management Plan appropriately addresses new or increased discharges to high quality waters, as specified in Section 3(*b*)(6).

(vi) The Stormwater Management Plan appropriately addresses new or increased discharges to impaired waters, as specified in Section 3(*b*)(7).

(G) For each of the Minimum Control Measures in Section 6(*a*), the following information shall be included:

(i) each Best Management Practice (BMP) to be implemented;

(ii) the person(s) responsible for implementing and maintaining each BMP;

(iii) the date by which each BMP will be implemented;

(iv) the measurable goal(s) by which each BMP will be evaluated.

(H) Provide an internet address (URL) where the Stormwater Management Plan required by Section 5(*b*) and the Annual Reports required by Section 6(*j*) are accessible for public review. Also provide a physical address where a paper copy of the Plan and Annual Reports are available for inspection. If the registrant claims that certain elements of their Plan constitute secure information (pursuant to Section 4(*d*)(2)) or are otherwise exempt from the disclosure requirements of the state Freedom of Information Act (section 1-210 et seq of the Connecticut General Statutes, also called FOIA) as specified in that Act, the registrant shall follow the procedures provided in the

registration form instructions for this general permit regarding information subject to FOIA requirements. The process of complying with the FOIA requirements does not exempt the registrant from the registration and Plan preparation deadlines of this general permit.

(I) The certification of the registrant and of the individual or individuals responsible for actually preparing the registration, in accordance with Section 3(*b*)(8).

(J) Certification (pursuant to the requirements and conditions of Section 3(*b*)(9)) that the Stormwater Management Plan has been reviewed by a qualified professional engineer (as defined in Section 2) licensed in the State of Connecticut.

(d) Availability of Registrations, Stormwater Management Plans and Annual Reports

(1) Registration Availability

Within thirty (30) days of receipt of a registration, the Commissioner shall post on the DEEP website a list of registrations submitted and identify the location where the Stormwater Management Plan is available.

On or before sixty (60) days from the date of posting of a registration by the Commissioner, members of the public may review the registration and submit written comments to the Commissioner.

(2) Stormwater Management Plan Availability

A permittee shall make its Stormwater Management Plan (Plan) available, electronically and at a publicly available location, for public review and comment at least ninety (90) days prior to the effective date of this general permit. The permittee shall also provide the internet address (URL) where the Plan may be located or an electronic copy to the Commissioner. Within thirty (30) days of receipt of a Stormwater Management Plan (or its URL), the Commissioner shall post on the DEEP website a list of Plans submitted and identify the location where the Plan will be available for review. In addition to the internet address (URL) required as part of the registration (pursuant to Section 4(*c*)(2)(H)), reasonable efforts to inform the public of this document shall be undertaken by the permittee. The Plan shall be made available at the permittee's main office or other designated municipal or institution office, a local library or other publicly available location for public inspection and copying consistent with the federal and state Freedom of Information Acts. On or before sixty (60) days from the date of the availability of the Plan, members of the public may review the Plan and submit written comments on it to the Commissioner.

If the registrant claims that certain elements of their Plan constitute secure information subject to restrictions related to Homeland Security or other security issues otherwise exempt from the disclosure requirements of the state Freedom of Information Act (section 1-210 et seq of the Connecticut General Statutes, also called FOIA) as specified in that Act, they shall follow the procedures provided in the registration form instructions for this general permit regarding information subject to FOIA requirements. The process of complying with the FOIA requirements does not exempt the registrant from the registration and Plan preparation deadlines in this general permit.

Following the comment period specified above, the final Plan shall remain available for public inspection on-line and a paper copy made available at the location specified above during regular business hours.

(3) Annual Report Availability

At least forty five (45) days prior to submission of each Annual Report to the Department, pursuant to Section 6(*j*), each permittee shall make available for public review and comment a draft copy of the complete Annual Report. Comments on the Annual Report may be made to the permittee and are *not* submitted to the Department. Reasonable efforts to inform the public of this document shall be undertaken by the permittee. Such draft copies shall be made available electronically on the permittee's website for public inspection and copying consistent with the federal and state Freedom of Information Acts and at at least one of the following locations: the permittee's main office or other designated municipal or institution office, a local library or other central publicly available location. Following submission of the Annual Report (pursuant to Section 6(*j*)), a copy of the final report shall be made available for public inspection during regular business hours.

(e) Where to File a Registration

A registration shall be filed with the Commissioner on forms available through the DEEP website.

(f) Additional Information

The Commissioner may require a registrant to submit additional information, which the Commissioner reasonably deems necessary to evaluate the consistency of the subject activity with the requirements for authorization under this general permit.

(g) Additional Notification

For discharges authorized by this general permit to another regulated Small MS4 or to the City of Stamford, a copy of the registration and all attachments thereto shall also be submitted to the owner and operator of that system.

For discharges authorized by this general permit to a DOT separate storm sewer system, a copy of the registration and all attachments thereto shall also be submitted to the DOT upon request.

For discharges within a public drinking water supply watershed or aquifer area, the permittee shall notify the water company of the availability (pursuant to Sections 4(*d*)(1) and (2), above) of the registration and the Plan described in subsection 5(*b*) of this general permit or the registration and Plan shall be submitted to the water company upon request.

For discharges to river components and tributaries which have been designated as Wild and Scenic under the Wild and Scenic Rivers Act, a copy of the registration and the Plan described in 5(*b*) of this general permit shall be submitted to the applicable Wild and Scenic Coordinating Committee upon request.

(h) Action by Commissioner

(1) The Commissioner may require that a permittee obtain an individual permit for any discharge authorized by this permit in accordance with Section 22a-430b of the Connecticut General Statutes.

(2) The Commissioner may reject without prejudice a registration if he or she determines that it does not satisfy the registration requirements (Section 4(*c*)) of this general permit. Any registration refiled after such a rejection shall be accompanied by the fee specified in the "Fees" section (Section 4(*c*)(1)) of this general permit.

(3) The Commissioner may disapprove a registration if he or she finds that the subject activity is inconsistent with the "Requirements for Authorization" section (Section 3(*b*)) of this general permit, or for any other reason provided by law.

(4) Disapproval of a registration under this subsection shall constitute notice to the registrant that the subject activity must be authorized by an individual permit.

(5) Disapproval of a registration shall be in writing.

Section 5. Requirements of this General Permit

The permittee shall at all times continue to meet the requirements for authorization set forth in Section 3 of this general permit. In addition, a permittee shall ensure that authorized activities are conducted in accordance with the following conditions:

(a) Conditions Applicable for Certain Discharges

(1) If the permittee initiates, creates, or originates a discharge of stormwater which is located less than 500 feet from a tidal wetland that is not a fresh-tidal wetland, such discharge shall flow through a system designed to retain the Water Quality Volume, as defined in Section 2.

(2) If the permittee wishes to initiate, create, or originate a discharge of stormwater below the coastal jurisdiction line into coastal, tidal, or navigable waters for which a permit is required under the Structures and Dredging Act in accordance with Section 22a-361(a) of the Connecticut General Statutes or into tidal wetlands for which a permit is required under the Tidal Wetlands Act in accordance with Section 22a-32 of the Connecticut General Statutes, the municipality shall obtain such permit(s) from the Commissioner prior to initiating, creating or originating such discharge.

(3) There shall be no distinctly visible floating scum, oil or other matter contained in the stormwater discharge. Excluded from this are naturally occurring substances such as leaves and twigs provided no person has placed such substances in or near the discharge.

(4) The stormwater discharge shall not result in pollution which may cause or contribute to acute or chronic toxicity to aquatic life, impair the biological integrity of aquatic or marine ecosystems, or result in an unacceptable risk to human health.

(5) The stormwater discharge shall not cause or contribute to an exceedance of the applicable Water Quality Standards in the receiving water.

(6) Any new stormwater discharge to high quality waters (as identified by the Commissioner consistent with the Water Quality Standards) shall be discharged in accordance with the Connecticut Anti-Degradation Implementation Policy in the Water Quality Standards manual. At a minimum, the permittee shall evaluate and implement to the Maximum Extent Practicable practices which will prevent the discharge of the Water Quality Volume to a surface water body or other practices necessary to protect and maintain designated uses and meet standards and criteria contained in the Water Quality Standards.

(7) Any stormwater discharge to the waters identified in Appendix D shall be managed for the Stormwater Pollutant of Concern identified in the appendix consistent with the requirements in Section 6 of this permit.

(b) Stormwater Management Plan

The permittee shall develop, implement, and enforce a stormwater management plan designed to reduce the discharge of pollutants from the Small MS4 to the maximum extent practicable, to protect water quality, and to satisfy the appropriate water quality requirements of the federal Clean Water Act. Maximum Extent Practicable (MEP) is a technology-based standard established by Congress in the Clean Water Act Section 402(p)(3)(B)(iii). Since no precise definition of MEP exists, it allows for maximum flexibility on the part of MS4 operators as they develop their programs. (40CFR 122.2, See also: Stormwater Phase II Compliance Assistance Guide EPA 833-R-00-002, March 2000). When trying to reduce pollutants to the MEP, there must be a serious attempt to comply, and practical solutions may not be lightly rejected. Factors such as the conditions of receiving waters, specific local concerns, MS4 size, climate, implementation schedules, current ability to finance the program, beneficial uses of receiving water, hydrology, geology, and capacity to perform operation and maintenance should be considered in determining whether permittee has complied with this general permit to the Maximum Extent Practicable.

Under this program, the permittee shall prepare a Stormwater Management Plan pursuant to Section 6 of this general permit, which plan must be completed by such time as specified in Section 4(*d*)(2) of this general permit. The permittee shall continue to implement the Stormwater Management Plan and all Minimum Control Measures required by this general permit throughout the entire term of the general permit. The permittee shall continue to provide for adequate staffing and economic resources for such implementation throughout the entire term of the general permit. If at any time the Commissioner finds that the Plan is not adequate to protect the waters of the state from pollution, the Commissioner may terminate authorization under this permit and require the permittee to submit an individual permit application.

Failure to implement all elements of the Stormwater Management Plan to the MEP constitutes a violation of this permit.

Section 6. Development of Stormwater Management Plan (Plan)

The Plan shall address the Minimum Control Measures as indicated in this section. Section 6(*a*) contains the requirements for Small MS4s. These measures shall be implemented throughout the boundaries of the municipality or institution except as otherwise indicated in this section.

(a) Minimum Control Measures

For each Minimum Control Measure, the permittee shall: define appropriate BMPs; designate a person(s) and job title responsible for each BMP; define a time line for implementation of each BMP; where appropriate, identify the location, including the address and latitude and longitude, for each BMP; and define measurable goals for each BMP. The Minimum Control Measures in the Plan include, but are not limited to:

(1) Public education and outreach

The goals of this minimum control measure are:

- To raise awareness that polluted stormwater runoff is the most significant source of water quality problems;
- To motivate residents to use Best Management Practices (BMPs) which reduce polluted stormwater runoff; and
- To reduce polluted stormwater runoff as a result of increased awareness and utilization of BMPs.

(A) Implement a public education program to distribute educational materials to the permittee's community (i.e. residents, business and commerce, students, staff, contractors, etc.) or conduct equivalent outreach activities about the sources and impacts of stormwater discharges on waterbodies and the steps that the public can take to reduce pollutants in stormwater runoff. The education program shall include, but not be limited to, information on management of pet waste, application of fertilizers, herbicides, and pesticides, impervious cover and impacts of illicit discharges and improper disposal of waste into the MS4. The form and content of the education program will be dependent on the audience and identified areas of concern for each MS4. Permittees may join other permittees in the same region to develop and implement a public education program. Educational information may be developed and/or acquired from other permittees, governmental agencies, community and non-governmental organizations, councils of government, academia, and/or environmental advocacy organizations. Outreach resources will be available from the DEEP stormwater webpage at www.ct.gov/deep/stormwater. Information may be disseminated with flyers, brochures, door hangers, television public service announcements, and/or web based tools. Each Annual Report shall summarize the types, sources, number of, and methods by which materials disseminated.

(i) Permittees previously authorized by the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems issued on January 9, 2004 (existing 2004 MS4 permittees) shall begin implementation of this measure within the first year following the effective date of this permit and continue until permit expiration. Permittees shall utilize the materials developed under the 2004 MS4 permit and update or modify as necessary to acquire and/or develop the content of the outreach materials for this general permit.

(ii) Permittees not previously authorized by the General Permit for the Discharge of Stormwater from Small Municipal Separate Storm Sewer Systems issued on January 9, 2004 (new MS4 permittees) shall begin implementation of this measure within the second year following the effective date of this permit and continue until

permit expiration. Permittees shall utilize the one year period following the effective date of this permit to acquire and/or develop the content of the outreach materials.

(B) To implement the public education and outreach program, the permittee shall develop or acquire current educational material from DEEP and other sources that identifies the pollutants (such as pathogens/bacteria, nitrogen, phosphorus, sediments, metals, oils & greases) associated with stormwater discharges, the potential sources of the pollutants, the environmental impacts of these pollutants, and related pollution reduction practices.

(C) Additional measures for discharges to waters associated with a Stormwater Pollutant of Concern

These measures may be implemented solely by the permittee or as part of a collaborative regional or statewide program to address the issue. However, the permittee retains sole responsibility for compliance with this section. The method of implementation shall be indicated in the permittee's Plan.

(i) For waters for which **Phosphorus** is a Stormwater Pollutant of Concern, educational materials shall be specifically tailored and targeted to educate on the sources, impacts, and available pollution reduction practices from the following:

a. Septic systems
b. Fertilizer use
c. Grass clippings and leaves management
d. Detergent use
e. Discharge of sediment (to which Phosphorus binds) from Construction sites
f. Other erosive surfaces

(ii) For waters for which **Nitrogen** is a Stormwater Pollutant of Concern, educational materials shall be specifically tailored and targeted to educate on the sources, impacts, and available pollution reduction practices from the following:

a. Septic systems
b. Fertilizer use
c. Grass clippings and leaves management
d. Discharge of sediment (to which Nitrogen binds) from Construction sites
e. Other erosive surfaces

(iii) For waters for which **Bacteria** is a Stormwater Pollutant of Concern, educational materials shall be specifically tailored and targeted to educate on the sources, impacts, and available pollution reduction practices from the following:

a. Septic systems
b. Sanitary cross connections
c. Waterfowl
d. Pet waste
e. Manure piles associated with livestock and horses

(iv) For waters for which **Mercury** is a Stormwater Pollutant of Concern, educational materials shall be specifically tailored and targeted to educate on the sources,

impacts and available recycling programs for elemental mercury and mercury-containing items such as:

a. Thermometers
b. Thermostats
c. Fluorescent lights
d. Button cell batteries

(D) Suggested Strategies.

(i) Target specific populations: Each permittee is encouraged to direct such outreach program and/or materials at specific populations. Such target populations may include, for example, school age populations, farming populations, and urban populations. Sample educational material for each Stormwater Pollutant of Concern noted above will be made available by DEEP.

(ii) Partner with local organizations: Permittees may wish to include in its outreach efforts various local organizations which may be able to assist in helping to spread the stormwater message.

(2) Public Involvement/Participation

The permittee shall provide opportunities to engage their community to participate in the review and implementation of the permittee's Plan. The goal of this minimum control measure is to involve the community in both the planning and implementation process of improving water quality. Public participation is beneficial to the success of a municipal stormwater management program because it allows for a broader public support, additional expertise, and a conduit to other programs. Community members are also more likely to apply these lessons/BMPs at home if they are part of the process.

(A) Publish a public notice on the permittee's website, through an email or mailing list, if the permittee maintains one, or in a newspaper with general circulation in the area to inform the public of the Plan and the Annual Report required by Section 6(*j*) of this permit and to solicit comments on the Plan and Annual Report. The notice shall provide a contact name (with phone number, address, and email) to whom the public can send comments and a publicly accessible location (such as the MS4's main office or other designated municipal office, a local library or other central publicly available location) and/or URL where the Plan and Annual Report are available for public review. The public notice shall allow for a 30 day comment period, at a minimum. Municipalities and institutions shall publish this public notice annually no later than January 31.

(B) The permittee is encouraged to enlist local organizations to help implement the elements of their Plan. However, the permittee retains sole responsibility for permit compliance.

(C) No requirements in addition to those specified in subsections (A)-(B), above, are specified for discharges to waters impaired for Phosphorus, Nitrogen, Bacteria, or Mercury.

(3) Illicit discharge detection and elimination.

Within one (1) year of the effective date of this general permit for existing 2004 MS4 permittees and within two (2) years of the effective date of this general permit for new MS4 permittees, the permittee shall develop a written Illicit Discharge Detection and Elimination (IDDE) program designed to: provide the legal authority to prohibit and eliminate illicit discharges (as defined in Section 2 except for those discharges noted in the Section 3(*a*)(2) of this permit) to the MS4; find the source of any illicit discharges; eliminate those illicit discharges; and ensure ongoing screening and tracking to prevent and/or eliminate future illicit discharges. Failure to implement all elements of the IDDE program to the MEP constitutes a violation of this permit.

(A) IDDE Program Elements

(i) The permittee shall, at a minimum, implement the IDDE program elements in this section and the IDDE protocol in Appendix B within the Urbanized Area and those catchment areas of the MS4 with either Directly Connected Impervious Area (DCIA) of greater than 11% (as identified on maps available at www.ct.gov/deep/municipalstormwater) or which discharge to impaired waters ("priority" areas). The permittee is encouraged to develop a prioritizing strategy to identify areas outside these identified areas to further implement these IDDE measures. This prioritizing strategy should utilize the prioritizing elements included in Section (A)(7)(c) of Appendix B.

(ii) Illicit discharges to the MS4 by any person are prohibited, and any such discharges are not authorized by the general permit, are unlawful, and remain unlawful until they are eliminated. The permittee shall prohibit all illicit discharges from entering its MS4. Upon detection, the permittee shall eliminate illicit discharges as soon as possible and require the immediate cessation of such discharges upon confirmation of responsible parties in accordance with its enforceable legal authorities established pursuant to subsection (B) below. Where elimination of an illicit discharge within sixty (60) days of its confirmation is not possible, the permittee shall establish a schedule for its elimination not to exceed 180 days (six (6) months). The permittee shall immediately commence actions necessary for elimination. The permittee shall diligently pursue elimination of all illicit discharges. In the interim, the permittee shall take all reasonable and prudent measures to minimize the discharge of pollutants to its MS4.

(iii) The permittee shall develop a program for citizen reporting of illicit discharges. This may include maintaining a website, email list or mailing program that provides clear instructions for the public describing how citizens can submit an illicit discharge report. The reporting program shall provide an email address and/or a phone number or other means for submissions. The permittee shall affirmatively investigate and eliminate any illicit discharges reported to it by any citizen or organization, provided that such report incorporates at least a time and location of an observed discharge. The permittee shall commence inspection of such a reported outfall or manhole promptly after receiving such a report, and incorporate those reported outfalls into its IDDE program subject to all provisions

of this subsection (3) and of Appendix B. All citizen reports and the responds to those reports shall be included in the Annual Report.

(iv) The permittee shall implement outfall screening and an illicit discharge detection protocol pursuant to **Appendix B** to identify, prioritize, and investigate separate storm sewer catchments for suspected illicit discharges of pollutants.

(v) The permittee shall maintain a record of illicit discharge abatement activities including, at a minimum: location (identified with an address or latitude and longitude), description, date(s) of inspection, sampling data (if applicable), action(s) taken, date of removal or repair and responsible party(ies). This information shall be included in the permittee's Annual Report pursuant to the Section 6(*j*) of this permit.

(vi) Timelines – permittees shall implement IDDE program elements in accordance with the schedules included in this section and in Appendix B.

(B) Establish the necessary and enforceable legal authority by statute, ordinance, rules and regulations, permit, easement, contract, order or any other means, to eliminate illicit discharges.

(i) The legal authority shall:

a. prohibit illicit discharges to its storm sewer system and require removal of such discharges consistent with subsection (3)(A), above; and

b. control the discharge of spills and prohibit the dumping or disposal of materials including, but not limited to, residential, industrial and commercial wastes, trash, used motor vehicle fluids, pesticides, fertilizers, food preparation waste, leaf litter, grass clippings, and animal wastes into its MS4; and

c. authorize fines or penalties and/or recoup costs incurred by the permittee from anyone creating an illicit discharge or spilling or dumping as specified in subsection (3)(A), above. For state and federal institutions, where this provision may conflict with existing rules, regulations, policies, chain of command or other circumstances, alternate provisions for enforcement may be utilized.

d. provide any additional legal authorities specified in Section (A)(7)(a) of Appendix B.

(ii) Existing 2004 MS4 permittees must establish and implement this legal authority within one year of the effective date of this permit.

(iii) New MS4 permittees must establish and implement this legal authority on or before two (2) years of the effective date of this permit.

(C) Develop a list (spreadsheet or database) and map or series of maps at a minimum scale of 1"=2000' and maximum scale of 1"=100' showing all stormwater discharges from a pipe or conduit located within and owned or operated by the municipality or institution

and all interconnections with other MS4s. The map(s) should, if possible, be developed in a GIS format.

(i) The list and map(s) shall include for each discharge:

a. Type, material, size, and location (identified with a latitude and longitude) of conveyance, outfall or channelized flow (e.g. 24" concrete pipe);

b. the name, water body ID and Surface Water Quality Classification of the immediate surface waterbody or wetland to which the stormwater runoff discharges;

c. if the outfall does not discharge directly to a named waterbody, the name and water body ID of the nearest named waterbody to which the outfall eventually discharges;

d. the name of the watershed, including the subregional drainage basin number (available from CT ECO at www.cteco.uconn.edu) in which the discharge is located; and

e. the spreadsheet or database should, if possible, be prepared in a format compatible with Microsoft Excel.

(ii) For existing 2004 MS4 permittees, this list and mapping must be completed within two (2) years of the effective date of this permit.

(iii) For new MS4 permittees, this list and mapping must commence upon the effective date of this permit and be completed within three (3) years from the effective date of this permit. The entirety of the municipal or institutional MS4 shall be mapped by the expiration date of this permit.

(D) For waters for which **Phosphorus**, **Nitrogen**, or **Bacteria** is a Stormwater Pollutant of Concern:

(i) To address septic system failures, the IDDE program shall give highest priority for the IDDE program in areas with the highest potential to discharge bacteria, phosphorus, and nitrogen to the MS4. Such areas shall be identified based on assessment of the following criteria: historic on-site sanitary system failures, proximity to bacteria impaired waters, low infiltrative soils, and shallow groundwater. Consultation with local or state health officials is strongly encouraged. The Annual Report shall include a summary of the program, the number of areas identified with failing systems, actions taken by the permittee to respond to and address the failures, and the anticipated pollutant reduction.

(E) No requirements in addition to those specified in subsections (A) - (C) above exist for discharges to waters for which **Mercury** is a Stormwater Pollutant of Concern.

(4) Construction Site Stormwater Runoff Control

The permittee shall implement and enforce a program to control stormwater discharges (to its MS4) associated with land disturbance or development (including re-development)

activities from sites (as defined in the Department's General Permit for the Discharge of Stormwater and Dewatering Wastewaters from Construction Activities) with one acre or more of soil disturbance, whether considered individually or collectively as part of a larger common plan. Such program shall include the following elements:

(A) Legal Authority

(i) The permittee shall establish an ordinance, bylaw, regulation, standard condition of approval or other appropriate legal authority that requires:

a. developers, construction site operators, or contractors to maintain consistency with the 2002 Guidelines for Soil Erosion and Sedimentation Control, as amended, the Connecticut Stormwater Quality Manual, and all stormwater discharge permits issued by the DEEP within the municipal or institutional boundary pursuant to CGS 22a-430 and 22a-430b;

b. the implementation of additional measures to protect/improve water quality (in addition to the above requirements) as deemed necessary by the municipality or institution;

c. the permittee to carry out all inspection, surveillance and monitoring procedures necessary to determine compliance with municipal regulations, ordinances or programs or institutional requirements related to the management of the permittee's MS4. Specifically, inspections shall be conducted, where allowed, to inventory the number of privately-owned retention ponds, detention ponds and other stormwater basins that discharge to or receive drainage from the permittee's MS4;

d. the owner of a site seeking development approval from the permittee to provide and comply with a long term maintenance plan and schedule to ensure the performance and pollutant removal efficiency of privately-owned retention ponds, detention ponds and other stormwater basins that discharge to or receive discharge from the permittee's MS4 including short-term and long-term inspection and maintenance measures to be implemented by the private owner; and

e. the permittee to control through interagency or inter-jurisdictional agreements, the contribution of pollutants between the permittee's MS4 and MS4s owned or operated by others.

(ii) For existing 2004 MS4 permittees, within two (2) year from the start of the permittee's first fiscal year that begins after the effective date of this permit, the permittee shall implement, upgrade (if necessary) and enforce its land use regulations to meet the requirements of subsections 4(A)(i)a. – e. above.

(iii) For new MS4 permittees, within three (3) years from the start of the permittee's first fiscal year that begins after the effective date of this permit, the permittee shall implement, upgrade (if necessary) and enforce its land use regulations (for municipalities) or its construction requirements (for institutions) to meet the requirements of Sections 4(A)(i)a. – e. above.

(B) Interdepartmental Coordination

(i) The permittee will develop and implement a plan outlining how all municipal or institutional departments and boards with jurisdiction over the review, permitting, or approval of land disturbance and development projects within the MS4 will coordinate their functions with one another.

(ii) All municipalities and institutions shall implement this measure upon the effective date of this permit.

(C) Site Review and Inspection

(i) The permittee will conduct site plan reviews that incorporate consideration of stormwater controls or management practices to prevent or minimize impacts to water quality.

(ii) The permittee will conduct site inspection(s) and enforcement to assess the adequacy of the installation, maintenance, operation, and repair of construction and post construction control measures.

(iii) All municipalities and institutions shall implement this measure upon the effective date of this permit.

(D) Public Involvement

(i) The permittee will implement a procedure for receipt and consideration of information submitted by the public concerning proposed and ongoing land disturbance and development activities.

(ii) All municipalities and institutions shall implement this procedure upon the effective date of this permit.

(E) State Permit Notification

(i) The permittee will implement a procedure for notifying developers (working in a municipality) or contractors (working for a municipality or an institution) of their potential obligation to obtain authorization under the DEEP's General Permit for the Discharge of Stormwater and Dewatering Wastewaters Associated with Construction Activities ("construction general permit") if their development or redevelopment project disturbs one or more acres of land, either individually or collectively, as part of a larger common plan, and results in a point source discharge to the surface waters of the state directly or through the permittee's MS4. The notification shall include a provision informing the developer/contractor of their obligation to provide a copy of the Storm Water Pollution Control Plan (required by the construction general permit) to the permittee upon request.

(ii) All municipalities and institutions shall implement this procedure upon the effective date of this permit.

(F) For construction discharges to waters for which **Phosphorus**, **Nitrogen**, **Bacteria**, or **Mercury** is a Stormwater Pollutant of Concern no additional measures are included in this section except as may be required by Sections 3(*b*)(7) or 6(*k*).

(5) Post-construction stormwater management in new development or redevelopment

(A) Legal Authority

(i) The permittee shall establish an ordinance, bylaw, regulation, standard condition of approval or other appropriate legal authority that requires, to the MEP, that a developer or contractor seeking the permittee's approval shall consider the use of low impact development ("LID") and runoff reduction site planning and development practices prior to the consideration of other practices in the permittee's land use regulations, guidance or construction project requirements to meet or exceed those LID and runoff reduction practices identified in the Stormwater Quality Manual. Such legal authority shall include the following standards: 1) for redevelopment of sites that are currently developed with Directly Connected Impervious Area (DCIA) of forty percent or more, retain on-site half the water quality volume for the site, or 2) for new development and redevelopment of sites with less than forty percent DCIA, retain the water quality volume for the site, or 3) an alternate retention/treatment standard as outlined in subsections 5(B)(i)-(ii) below. All permittees shall identify and, where appropriate, reduce or eliminate existing local regulatory barriers to implementing LID and runoff reduction practices to the MEP. These may include site planning requirements, zoning regulations, street design regulations, or infrastructure specifications that address minimal dimensional criteria for the creation of roadways, parking lots, and other DCIA. If such barriers cannot be eliminated within the timeframe dictated by subsections 5(A)(ii) and (iii), below, the permittee shall provide in the Annual Report(s) required by Section 6(*j*) a justification and a revised schedule for implementation.

In establishing the legal authority, the permittee shall consider the following watershed protection elements to manage the impacts of stormwater on receiving waters, except where noted:

a. Minimize the amount of impervious surfaces (roads, parking lots, roofs, etc.) within each municipality by minimizing the creation, extension, and widening of parking lots, roads, and associated development and encourage the use of Low Impact Development or green infrastructure practices.

b. Preserve, protect, create and restore ecologically sensitive areas that provide water quality benefits and serve critical watershed functions. These areas may include, but are not limited to; riparian corridors, headwaters, floodplains and wetlands.

c. Implement stormwater management practices that prevent or reduce thermal impacts to streams, including requiring vegetated buffers along waterways, and disconnecting discharges to surface waters from impervious surfaces such as parking lots.

d. Seek to avoid or prevent hydromodification of streams and other water bodies caused by development, including roads, highways, and bridges.

e. Implement standards to protect trees, and other vegetation with important evapotranspirative qualities.

f. Implement policies to protect native soils, prevent topsoil stripping, and prevent compaction of soils.

(ii) For existing 2004 MS4 permittees, the permittee shall consider the elements of this section during regular reviews and implement this requirement no later than four (4) years after the effective date of this permit.

(iii) For new permittees, the permittee shall consider the elements of this section during regular reviews and implement this requirement no later than five (5) years after the effective date of this permit.

(B) Runoff Reduction/Low Impact Development ("LID") Measures

Pursuant to the requirements of subsection 5(A)(i) above, the permittee shall require the party responsible (i.e. a developer within a municipal boundary or a developer/contractor with the institution) for development and redevelopment projects within its MS4 to:

(i) For development or redevelopment of sites that are currently developed with Directly Connected Impervious Area (DCIA) of forty percent or more, retain on-site half the water quality volume for the site. In cases where this entire amount cannot be retained, the permittee shall require the responsible party to retain runoff volume to the maximum extent achievable using control measures that are technologically available and economically practicable and achievable in light of best industry practice. In such cases, additional stormwater treatment, to the maximum extent achievable using control measures that are technologically available and economically practicable and achievable in light of best industry practice, shall be required for sediment, floatables and nutrients for the volume above that which can be retained up to the water quality volume. In cases where the runoff reduction requirement cannot be met, the developer/contractor shall submit, for the permittee's review, a report detailing factors limiting the capability of achieving this goal. In such cases, the permittee shall approve a stormwater mitigation project on another site proposed by the developer/contractor or approve a fee to be deposited into a dedicated account of the permittee for use by the permittee to fund in whole or in part the retrofit of one or more existing DCIA. Unless such fee is established by DEEP, the fee proposed by the developer/contractor should be set in amount approved by the permittee as calculated based on an estimate of the cost necessary to implement the retrofit to achieve a similar amount of runoff reduction to the amount by which the actual amount of runoff reduced fails to achieve the requirement to retain the water quality volume for the site. The report shall include: the measures taken to maximize runoff reduction practices on the site; the reasons why those practices constitute the maximum extent achievable; the alternative retention volume; and a description of the measures used to provide additional stormwater treatment above

the alternate volume up to the water quality volume. In the case of linear redevelopment projects (e.g. roadway reconstruction or widening) for the developed portion of the right of way: (1) for projects that may be unable to comply with the full retention standard, the alternate retention and treatment provisions may also be applied as specified above, or (2) for projects that will not increase the DCIA within a given watershed, the developer/contractor shall implement the additional stormwater treatment measures referenced above, but will not be required to retain half of the water quality volume.

(ii) For all new development and for redevelopment of sites with less than forty percent DCIA, retain the water quality volume for the site. If there are site constraints that would prevent retention of this volume on-site (e.g. brownfields, capped landfills, bedrock, elevated groundwater, etc.), documentation must be submitted, for the permittee's review and written approval, which: explains the site limitations; provides a description of the runoff reduction practices implemented; provides an explanation of why this constitutes the maximum extent achievable; offers an alternative retention volume; and provides a description of the measures used to provide additional stormwater treatment for sediment, floatables and nutrients above the alternate volume up to the water quality volume. In such cases, the permittee shall approve a stormwater mitigation project on another site proposed by the developer/contractor or approve a fee to be deposited into a dedicated account of the permittee for use by the permittee to fund in whole or in part the retrofit of one or more existing DCIA. Unless such fee is established by DEEP, the fee proposed by the developer/contractor should be set in amount approved by the permittee as calculated based on an estimate of the cost necessary to implement the retrofit to achieve a similar amount of runoff reduction to the amount by which the actual amount of runoff reduced fails to achieve the requirement to retain the water quality volume for the site. Any such treatment shall otherwise be designed, installed and maintained consistent with the Stormwater Quality Manual. In the case of linear projects that do not involve impervious surfaces (e.g. electrical transmission rights-of-way or natural gas pipelines), retention of the water quality volume is not required as long as the post-development runoff characteristics do not differ significantly from pre-development conditions.

(iii) Consider the limitation of turf areas to those areas necessary to construct buildings, utilities, stormwater management measures, parking, access ways, reasonable lawn areas and contouring necessary to prevent future site erosion,

(iv) Maintain consistency with the Connecticut Stormwater Quality Manual, or if inconsistent, provide an explanation of why consistency is not feasible or practicable and information that the proposed plan of development is adequately protective.

(v) In areas served by on-site sewage disposal (septic) systems, the permittee should coordinate with the state or local health official, as appropriate, to confirm that any infiltration measures are appropriately sized, located and constructed in a manner consistent with the Connecticut Department of Public Health's *Technical Standards for Subsurface Sewage Disposal Systems*, Section 19-13-B100A of the Regulations of Connecticut State Agencies and/or DEEP requirements for on-site sewage disposal systems.

(vi) For existing 2004 MS4 permittees, the permittee shall implement this requirement within two (2) years after the effective date of this permit.

(vii) For new MS4 permittees, the permittee shall implement this requirement within three (3) years from the start of the permittee's first fiscal year that begins after the effective date of this permit.

(C) Directly Connected Impervious Area

Using mapping provided by the Commissioner (available at www.ct.gov/deep/municipalstormwater) or other equivalent source, the permittee shall calculate the Directly Connected Impervious Area (DCIA) that contributes stormwater runoff to each of its MS4 outfalls (i.e. catchment area) within three (3) years of the effective date of this general permit. The DCIA calculation shall be based upon the criteria available through the DEEP stormwater webpage (www.ct.gov/deep/municipalstormwater) and the precise methodology and assumptions shall be described in the permittee's Plan and initial annual report. Each annual report shall document the progress of this task until its completion. The Permittee shall revise its DCIA estimate as development, redevelopment, or retrofit projects effectively add or remove DCIA to its MS4.

(D) Long Term Maintenance

(i) The permittee shall implement a maintenance plan for ensuring the long-term effectiveness of retention or detention ponds located in the Urbanized Area and those catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters and which discharge to, or receive stormwater from, its MS4. This shall include such ponds that are owned by the permittee and all privately-owned ponds where the permittee maintains an easement or other legal authority pursuant to Section 6(*a*)(4)(A)(i) of this permit. At a minimum, the permittee shall annually inspect all such retention or detention ponds and remove accumulated sediment to restore full solids capture design capacity where found to be in excess of 50% design capacity.

(ii) The permittee shall implement a maintenance plan for ensuring the long-term effectiveness of stormwater treatment structures or measures (such as swirl concentrators, oil/grit separators, water quality wetlands or swales, etc.) installed within the Urbanized Area and those catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters. This shall include structures that are owned by the permittee or those for which the permittee maintains an easement or other legal authority pursuant to Section 6(*a*)(4)(A)(i) of this permit. At a minimum, the permittee shall annually inspect all such structures/measures and remove accumulated pollutants (such as sediment, oils, leaves, litter, etc.) to restore full solids capture design capacity where found to be in excess of 50% design capacity.

(iii) For existing 2004 MS4 permittees, the permittee shall implement this requirement within two (2) years of the effective date of this permit.

(iv) For new MS4 permittees, the permittee shall implement this requirement within three (3) years after the effective date of this permit.

(E) Additional measures for discharges to impaired waters (with or without a TMDL)

(i) For waters for which **Nitrogen, Phosphorus** or **Bacteria** is a Stormwater Pollutant of Concern:

To address erosion and sediment problems noted during the course of conducting the inspections required by subsection D above and identified by other means, the permittee shall develop, fund, implement, and prioritize these problems under the Retrofit program specified in Section 6(a)(6)(B) to correct the problem(s) in a specific timeframe and to establish short term and long term maintenance. Each annual report shall include which problem areas were retrofitted, the cost of the retrofit, and the anticipated pollutant reduction.

(ii) No requirements in addition to those specified in subsections (A)-(D) above exist for discharges to waters for which **Mercury** is a Stormwater Pollutant of Concern.

(6) Pollution Prevention/Good Housekeeping

The permittee shall implement an operations and maintenance program for permittee-owned or –operated MS4s that has a goal of preventing or reducing pollutant runoff and protecting water quality from all permittee-owned or -operated MS4s.

(A) Employee Training

The existing 2004 MS4 permittees shall continue a formal employee training program to increase awareness of water quality related issues in management of its MS4. New MS4 permittees shall develop this program within two (2) years of the effective date of this general permit. In addition to providing key staff with topical training regarding standard operating procedures and other activities necessary to comply with the provisions of this permit, the training program shall include establishing an awareness of the general goals and objectives of the Plan; identification and reporting of illicit discharges and improper disposal; and spill response protocols and respective responsibilities of involved personnel.

(B) Infrastructure Repair, Rehabilitation and Retrofit

(i) The permittee shall repair and rehabilitate its MS4 infrastructure in a timely manner to reduce or eliminate the discharge of pollutants from its MS4 to receiving waters. Priority for repair and rehabilitation shall be based on the following:

a. For existing 2004 MS4 permittees, the permittee shall utilize the information developed pursuant to Section 6(*a*)(6)(A)(v) of the 2004 MS4 permit to fund and implement a program for repairing, retrofitting or upgrading the conveyances, structures and outfalls of the MS4. This program shall be updated based on new information on outfalls discharging pollutants, impaired waters, inspection observations or observations made during outfall mapping pursuant to Section 6(*a*)(3)(C) of this permit.

b. For new MS4 permittees, the permittee shall, within the first three (3) years following the effective date of this general permit, develop a program to

identify conveyances, structures and outfalls in need of repairing, retrofitting or upgrading utilizing new and existing information on outfalls discharging pollutants, impaired waters, inspection observations or observations made during outfall mapping pursuant to Section 6(*a*)(3)(C) of this permit.

(ii) Retrofit Program

The goal of the retrofit program is to "disconnect" existing Directly Connected Impervious Areas (DCIA). An area of DCIA is considered disconnected when the appropriate portion of the Water Quality Volume has been retained in accordance with the requirements of Section 6(*a*)(5)(B)(i) or (ii) of this general permit. This may be accomplished through retrofits or redevelopment projects (public or private) that utilize Low Impact Development (LID) and runoff reduction measures or any other means by which stormwater is infiltrated into the ground or reused for other purposes without a surface or storm sewer discharge. A redevelopment project, as that term is used here and in Section 6(*a*)(5)(B)(i) and (ii), is one that modifies an existing developed site for the purpose of enhancing, expanding or otherwise modifying its function or purpose. A retrofit project is one that modifies an existing developed site for the primary purpose of disconnecting DCIA. The DCIA calculation performed pursuant to Section 6(*a*)(5)(C) shall serve as the baseline for the retrofit program required in this section.

a. DCIA Disconnection Tracking

Beginning on the effective date of this general permit, the permittee shall track on an annual basis the total acreage of DCIA that is disconnected as a result of redevelopment or retrofit projects within the MS4. Tracking the disconnection of DCIA means documenting within a given redevelopment or retrofit project the amount of existing DCIA that is modified such that it is disconnected. This tracking may include disconnections of DCIA from redevelopment or retrofit projects implemented as early as five (5) years prior to the effective date of this permit. Any redevelopment or retrofit of an existing developed site, whether public (municipal, state or federal) or private (residential, commercial or industrial) shall be included in this tracking.

Tracking the disconnection of DCIA does <u>not</u> apply for sites that were previously undeveloped as there were no existing impervious surfaces on those sites. The total amount of DCIA that has been disconnected during a given year shall be reported in that year's Annual Report.

b. Retrofit Planning

On or before the end of third year after the effective date of this general permit, the permittee shall develop a plan to implement retrofit projects to meet the goals of this section. The permittee shall identify and prioritize sites that may be suitable for retrofit. Considerations for prioritizing retrofit projects may include outfall catchment areas that discharge to impaired waters, areas within the Urbanized Area of the MS4 or catchment areas with greater than eleven percent (11%) DCIA. The permittee shall select from the list of prioritized projects those that it will implement to meet the goals in subparagraph (c) below. In the Annual Report for the third year of this general permit, the

permittee shall report on its identification and prioritization process, the selection of the projects to be implemented, the rationale for the selection of those projects and the total DCIA to be disconnected upon implementation of the projects.

c. Retrofit Schedule

By the end of this permit term, the permittee shall commence the implementation of the retrofit projects identified in subparagraph (b), above, with a goal of disconnecting one percent (1%) per year of the permittee's DCIA for the fourth and fifth years of this general permit, or a total of 2%, to the MEP. The two percent (2%) goal may be achieved by compiling the total disconnected DCIA tracked pursuant to subparagraph (a), above, or the retrofit projects designated in subparagraph (b), above, or a combination of the two.

If the two percent (2%) goal will not be met, the permittee shall include in the Annual Report a discussion of what percentage of DCIA will actually be disconnected and why the remainder of the two percent (2%) goal could not be achieved based on the MEP standard outlined in Section 5(*b*). The permittee shall also provide in the Annual Report for the fifth year of this permit for continuation of the retrofit program and continue such program with a goal to disconnect one percent (1%) of DCIA in each year thereafter.

(C) MS4 Property and Operations Maintenance

Permittee-owned or -operated properties, parks, and other facilities that are owned, operated, or otherwise the legal responsibility of the permittee shall be maintained so as to minimize the discharge of pollutants to its MS4. Such maintenance shall include, but not be limited to:

.

(i) Parks and open space

The permittee shall optimize the application of fertilizers by municipal employees, institutional staff, or private contractors on lands and easements for which it is responsible for maintenance. Optimization practices considered may include conducting soil testing and analysis to determine soil phosphorus levels, the reduction or elimination of fertilizers, reduction of usage by adhering to the manufacturers' instructions, and use of alternative fertilizers forms (i.e. products with reduced, slow-releasing, or insoluble phosphorus compositions). Additional optimization practices to be considered include: proper storage and application practices (i.e. avoid impervious surfaces), application schedule (i.e. appropriate season or month) and timing (i.e. coordinated with climatic conditions to minimize runoff potential); develop and implement standard operating practices for the handling, storage, application, and disposal of pesticides and herbicides in compliance with applicable state and federal laws; evaluate lawn maintenance and landscaping activities to promote water quality (protective practices include reduced mowing frequencies, proper disposal of lawn clippings, and use of alternative landscaping materials like drought resistant and native plantings); and establish procedures for management of trash containers at parks (scheduled cleanings; sufficient number).

The permittee shall establish practices for the proper disposal of grass clippings and leaves at permittee-owned lands. Clippings shall be composted or otherwise appropriately disposed. Clippings should not enter the MS4 system or waters of the state.

(ii) Pet waste management

The permittee shall identify locations within its community/institution where inappropriate pet waste management practices are immediately apparent and pose a threat to receiving water quality due to proximity and potential for direct conveyance of waste to its storm system and waters. In such areas, the permittee shall, implement targeted management efforts such as public education and enforcement (e.g. increased patrol for violators). In permittee-owned recreational areas where dog walking is allowed, the permittee shall install educational signage, pet waste baggies, and disposal receptacles (or require carry-out). The permittee shall document its efforts in its annual reports. The permittee should consider including information regarding the scope and extent of its education, compliance, and enforcement efforts (including the number of violations pursued and fines levied or other enforcement taken).

(iii) Waterfowl management

Identify lands where waterfowl congregate and feeding by the public or institutional staff/residents occurs. To raise awareness regarding the water quality impacts, the permittee shall install signage or use other targeted techniques to educate the public about the detrimental impacts of feeding waterfowl (including the resulting feces deposition) and discourage such feeding practices. The permittee shall also implement practices that discourage the undesirable congregation of waterfowl in these areas, or otherwise isolate the direct drainage from these areas away from its storm system and waters.

(iv) Buildings and facilities (schools under the jurisdiction of the permittee, town offices, police and fire stations, pools, parking garages and other permittee-owned or operated buildings or utilities)

Evaluate the use, storage, and disposal of both petroleum and non-petroleum products; ensure, through employee training, that those responsible for handling these products know proper procedures; ensure that Spill Prevention Plans are in place, if applicable, and coordinate with the fire department as necessary; develop management procedures for dumpsters and other waste management equipment; sweep parking lots and keep areas surrounding the facilities clean to minimize runoff of pollutants; and ensure that all interior building floor drains are not connected to the MS4. This permit does not authorize such discharges; wastewaters from interior floor drains must be appropriately permitted.

(v) Vehicles and Equipment

Establish procedures for the storage of permittee-owned or -operated vehicles; require vehicles with fluid leaks to be stored indoors or in contained areas until repaired; evaluate fueling areas owned by the permittee and used by permittee-owned or -operated vehicles and if possible, place fueling areas under cover in

order to minimize exposure; establish procedures to ensure that vehicle wash waters are not discharged to the municipal storm sewer system or to surface waters. This permit does not authorize such discharges; wastewaters from interior floor drains must be appropriately permitted.

(vi) Leaf Management

The permittee shall establish and implement procedures to minimize or prevent the deposition of leaves in catch basins, streets, parking lots, driveways, sidewalks or other paved surfaces that discharge to the MS4. Such procedures shall also apply to leaves collected by the permittee.

(D) Street, Parking & MS4 Maintenance

The permittee shall implement a program to provide for regular inspection and maintenance of permittee-owned or -operated streets, parking areas and other MS4 infrastructure.

(i) Sweeping

a. Establish and implement procedures for sweeping permittee-owned or -operated streets and parking lots. All streets and parking lots within the Urbanized Area of the MS4, and outside the Urbanized Area within the catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters, shall be inspected, swept and/or cleaned (as necessary) with a minimum frequency of once per year in the spring following the cessation of winter maintenance activities (i.e. sanding, deicing, etc.). The procedures shall also include more frequent inspections, cleaning and/or sweeping of targeted areas determined by the permittee to have increased pollutant potential based on the presence of active construction activity or other potential pollutant sources. The permittee shall identify such potential pollutant sources based upon surface inspections, catch basin cleaning or inspection results, land use, winter road deicing and/or sand application, impaired or TMDL waters or other relevant factors as determined by the permittee. If wet dust suppression is conducted, the use of water should be minimized such that a discharge of excess water to surface waters and/or the storm sewer system does not occur.

For streets and parking lots outside the Urbanized Area and outside the catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters, including any rural uncurbed streets and parking lots with no catch basins, the permittee shall either meet the minimum frequencies above, or develop and implement an inspection, documentation and targeted sweeping and/or cleaning plan within one (1) year of the effective date of the general permit, and submit such plan with its year one Annual Report. For new and redeveloped municipal parking lots, evaluate options from reducing stormwater runoff to surface waters and/or the storm sewer system by the installing pervious pavements and/or other measures to promote sheet flow of stormwater.

b. Ensure the proper disposal of street sweepings in accordance with Department policies, guidance and regulations. Sweepings shall not be discharged back into the storm drain system and/or surface waters.

c. In its Annual Report, the permittee shall document results of its sweeping program including, at a minimum: a summary of inspection results, curb miles swept, dates of cleaning, volume or mass of material collected, and method(s) of reuse or disposal. The permittee shall also include documentation of any alternate sweeping plan for rural uncurbed streets and any runoff reduction measures implemented.

(ii) Catch Basin Cleaning

The Permittee shall conduct routine cleaning of all catch basins. The Permittee shall track catch basin inspection observations. Utilizing information compiled through its inventory of catch basins, operational staff and public complaints, the Permittee shall optimize routine cleaning frequencies for particular structures or catchment areas as follows to maintain acceptable sediment removal efficiencies:

a. Inspect all permittee-owned catch basins within the Urbanized Area of the MS4 and outside the Urbanized Area within the catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters at least once by the end of the third year following the effective date of this general permit. Catch basins outside the Urbanized Area and outside the catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters shall be inspected by the end of the fifth year following the effective date of this general permit.

b. Prioritize inspection and maintenance for permittee-owned catch basins located near impaired waters and construction activities (roadway construction, residential, commercial, or industrial development or redevelopment). Clean catch basins in such areas more frequently if inspection and maintenance activities indicate excessive sediment or debris loadings.

c. Establish a schedule that the frequency of routine cleaning will ensure that no catch basin at any time will be more than fifty (50) percent full.

d. If a catch basin sump is more than fifty (50) percent full during two consecutive routine inspections/cleaning events, the permittee shall document that finding, investigate the contributing drainage area for sources of excessive sediment loading, and to the maximum extent practicable, abate contributing sources. The permittee shall describe any actions taken in its Annual Report.

e. For the purposes of this subsection, an excessive sediment or debris loading is a catch basin sump more than fifty (50) percent full. A catch basin sump is more than 50 percent full if the contents within the sump exceed one half the distance between the bottom interior of the catch basin to the invert of the deepest outlet of the catch basin.

f. The permittee shall document in the Plan and in the first Annual Report its plan for optimizing catch basin cleaning, inspection plans, or its schedule for gathering information to develop the optimization plan. Documentation shall include metrics and other information used to reach the determination that the established plan for cleaning and maintenance is optimal for the MS4. The permittee shall keep a log of catch basins cleaned or inspected.

g. The permittee shall report in each Annual Report the total number of catch basins, number inspected, number cleaned, the total volume or mass of material removed from all catch basins and, if practicable, the volume or mass of material removed from each catch basin draining to water quality limited waters.

(E) Snow Management Practices

(i) Deicing Material Management

Develop and implement standard operating practices for the use, handling, storage, application, and disposal of deicing products such as salt and sand to minimize exposure to stormwater; consider means to minimize the use and optimize the application of chloride-based or other salts or deicing product (while maintaining public safety) and consider opportunities for use of alternative materials; for any exterior containers of liquid deicing materials installed after the effective date of this permit, provide secondary containment of at least 110% of the largest container or 10% of the total volume of all containers, whichever is larger, without overflow from the containment area.

(ii) Snow and Ice Control Practices

The permittee shall implement and refine its standard operating practices regarding its snow and ice control to minimize the discharge of sand, anti-icing or de-icing chemicals and other pollutants (while maintaining public safety). The permittee shall establish goals for the optimization of sand and/or chemical application rates through the use, where practicable, of automated application equipment (e.g. zero-velocity spreaders), anti-icing and pre-wetting techniques, implementation of pavement management systems, and alternate chemicals. The permittee shall maintain records of the application of sand, anti-icing and/or de-icing chemicals to document the reduction of chemicals to meet established goals. The permittee shall ensure the proper training for deicing applications for municipal employees, institutional staff, or private contractors on lands and easements for which it is responsible for maintenance.

The permittee shall manage and dispose of snow accumulations in accordance with DEEP's Best Management Practices for Disposal of Snow Accumulations from Roadways and Parking Lots, revised 2/4/11 and as amended (see link at: www.ct.gov/deep/stormwater). In its Annual Report, the permittee shall document results of its snow removal program including, at a minimum: the type of staff training conducted on application methods and equipment, type(s) of deicing materials used; lane-miles treated; total amount of each deicing material used; type(s) of deicing equipment used; any changes in deicing practices (and the reasons for the change); and snow disposal methods.

(F) Interconnected MS4s

As part of interagency agreements established pursuant to Section 6(*c*)(3) of this permit, the Permittee shall coordinate with operators of interconnected MS4s (such as neighboring municipalities, institutions and DOT) regarding the contribution of potential pollutants from the storm sewer systems, contributing land use areas and stormwater control measures in the respective MS4s. This same coordination shall be conducted regarding operation and maintenance procedures utilized in the respective systems.

(G) Sources contributing pollutants to the MS4

The permittee shall develop and implement a program to control the contribution of pollutants to its MS4 from commercial, industrial, municipal, institutional or other facilities, not otherwise authorized by permit issued pursuant to Sections 22a-430 or 22a-430b of the Connecticut General Statutes.

(H) Additional measures for discharges to impaired waters (with or without a TMDL)

(i) For waters for which **Nitrogen** or **Phosphorus** is a Stormwater Pollutant of Concern:

On Permittee-owned or -operated lands, implement a turf management practices and procedures policy which includes, but is not limited to, procedures for proper fertilizer application and the planting of native plant materials to lessen the amount of turf area requiring mowing and the application of chemicals. Each Annual Report shall discuss the actions taken to implement this policy with an estimate of fertilizer and turf reduction.

(ii) For waters for which **Bacteria** is a Stormwater Pollutant of Concern:

On Permittee-owned or -operated lands with a high potential to contribute bacteria (such as dog parks, parks with open water, sites with failing septic systems), the permittee shall develop, fund, implement, and prioritize a retrofit or source management program to correct the problem(s) within a specific timeframe. Each Annual Report shall identify problem areas for which a retrofit or source management program were developed, the location of the closest outfall monitored in accordance with Section 6(*i*), the cost of such retrofit or program, and the anticipated pollutant reduction.

On Permittee-owned or -operated lands, prohibit the feeding of geese or waterfowl and implement a program to manage geese and waterfowl populations. Each Annual Report shall discuss the actions taken to implement this program.

(iii) No additional requirements in addition to those specified in subsections (A)-(C) above exist for discharges to waters for which **Mercury** is a Stormwater Pollutant of Concern.

(b) Sharing Responsibility

(1) Qualifying Local Program

The permittee may satisfy the requirement to implement a BMP for a Minimum Control Measure by having a third party implement the BMP.

When a permittee is relying on a third party to implement one or more BMP(s), the permittee shall note that fact in the registration and Annual Report required in Section 6(*j*), below. If the third party fails to implement the BMP(s), the permittee remains responsible for its implementation.

(Note: For example, if a local watershed organization performs an annual "river clean-up", this event may be used to satisfy a BMP for the Public Participation and/or the Pollution Prevention and Good Housekeeping Minimum Control Measure.)

(2) Qualifying State or Federal Program

If a BMP or Minimum Control Measure is the responsibility of a third party under another NPDES stormwater permit, the permittee is not required to include such BMP or Minimum Control Measure in its Stormwater Management Plan. The permittee shall reference this qualifying program in their Stormwater Management Plan. However, the permittee is not responsible for its implementation if the third party fails to perform. The permittee shall periodically confirm that the third party is still implementing this measure. If the third party fails to implement the measure, the Stormwater Management Plan may be modified to address the measure, if necessary.

In the case of a permitted municipal industrial activity that is covered by the General Permit for the Discharge of Stormwater Associated with Industrial Activity, the permittee may reference the activity's Stormwater Pollution Prevention Plan to address a portion of the permittee's Stormwater Management Plan.

(Note: For example, the permittee may reference a regional mall's requirement to perform sweeping and catch basin cleaning under the General Permit for the Discharge of Stormwater Associated with Commercial Activity. This third party action may be used to address a portion of the permittee's requirement under the Good Housekeeping and Pollution Prevention Minimum Control Measure.)

(3) Coordination of Permit Responsibilities

Where a portion of the separate storm sewer system within a municipality is owned or otherwise the responsibility of another municipality, institution or a state or federal agency the entities shall coordinate the development and implementation of their respective Stormwater Management Plans to address all the elements of Section 6. A description of the respective responsibilities for these elements shall be included in the Stormwater Management Plan for each municipality.

(Note: For example, a storm sewer system within a municipality may be operated and maintained by the DOT. In cases such as these, the two entities shall coordinate their Stormwater Management Plans to address the Minimum Control Measures, particularly at the interface between the two storm sewer systems.)

(4) Co-Permitting

When a municipal Regulated Small MS4s is co-located within the corporate boundary of another Regulated Small MS4, the two may, at their discretion, submit a single registration and share a single Plan as co-permittees. In such a case, the Plan shall clearly indicate which co-permittee is responsible for implementing each of the control measures and other elements of the Plan.

(Note: This provision currently applies only to the City of Groton within the Town of Groton and the Borough of Stonington within the Town of Stonington.)

(c) Proper Operation and Maintenance

The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control, including related appurtenances, which are installed or used by the permittee to achieve compliance with the conditions of this permit. Proper operation and maintenance includes adequate laboratory controls and appropriate quality assurance procedures. Proper operation and maintenance requires the operation of backup or auxiliary facilities or similar systems, installed by a permittee when necessary to achieve compliance with this permit.

(d) Signature Requirements

The Plan shall be signed by the chief elected official or principal executive officer, as those terms are defined in Section 22a-430-3(b)(2) of the Regulations of Connecticut State Agencies. The Plan shall be retained by the chief elected official or principal executive officer and copies retained by MS4 officials or employees responsible for implementation of the Plan.

(e) Plan Review Fee

When submitting a Stormwater Management Plan as requested by the Commissioner pursuant to Section 6(*f*), below, the permittee shall submit a plan review fee of $375.

(f) Keeping Plans Current

The permittee shall amend the Plan whenever; (1) there is a change which has the potential to cause pollution of the waters of the state; or (2) the actions required by the Plan fail to prevent pollution of the waters of the state or fail to otherwise comply with any other provision of this general permit; or (3) the Commissioner requests modification of the Plan. The amended Plan shall be completed and all actions required by such Plan shall be completed within a time period determined by the Commissioner.

The Commissioner may notify the permittee in writing at any time that the Plan does not meet one or more of the requirements of this general permit. Within thirty (30) days of such notification, unless otherwise specified by the Commissioner in writing, the permittee shall respond to the Commissioner indicating how they plan to modify the Plan to address these requirements. Within ninety (90) days of this response or within one hundred twenty (120) days of the original notification, whichever is less, unless otherwise specified by the Commissioner in writing, the permittee shall then revise the Plan, perform all actions required by the revised Plan, and shall certify to the Commissioner that the requested changes have been

made and implemented. The permittee shall provide such information as the Commissioner requires to evaluate the Plan and its implementation. If at any time the Commissioner finds that the Plan is not adequate to protect the waters of the state from pollution, the Commissioner may terminate authorization under this permit and require the permittee to submit an individual permit application.

(g) Failure to Prepare or Amend Plan

In no event shall failure to complete or update a Plan in accordance with Sections 5(*b*) and 6 of this general permit relieve a permittee of responsibility to implement actions required to protect the waters of the state and to comply with all conditions of this general permit.

(h) Plan Review Certification

A copy of the Plan review certification made in accordance with Section 3(*b*)(9) shall be maintained with the Plan.

(i) Monitoring Requirements

All permittees shall comply with the screening and monitoring requirements in this subsection.

(1) Impaired Waters Outfall Investigation and Monitoring

Regulated Small MS4s that discharge to impaired waters, as identified in Section 6(*k*) below, must create an inventory of all outfalls that discharge to impaired waters utilizing the list and mapping prepared pursuant to Section 6(*a*)(3)(C). The permittee shall then screen these outfalls for the pollutant identified as the pollutant of concern for the impairment in accordance with the following procedures. If the permittee has wet weather sampling data for an outfall pursuant to their sampling conducted under the 2004 MS4 permit or other appropriate wet weather sampling, they may use that data for their outfall screening and will not be required to screen that outfall under this general permit.

(A) Outfall Screening for Phosphorus and Nitrogen

The permittee shall screen outfalls from the MS4 identified in Section 6(*a*)(3)(C) that discharge to impaired waters for which phosphorus or nitrogen is the pollutant of concern. The permittee may take a sample at the outfall during any rain event that results in a discharge from the outfall in accordance with subsection (2), below. This screening shall be conducted for all such outfalls at least once during the term of this general permit in accordance with subparagraphs (i) and (ii) below.

(i) Nitrogen Screening

The permittee may use a portable nitrogen meter to take a field reading during the wet weather discharge. If the nitrogen reading exceeds the following threshold, the outfall shall be identified for follow-up investigation pursuant to subsection (D) below.

Total Nitrogen > 2.5 mg/l

(ii) Phosphorus Screening

The permittee may use a portable phosphorus meter to take a field reading during the wet weather discharge. If the phosphorus reading exceeds the following threshold, the outfall shall be identified for follow-up investigation pursuant to subsection (D) below.

Total Phosphorus > 0.3 mg/l

(B) Outfall Screening for Bacteria

The permittee shall screen outfalls from the MS4 that discharge to impaired waters for which bacteria is the pollutant of concern. The permittee may take a sample at the outfall during any rain event that results in a discharge from the outfall in accordance with subsection (2), below. The sample shall be analyzed for the following:

- E. coli and Total Coliform (col/100ml) (for discharges to Class AA, A and B surface waters)
- Fecal coliform and Enterococci (col/100ml) (for discharges to Class SA and SB surface waters)

The outfall shall be identified for follow-up investigation pursuant to subsection (D) below if any of the following conditions apply:

- E. coli >235 col/100ml for swimming areas and >410 col/100ml for all others, or
- Total Coliform >500 col/100ml, or
- Fecal coliform >31 col/100ml for Class SA and >260 col/100ml for Class SB, or
- Enterococci >104 col/100ml for swimming areas and >500 col/100ml for all others.

If the permittee can document that bacteria levels at an outfall that exceed these levels are solely the result of natural sources of bacteria, they are not required to conduct a follow-up investigation for that outfall. Natural sources may include wildlife or runoff from undeveloped wooded areas but do not include pet waste or waterfowl congregating at parks, ponds or other attractive nuisance areas.

(C) Outfall Screening for Other Pollutants of Concern

The permittee shall screen outfalls from the MS4 identified in Section 6(*a*)(3)(C) that discharge to impaired waters for which pollutants other than phosphorus, nitrogen or bacteria are listed as the pollutant of concern. The permittee shall take a sample at the outfall and in-stream immediately upstream or otherwise outside the influence of the outfall. The sample may be taken during any rain event that results in a discharge from the outfall in accordance with subsection (2), below. These samples shall be analyzed for turbidity. The permittee may use a field turbidity meter for these analyses. If the

outfall sample is more than 5 NTU greater than the in-stream sample, the outfall shall be identified for follow-up investigation pursuant to subsection (D) below.

(D) Follow-up Investigations

The permittee shall conduct follow-up investigations for the drainage areas associated with the outfalls identified as potentially contributing to an impairment as a result of the analyses conducted pursuant to subsections (A) – (C), above.

(i) Drainage Area Investigation

The permittee shall investigate activities within the drainage area contributing to each outfall identified for follow-up investigation pursuant to subsections (A) – (C), above. This investigation shall include factors potentially associated with the cause of the related stream impairment. Such factors may include: land use or development patterns; business or commercial activities; industrial activities; DCIA; natural contributors; potential MS4 maintenance issues; residential activities; and any other activities identified by the permittee as potentially contributing to the related impairment.

(ii) Control Measure Implementation

In each outfall drainage area identified for follow-up investigation pursuant to subsections (A) – (C), above, the permittee shall implement a BMP program focusing on the impaired waters provisions of each of the Control Measures in Section 6(*a*) of this general permit and on the findings of the drainage area investigation in subparagraph (i), above.

(iii) Prioritized Outfall Monitoring

Once outfall screening has been completed for at least half of the outfalls identified pursuant to this section, the permittee shall utilize the screening results to select six (6) of the highest contributors of any of the pollutants of concern. These six outfalls shall be sampled annually for the appropriate pollutant of concern in accordance with the schedule in subsection (E), below. If more than one pollutant of concern is identified for any monitored outfall (i.e. more than one impairment), all of these pollutants shall be monitored. If fewer than six outfalls were identified for follow-up investigation, all of these outfalls shall be monitored, but no more than six.

(E) Schedule

(i) Impaired Waters Discharge Mapping

Inventory and mapping of discharges to impaired waters prepared pursuant to this section shall be completed within two (2) years from the effective date of this general permit for existing 2004 MS4 permittees and within three (3) years from the effective date of this general permit for new MS4 permittees.

(ii) Outfall Screening

Outfall screening pursuant to subsections (A) – (C) shall begin within one (1) year of the effective date of this general permit for existing 2004 MS4 permittees and two (2) years for new MS4 permittees. At least fifty percent (50%) of these outfalls shall be screened no later than the end of the third year following the effective date of this general permit for existing 2004 MS4 permittees and no later than the end of the fourth year for new MS4 permittees. All such outfalls shall be screened by the end of the term of this general permit (5 years).

(iii) Follow-up Investigations

The permittee shall commence follow-up investigations identified pursuant to subsection (D), above, no later than two (2) years following the effective date of this general permit for existing 2004 MS4 permittees and three (3) years for new MS4 permittees.

(iv) Prioritized Outfall Monitoring

The permittee shall commence annual monitoring of the six outfalls identified pursuant to subsection (D)(iii), above, no later than beginning of the fourth year following the effective date of this general permit for existing 2004 MS4 permittees and no later than the beginning of the fifth year for new MS4 permittees.

(F) Reporting

The permittee shall report on the progress of their impaired waters investigation and monitoring program in their Annual Report beginning in the second year following the effective date of this general permit. The report shall include a listing of the outfalls screened during the year, the number of outfalls identified for follow-up investigation, the progress of drainage area investigations, a description of the control measure implementation for the different impairments, identification of the six outfalls to be monitored, and the results of the prioritized outfall monitoring.

(2) Stormwater Monitoring Procedures

(A) Wet Weather Outfall Monitoring

Samples shall be collected from discharges resulting from any rain storm that produces a discharge from the outfall(s) being monitored and that occurs at least 48 hours after any previous rain storm that produced a discharge from the outfall. Runoff events resulting from snow or ice melt alone cannot be used to meet these monitoring requirements. However, monitoring may be conducted during a rain event that may include insignificant amounts of snow or ice melt. Monitoring shall consist of a single grab sample taken within the first six (6) hours of discharge from the outfall.

(B) Rain Event Information

The following information shall be collected for the rain events during which monitoring is conducted:

(i) The date, temperature, time of the start of the discharge, time of sampling, and magnitude (in inches) of the rain event sampled.

(ii) The duration between the rain event sampled and the end of the previous measurable (greater than 0.1 inch rainfall) rain event.

(C) Test Procedures

Unless otherwise specified in this permit, all pollutant parameters shall be tested according to methods prescribed in Title 40, CFR, Part 136 (1990). Laboratory analyses must be consistent with Connecticut Reasonable Confidence Protocols.

(j) Reporting & Record Keeping Requirements

(1) The permittee shall keep records required by this permit for at least 5 years following its expiration or longer if requested by the Commissioner in writing. Such records, including the Stormwater Management Plan, shall be available to the public at reasonable times during regular business hours.

(2) Annual Report

By April 1 of the second year following the effective date of this general permit and annually thereafter by April 1, the permittee shall submit an Annual Report for the preceding calendar year electronically to the Department. The DEEP MS4 stormwater webpage (www.ct.gov/deep/municipalstormwater) will provide guidance on Annual Report submittal. The Annual Report must be in Microsoft Word©, Adobe Acrobat© or other format acceptable to the Commissioner. In the event that electronic submission is not available or possible, please contact the Stormwater Section at (860) 424-3025.

The report shall include:

(A) The Annual Report review fee is $375.00.

(i) The fees for municipalities shall be half of those indicated above pursuant to section 22a-6(b) of the Connecticut General Statutes. State and Federal agencies shall pay the full fees specified in this subsection.

(B) A written discussion of the status of compliance with this general permit including, but not limited to:

(i) a listing and brief description (including, where appropriate, the address or latitude and longitude) of all BMPs within each Minimum Control Measure;

(ii) any reporting requirements enumerated in the controls measures sections 6(*a*) and its subsections;

(iii) an implementation schedule for each BMP and an indication of whether or not the BMP or any portion of the BMP was scheduled to be implemented during the year covered by the Annual Report;

(iv) the status of implementation for each BMP scheduled to be completely or partially implemented during the year covered by the Annual Report, including an assessment of the appropriateness of the BMP and progress towards achieving the implementation dates and measurable goals for that BMP;

(v) for any portion of a BMP implementation scheduled for the year covered by the Annual Report that was *not* completed as scheduled, a discussion of the circumstances and reasons for non-implementation, a modified implementation schedule, and, if necessary, a modified or alternate BMP to replace the BMP not implemented including the rationale for such modification or alternate BMP;

(vi) the overall status of each of the six categories of the Minimum Control Measures and a discussion of the effectiveness of each category in achieving its goals;

(vii) a discussion of any changes to personnel responsible for the Plan or BMP implementation;

(viii) a description of any new BMPs added to the Plan during the year including a description of the BMP, the reason or rationale for adding the BMP, the timeline for implementation, the party responsible for implementation and the measurable goal for the BMP and, where appropriate, the location for each BMP, including the address and latitude and longitude;

(ix) a discussion of the progress and status of the MS4's IDDE program (see Section 6(*a*)(3)) including outfall screening, mapping, drainage area evaluation and prioritization, illicit discharge tracking activities, IDDP field monitoring results, number and type of illicit discharges detected, and number of illicit discharges eliminated;

(x) a discussion of measures included in the Plan for the control of discharges to impaired waters (see Section 6(*k*) below) including a list of BMPs in the Minimum Control Measures that are targeted for such discharges, progress in implementing these measures, any evaluation of the effectiveness of these measures in meeting the goals of the Plan's impaired waters program, and any new or modified BMPs to be added to the Plan to improve its effectiveness;

(xi) a discussion of the MS4's stormwater monitoring program describing the status of monitoring for the year of the report, the overall status of the monitoring program, a summary of the findings, any significant observations regarding the results, any modifications to the Plan as a result of the monitoring results; and

(xii) a discussion of any planned BMP implementation in the coming year, including a discussion of any new or modified BMPs planned for future implementation.

(C) All monitoring data collected and analyzed pursuant to Section 6(*i*).

(D) All other information collected and analyzed, including data collected under the Illicit Discharge Detection Protocol (Appendix B), during the reporting period.

(k) Discharges to Impaired Waters or Water bodies subject to a Pollutant Load Reduction within a TMDL

MS4s that discharge to impaired waters (with or without a TMDL), waters for which nitrogen, phosphorus, bacteria or mercury are stormwater pollutants of concern, or waters which have pollution load reductions specified within a TMDL are required to meet certain criteria identified in this section and other sections of this general permit.

(1) Existing Discharge to an Impaired Water without an Established TMDL

If the permittee discharges to an impaired water without an established TMDL, the permittee must follow:

(A) For waters for which Phosphorus, Nitrogen, Bacteria, or Mercury are stormwater pollutants of concern, the control measures in Section 6(*a*) and the screening and monitoring requirements of Section 6(*i*)(1),

(B) For all other impairments, implement control measures to reduce the discharge of the pollutant(s) associated with the impairment and follow the requirements of Section 6(*i*)(1)(C), or as directed by the Commissioner.

(2) Existing Discharge to a Water with an Established TMDL or with a Pollutant Load Reduction specified within the TMDL

If the permittee discharges to a water included in a TMDL, the permittee must follow:

(A) For waters for which Phosphorus, Nitrogen, Bacteria, or Mercury is a stormwater pollutant of concern, the control measures in Section 6(*a*) and the screening and monitoring requirements of Section 6(*i*)(1),

(B) For all other discharges subject to a pollutant load reduction contained within a TMDLs, implement control measures to be consistent with the Waste Load Allocation in the specific TMDL. The permittee must also conduct the appropriate screening and monitoring in accordance with Section 6(*i*)(1).

(C) The permittee shall implement BMPs as necessary to achieve the Waste Load Allocation, Load Allocation or Water Quality Targets specified within the TMDL (see Appendix D).

(3) New Discharge to an Impaired Water without an Established TMDL

If a new discharge to an impaired water without a TMDL is authorized pursuant to the conditions of Section 3(*b*)(7), the permittee must implement and maintain any control measures or conditions on the site that enabled such authorization, and modify such measures or conditions as necessary to maintain such authorization. The permittee must also maintain compliance with this subsection and Section 6(*i*) and maintain documentation of these measures and conditions in their Plan.

(4) New Discharge to a Water with an Established TMDL or with a Pollutant Load Reduction specified within the TMDL

If a new discharge to a water with a TMDL or with a pollutant load reduction established within the TMDL is authorized pursuant to the conditions of Section 3(*b*)(7), the permittee must follow the discharge requirements consistent with the applicable Wasteload Allocations, Load Allocations or Water Quality Targets for that TMDL. The permittee must also conduct the appropriate screening and monitoring in accordance with Section 6(*i*)(1) and maintain documentation of these measures and conditions in their Plan.

Section 7. Additional Requirements of this General Permit

(a) Regulations of Connecticut State Agencies Incorporated into this General Permit

The permittee shall comply with all laws applicable to the subject discharges, including but not limited to, the following Regulations of Connecticut State Agencies which are hereby incorporated into this general permit, as if fully set forth herein:

(1) Section 22a-430-3:

Subsection (b) General - subparagraph (1)(D) and subdivisions (2), (3), (4) and (5)
Subsection (c) Inspection and Entry
Subsection (d) Effect of a Permit - subdivisions (1) and (4)
Subsection (e) Duty to Comply
Subsection (f) Proper Operation and Maintenance
Subsection (g) Sludge Disposal
Subsection (h) Duty to Mitigate
Subsection (i) Facility Modifications, Notification - subdivisions (1) and (4)
Subsection (j) Monitoring, Records and Report Requirements - subdivisions (1), (6), (7), (8), (9) and (11) (except subparagraphs (9) (A) (2) and (9) (c)
Subsection (k) Bypass
Subsection (m) Effluent Limitation Violations
Subsection (n) Enforcement
Subsection (p) Spill Prevention and Control
Subsection (q) Instrumentation, Alarms, Flow Recorders
Subsection (r) Equalization

(2) Section 22a-430-4

Subsection (t) Prohibitions
Subsection (p) Revocation, Denial, Modification
Appendices

(b) Reliance on Registration

In evaluating the permittee's registration, the Commissioner has relied on information provided by the permittee. If such information proves to be false or incomplete, the permittee's authorization may be suspended or revoked in accordance with law, and the Commissioner may take any other legal action provided by law.

(c) Duty to Correct and Report Violations

Upon learning of a violation of a condition of this general permit, a permittee shall immediately take all reasonable action to determine the cause of such violation, correct and mitigate the results of such violation and prevent further such violation. The permittee shall report in writing such violation and such corrective action to the Commissioner within five (5) days of the permittee's learning of such violation. Such information shall be filed in accordance with the certification requirements prescribed in Section 7(*e*) of this general permit.

(d) Duty to Provide Information

If the Commissioner requests any information pertinent to the authorized activity or to compliance with this general permit or with the permittee's authorization under this general permit, the permittee shall provide such information within thirty (30) days of such request. Such information shall be filed in accordance with the certification requirements prescribed in Section 7(*e*) of this general permit.

(e) Certification of Documents

Any document, including but not limited to any notice, information or report, which is submitted to the Commissioner under this general permit shall be signed by the chief elected official or principal executive officer of the municipality or institution, and by the individual or individuals responsible for actually preparing such document, each of whom shall certify in writing as follows:

"I have personally examined and am familiar with the information submitted in this document and all attachments thereto, and I certify that, based on reasonable investigation, including my inquiry of those individuals responsible for obtaining the information, the submitted information is true, accurate and complete to the best of my knowledge and belief. I understand that a false statement made in this document or its attachments may be punishable as a criminal offense, in accordance with Section 22a-6 of the Connecticut General Statutes, pursuant to Section 53a-157b of the Connecticut General Statutes, and in accordance with any other applicable statute."

(f) Date of Filing

For purposes of this general permit, the date of filing with the Commissioner of any document is the date such document is received by the Commissioner. The word "day" as used in this general permit means the calendar day; if any date specified in the general permit falls on a Saturday, Sunday, or legal holiday, such deadline shall be the next business day.

(g) False Statements

Any false statement in any information submitted pursuant to this general permit may be punishable as a criminal offense, in accordance with Section 22a-6, under Section 53a-157b of the Connecticut General Statutes.

(h) Correction of Inaccuracies

Within fifteen days after the date the permittee becomes aware of a change in any information in any material submitted pursuant to this general permit, or becomes aware that any such information is inaccurate or misleading or that any relevant information has been omitted, the permittee shall correct the inaccurate or misleading information or supply the omitted

information in writing to the Commissioner. Such information shall be filed in accordance with the certification requirements prescribed in Section 7(*e*) of this general permit.

(i) Other Applicable Law

Nothing in this general permit shall relieve the permittee of the obligation to comply with any other applicable federal, state and local law, including but not limited to the obligation to obtain any other authorizations required by such law.

(j) Other Rights

This general permit is subject to and does not derogate any present or future rights or powers of the State of Connecticut and conveys no rights in real or personal property nor any exclusive privileges, and is subject to all public and private rights and to any federal, state, and local laws pertinent to the property or activity affected by such general permit. In conducting any activity authorized hereunder, the permittee may not cause pollution, impairment, or destruction of the air, water, or other natural resources of this state. The issuance of this general permit shall not create any presumption that this general permit should or will be renewed.

Section 8. Commissioner's Powers

(a) Abatement of Violations

The Commissioner may take any action provided by law to abate a violation of this general permit, including but not limited to penalties of up to $25,000 per violation per day under Chapter 446k of the Connecticut General Statutes, for such violation. The Commissioner may, by summary proceedings or otherwise and for any reason provided by law, including violation of this general permit, revoke a permittee's authorization hereunder in accordance with Sections 22a-3a-2 through 22a-3a-6, inclusive, of the Regulations of Connecticut State Agencies. Nothing herein shall be construed to affect any remedy available to the Commissioner by law.

(b) General Permit Revocation, Suspension, or Modification

The Commissioner may, for any reason provided by law, by summary proceedings or otherwise, revoke or suspend this general permit or modify to establish any appropriate conditions, schedules of compliance, or other provisions which may be necessary to protect human health or the environment.

(c) Filing of an Individual Application

If the Commissioner notifies a permittee in writing that such permittee shall obtain an individual permit under Section 22a-430 of the Connecticut General Statutes if he wishes to continue lawfully conducting the authorized activity, the permittee shall file an application for an individual permit within thirty (30) days of receiving the Commissioner’s notice, or at such other date as the Commissioner may allow. While such application is pending before the Commissioner, the permittee shall comply with the terms and conditions of this general permit and the subject approval of registration. If the Commissioner issues an individual permit to a permittee under this general permit, this general permit, as it applies to such permittee, shall automatically terminate on the date such individual permit is issued. Nothing herein shall affect the Commissioner's power to revoke a permittee's authorization under this general permit at any time.

Issued Date: January 20, 2016

Michael Sullivan

Deputy Commissioner

This is a true and accurate copy of the general permit executed on January 20, 2016 by the Department of Energy and Environmental Protection.

Appendix A – Small MS4 Municipalities

Connecticut Municipalities with >1,000 People in Urbanized Areas		
Ansonia	Avon	Beacon Falls
Berlin	Bethany	Bethel
Bloomfield	Bolton	Branford
Bridgeport	Bristol	Brookfield
Brooklyn*	Burlington	Canton
Cheshire	Chester	Clinton
Cromwell	Danbury	Darien
Deep River	Derby	Durham
East Granby	East Hartford	East Haven
East Lyme	East Windsor	Easton
Ellington	Enfield	Essex
Fairfield	Farmington	Glastonbury
Granby	Greenwich	Griswold
Groton (City)	Groton (Town)	Guilford
Haddam*	Hamden	Hartford
Hebron	Killingly*	Ledyard
Lisbon	Madison	Manchester
Marlborough	Meriden	Middlebury
Mansfield*	Middlefield	Middletown
Milford	Monroe	Montville
Naugatuck	New Britain	New Canaan
New Fairfield	New Hartford*	New Haven
New London	New Milford	Newington
Newtown	North Branford	North Haven
Norwalk	Norwich	Old Lyme
Old Saybrook	Orange	Oxford
Plainfield*	Plainville	Plymouth
Portland	Prospect	Putnam
Redding	Ridgefield	Rocky Hill
Seymour	Shelton	Simsbury
Somers	South Windsor	Southbury
Southington	Sprague*	Stonington (Town & Borough)
Stratford	Suffield	Thomaston
Thompson	Tolland	Trumbull
Vernon	Wallingford	Waterbury
Waterford	Watertown	West Hartford
West Haven	Westbrook	Weston
Westport	Wethersfield	Wilton
Willington*	Windsor	Windsor Locks
Wolcott	Woodbridge	Woodbury

* Designates New MS4 Permittees

Appendix B
Illicit Discharge Detection and Elimination (IDDE) Program Protocol

(A) Illicit Discharge Detection and Elimination (IDDE) Program

Objective: The permittee shall implement an IDDE program to systematically find and eliminate sources of non-stormwater discharges to its MS4 and implement procedures to prevent such discharges.

During the development of the new components of the IDDE program required by this permit, permittees previously authorized by the permit issued January 9, 2004 must continue to implement their existing IDDE program required by that permit to detect and eliminate illicit discharges to their MS4.

(1) Definitions and Prohibitions

The permittee shall prohibit illicit discharges and sanitary sewer overflows (SSOs) to its MS4 and require removal of such discharges consistent with subsections (2) and (4), below.

An SSO is a discharge of untreated sanitary wastewater from a municipal sanitary sewer.

An illicit discharge is any discharge to an MS4 that is not composed entirely of stormwater, *except*:

(a) discharges authorized under a separate NPDES permit that authorize a discharge to the MS4

(b) non-stormwater discharges allowed by Section 3(a)(2) of this general permit

(2) Elimination of Illicit Discharges

(a) Upon detection, the permittee shall eliminate illicit discharges as soon as possible and require the immediate cessation of such discharges upon confirmation of responsible parties in accordance with its enforceable legal authorities established pursuant to subsection (B) below. Where elimination of an illicit discharge within sixty (60) days of its confirmation is not possible, the permittee shall establish a schedule for its elimination not to exceed 180 days (six (6) months). The permittee shall immediately commence actions necessary for elimination. The permittee shall diligently pursue elimination of all illicit discharges. In the interim, the permittee shall take all reasonable and prudent measures to minimize the discharge of pollutants to its MS4.

(b) The period between identification and elimination of an illicit discharge is not a grace period. Discharges from an MS4 that are mixed with an illicit discharge are not authorized by this general permit, are unlawful, and remain unlawful until eliminated.

(3) Non-Stormwater Discharges

The permittee may presume that the sources of non-stormwater listed in Section 3(a)(2) of this permit need not be addressed. However, if the permittee identifies any of these sources as significant contributors of pollutants to the MS4, then the permittee shall implement measures to control these sources so they are no longer significant contributors of pollutants, and/or eliminate them entirely, consistent with this appendix.

(4) Sanitary Sewer Overflows

(a) Upon detection of an SSO the permittee shall eliminate it as expeditiously as possible and take interim mitigation measures to minimize the discharge of pollutants to and from its MS4 until elimination is completed.

(b) The permittee shall identify all known locations where SSOs have discharged to the MS4 within the previous five years. This shall include SSOs resulting, during dry or wet weather, from inadequate conveyance capacities, or where interconnectivity of the storm and sanitary sewer infrastructure allows for communication of flow between the systems. Within 120 days of the effective date of the permit, the permittee shall develop an inventory of all identified SSOs indicating:

- Location (approximate street crossing/address and receiving water, if any);
- A clear statement of whether the discharge entered a surface water directly or entered the MS4;
- Date(s) and time(s) of each known SSO occurrence (i.e. beginning and end of any known discharge);
- Estimated volume(s) of the occurrence;
- Description of the occurrence indicating known or suspected cause(s);
- Mitigation and corrective measures completed with dates implemented; and
- Mitigation and corrective measures planned with implementation schedules.

The permittee shall maintain the inventory as a part of the Plan and update the inventory annually.

(c) The permittee shall provide written notice to the Commissioner within five (5) days of becoming aware of the SSO occurrence and shall include the information in the updated inventory. The notice shall contain all of the information listed in subsection (b), above.

(d) The permittee shall include and update the SSO inventory in its annual report, including the status of mitigation and corrective measures implemented by the permittee to address each SSO identified pursuant to this appendix.

(e) The period between identification and elimination of a discharge from the SSO to the MS4 is not a grace period. Discharges from an MS4 that are mixed with an SSO are not authorized by this general permit, are unlawful and remain unlawful until eliminated.

(5) Outfall/Interconnection Inventory

The permittee shall develop an outfall and interconnection inventory that identifies each outfall and interconnection discharging from the MS4, records its location and condition, and provides a framework for tracking inspections, screenings and other activities under the permittee's IDDE program pursuant to Section 6(*a*)(3) of this general permit.

(a) An outfall means a point source as defined by 40 CFR § 122.2 and in Section 2 of this general permit as the point where the MS4 discharges to waters of the state. An outfall does not include open conveyances connecting two separate storm sewers or pipes, tunnels or other conveyances that connect segments of the same stream or other waters of the state and that are used to convey waters of the state. However, it is strongly recommended that a permittee inspect all

accessible portions of the system as part of this process. Culverts longer than a simple road crossing shall be included in the inventory unless the permittee can confirm that they are free of any connections and simply convey waters of the state.

An interconnection means the point where the permittee's MS4 discharges to another MS4 or other storm sewer system, through which the discharge is conveyed to waters of the state or to another storm sewer system and eventually to a water of the state.

(b) The permittee shall complete its outfall and interconnection inventory in accordance with the timelines in Sections 6(*a*)(3)(C)(ii) and (iii) and shall include the progress of this inventory in each annual report. The inventory shall be updated annually to include data collected in connection with the dry weather screening under subsection (7(d)), below, and other relevant inspections conducted by the permittee.

(c) The inventory shall include the following information: unique identifier, receiving water, date of most recent inspection, dimensions, shape, material (concrete, PVC), spatial location (latitude and longitude with a minimum accuracy of +/-30 feet, physical condition and indicators of potential non-stormwater discharges (including presence or evidence of suspect flow and sensory observations such as odor, color, turbidity, floatables, or oil sheen) as of the most recent inspection.

(6) System mapping

The permittee shall develop a revised and more detailed map than was required by the previous permit issued January 9, 2004. This revised map of the MS4 shall include, at a minimum, parts of the MS4 within the Urbanized Area and those catchment areas of the MS4 with either DCIA of greater than 11% or which discharge to impaired waters ("priority" areas). This map shall be completed within three (3) years of the effective date of this permit for existing 2004 MS4 permittees and by the end of the permit term for new 2004 MS4 permittees. This permit does not provide additional time for existing 2004 MS4 permittees for completion of the mapping that was required by the previous permit.

(a) The mapping shall include, at a minimum, a depiction of the permittee's separate storm sewer system in the priority areas described above. The mapping is intended to facilitate the identification of key infrastructure and factors influencing proper system operation, and the potential for illicit sanitary sewer discharges. The map shall include the required infrastructure and water resources information as indicated in subparagraph (i), below, and shall include the information in subparagraph (ii), below, where available. The Commissioner also recommends the inclusion of additional items as indicated in subparagraph (iii), below.

(i) Required mapping elements

- Municipal separate storm sewer system
  - outfalls and receiving waters (required by previous permit)
  - pipes
  - open channel conveyances (swales, ditches, etc.)
  - catch basins
  - manholes
  - interconnections with other MS4s and other storm sewer systems

- municipally-owned stormwater treatment structures (e.g. detention and retention basins, infiltration systems , bioretention areas, water quality swales, gross particle separators, oil/water separators, or other proprietary systems)

- Catchment delineations as defined in Section 2 for use in priority rankings required in subsection (7)(c), below, or prioritizing BMP retrofits.
- Waterbodies identified by name and indication of all use impairments as identified on the most recent Integrated Water Quality Report pursuant to Clean Water Act section 303(d) and 305(b).

(ii) Elements required where available

- Municipal sanitary sewer system;
- Municipal combined sewer system, if applicable

(iii) Recommended elements

- Storm sewer material, size and age.
- Sanitary sewer system material, size and age
- Where a municipal sanitary sewer system exists, properties known or suspected to be served by a septic system, especially in high-density urban areas
- Area where the permittee's MS4 has received or could receive flow from septic system discharges (e.g. areas with poor soils, or high ground water elevations unsuitable for conventional subsurface disposal systems)
- Seasonal high water table elevations impacting sanitary alignments
- Topography
- Orthophotography
- Alignments, dates and representation of work completed (with legend) of past illicit discharge investigations (e.g. flow isolation, dye testing, CCTV)
- Locations of suspected, confirmed and corrected illicit discharges (with dates and flow estimates)

(b) The mapping may be produced by hand or through computer-aided methods (e.g. GIS). The required scale and detail of the map shall be appropriate to facilitate a rapid understanding of the system by the permittee and the Commissioner. In addition, the mapping shall serve as a planning tool for the implementation and phasing of the IDDE program and demonstration of the extent of complete and planned investigations and corrections. The permittee shall update the mapping as necessary to reflect newly discovered information and required corrections or modifications.

(c) The permittee shall report on the progress towards the completion of the map required by this permit in each annual report.

(7) Written Illicit Discharge Detection and Elimination Program

The IDDE program shall be recorded in a written document pursuant to Section 6(*a*)(3) of the general permit. The IDDE program shall include each of the elements described in subsections (a) – (h), below, unless the permittee provides a written explanation within the IDDE program as to why a particular element is not applicable to the permittee.

Notwithstanding the permittee's explanation, the Commissioner may at any time determine that a particular element is in fact applicable to the permittee and require the permittee to add it to the IDDE program. The written IDDE program shall be completed within one (1) year of the effective date of the permit for existing 2004 MS4 permittees and within two (2) years of the effective date of this general permit for new MS4 permittees. The permittee shall implement the IDDE program in accordance with the goals and milestones set forth in subsection (8), below.

(a) Legal Authority

The IDDE program shall provide that the permittee has adequate legal authority to accomplish the following tasks: prohibit illicit discharges; investigate suspected illicit discharges; eliminate illicit discharges, including discharges from properties not owned by or controlled by the MS4 that discharge into the MS4 system; and implement appropriate enforcement procedures and actions. Adequate legal authority consists of a currently effective ordinance, by-law, or other regulatory mechanism. For existing 2004 MS4 permittees, the ordinance, by-law, or other regulatory mechanism was a requirement of that permit and was required to be effective by January 8, 2009. These permittees shall update their IDDE legal authority within one year of the effective date of this permit. New MS4 permittees must establish this legal authority on or before two (2) years of the effective date of this permit. The written IDDE program shall include a reference or citation of the authority the permittee will use to implement all aspects of the IDDE program.

(b) Statement of IDDE Program Responsibilities

The permittee shall establish a written statement that clearly identifies responsibilities with regard to eliminating illicit discharges. The statement shall identify the lead permittee agency(ies), department(s) or personnel responsible for implementing the IDDE Program as well as any other agencies, departments or personnel that may have responsibilities for aspects of the program (e.g. state or local health officials responsible for overseeing septic system construction; sanitary sewer system staff; inspectional services for enforcing plumbing codes; town counsel responsibilities in enforcement actions, institutional support staff etc.). Where multiple departments, agencies or personnel have responsibilities with respect to the IDDE program specific areas of responsibility shall be defined and processes for coordination and data sharing shall be established and documented.

(c) Assessment and Priority Ranking of Catchments

The permittee shall assess and priority rank the catchments, delineated as required by subsection (6)(a), above, in terms of their potential to have illicit discharges and SSOs and the related public health significance. This ranking will determine the priority order for screening of outfalls and interconnections pursuant to subsection (d), below, catchment investigations for evidence of illicit discharges and SSOs pursuant to subsection (e), below, and provides the basis for determining permit milestones pursuant to subsection (8), below.

(i) The permittee shall classify each catchment into one of the following categories:

- Excluded catchments: Catchments with no potential for illicit discharges may be excluded from the IDDE program. This category is limited to roadway drainage in undeveloped areas with no dwellings and no sanitary sewers; drainage for athletic fields, parks or undeveloped green space and associated parking without services;

cross-country drainage alignments (that neither cross nor are in proximity to sanitary sewer alignments) through undeveloped land.

- Problem Catchments: Catchments with known or suspected contributions of illicit discharges based on existing information shall be designated as Problem Catchments. This shall include any catchments where previous outfall/interconnection screening indicates sewer input based on olfactory/visual evidence or sampling results (ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and bacteria levels greater than the water quality criteria applicable to the receiving water; or ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and detectable levels of chlorine). Problem Catchments need not be screened pursuant to subsection (d), below, and shall be scheduled for catchment investigation pursuant to subsection (e), below. Problem catchments shall be identified during the initial ranking of catchments and subsequent rankings shall not add any catchments to the Problem Catchment category.
- High Priority Catchments: Catchments that have not been classified as Problem Catchments and that are discharging to an area of concern to public health due to proximity of public beaches, recreational areas, drinking water supplies or shellfish beds; catchments determined by the permittee as high priority based on outfall/interconnection screening under subsection (d), below, and catchment characteristics assessment under subparagraph (c)(ii), below. Any catchment where outfall/interconnection screening indicates sewer input based on olfactory/visual evidence or sampling results (ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and bacteria levels greater than the water quality criteria applicable to the receiving water; or ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and detectable levels of chlorine) shall be ranked at the top of the High Priority Catchments category and scheduled for catchment investigation pursuant to subsection (e), below.
- Low Priority Catchments: Catchments determined by the permittee as low priority based on outfall/interconnection screening under subsection (d), below, and catchment characteristics assessment under subparagraph (c)(ii), below.

(ii) The permittee shall priority rank catchments within each category (except for excluded catchments), based on screening factors. The permittee shall, at a minimum, consider the following screening factors:

- Past discharge complaints and reports.
- Poor dry weather receiving water quality- the following guidelines are recommended to identify waters as having a high illicit discharge potential: exceeding water quality standards for bacteria; ammonia levels above 0.5 mg/l; surfactants levels greater than or equal to 0.25 mg/l.
- Density of generating sites - Generating sites are those places, including institutional, municipal, commercial, or industrial sites, with a potential to generate pollutants that could contribute to illicit discharges. Examples of these sites include, but are not limited to, car dealers; car washes; gas stations; garden centers; and industrial manufacturing areas.
- Age of surrounding development and infrastructure – Industrial areas greater than 40 years old and areas where the sanitary sewer system is more than 40 years old will probably have a high illicit discharge potential. Developments 20 years or younger will probably have a low illicit discharge potential.
- Sewer conversion – Catchments that were once serviced by septic systems, but have been converted to sewer connections may have a high illicit discharge potential.

- Historic combined sewer systems – Catchments that were once serviced by a combined sewer system, but have been separated may have a high illicit discharge potential.
- Density of aging septic systems – Septic systems thirty years or older in residential land use areas are prone to have failures and may have a high illicit discharge potential. Consultation with local or state health officials is strongly encouraged.
- Culverted streams – any river or stream that is culverted for distances greater than a simple roadway crossing may have a high illicit discharge potential.

The permittee may also consider as priorities for evaluation for illicit discharges, although not necessarily indicators of the presence of illicit connections or discharges:

- Water bodies that receive a discharge from the MS4 and are drinking water supplies, shell fishing areas, beaches or waters used for contact recreation.
- Impaired waterbodies that receive a discharge from the MS4 or waters with approved TMDLs applicable to the permittee, where illicit discharges have the potential to contain the pollutant identified as the cause of the impairment.

The permittee may add additional relevant factors, including location-specific screening factors; if so, the permittee shall include the additional factors in its written IDDE program.

(iii) An initial illicit discharge potential assessment and priority ranking based on existing information shall be completed within two (2) years from the effective date of the permit for existing 2004 MS4 permittees. New MS4 permittees shall complete this assessment and ranking by the end of the term of the permit. The permittee shall update its assessment and priority ranking annually based on catchment delineations pursuant to subsection (6), above, the results of screening pursuant to subsection (d), below, and other new relevant information. The permittee shall provide a listing of all catchments and the results of the ranking for each catchment in each annual report. For each catchment being investigated the permittee shall also provide in its annual report (1) a summary of evidence of known or suspected illicit discharges and SSOs; (2) completed, ongoing or planned corrective measures addressing confirmed illicit discharges and SSOs; and (3) a schedule for completing and verifying measures correcting the confirmed illicit discharges and SSOs.

(d) Outfall and Interconnection Screening and Sampling

The IDDE program shall include a written procedure for screening and sampling of outfalls and interconnections from the MS4 in dry and wet weather for evidence of illicit discharges and SSOs. This screening procedure shall be used for:

- baseline outfall and interconnection screening pursuant to subparagraph (iii), below (dry weather);
- confirmatory screenings pursuant to subsection (f), below (dry and/or wet weather depending on catchment characteristics);
- follow-up screening pursuant to subsection (g), below (dry and/or wet weather depending on catchment characteristics).

(i) The screening and sampling procedure shall include procedures for sample collection, use of field kits, storage and conveyance of samples (including relevant hold times).

(ii) If an outfall is inaccessible or submerged, the permittee shall proceed to the first accessible upstream manhole or structure for the observation and sampling and report the location with the screening results. If an interconnection is inaccessible or submerged, interconnection screening shall occur at the first accessible location within the permittee's system upgradient of the interconnection.

(iii) Dry weather screening and sampling shall proceed only when no more than 0.1 inches of rainfall has occurred in the previous 24-hour period. When a flow is observed, a sample of the flow shall be collected and analyzed for the parameters listed in subparagraph (v), below. If no dry weather flow is observed, the permittee shall record the condition of the outfall and other relevant information. If no flow is observed, but evidence of dry weather flow exists, the permittee shall revisit the outfall during dry weather within one week of the initial observation, if practicable, to perform a second dry weather screening and sample any observed flow. The permittee shall identify in the annual report any other necessary follow-up actions to identify the source of any apparent intermittent flow not sampled.

(iv) Wet weather screening and sampling, which shall be conducted at an outfall and/or within the catchment area in accordance with subparagraph (e)(ii)b., below, shall proceed during or after a storm event of sufficient depth or intensity to produce a stormwater discharge but only during the spring (March to June) when groundwater levels are relatively high. The permit does not require a minimum rainfall event prior to wet weather screening. However, the purpose of wet weather screening and sampling under the IDDE program is to identify illicit discharges that may activate or become evident during wet weather. Permittees may incorporate provisions that assist in targeting such discharges, including avoiding sampling during the initial period of discharge ("first flush") and/or identifying minimum storm event intensities likely to trigger sanitary sewer interconnections.

(v) Samples shall be analyzed at a minimum for ammonia, chlorine, conductivity, salinity, *E. coli*. (freshwater receiving water) or enterococcus (saline or brackish receiving water), surfactants (such as MBAS), and temperature. All analyses with the exception of indicator bacteria can be performed with field test kits or field instrumentation. In addition, where the discharge is directly into a water quality limited water or a water subject to an approved TMDL, the sample shall be analyzed for the pollutants identified as the cause of the impairment. Sampling for pollutants of concern shall be conducted using the analytical methods found in 40 CFR §136, or alternative methods approved by the Commissioner in accordance with the procedures in 40 CFR §136. Other IDDE screening parameters shall be considered field screening and are not subject to 40 CFR Part 136 requirements.

(vi) Catchments where there is relevant information indicating sewer input to the MS4 or sampling results where ammonia $\geq$ 0.5 mg/l, surfactants $\geq$ 0.25 mg/l, and bacteria levels greater than the water quality criteria applicable to the receiving water (or alternatively, ammonia $\geq$ 0.5 mg/l, surfactants $\geq$ 0.25 mg/l, and detectable levels of chlorine) shall be considered highly likely to contain illicit discharges from sanitary sources, and such catchments shall be ranked at the top of the High Priority Catchments category for investigation.

(e) Catchment Investigation Procedure

The permittee shall develop a written systematic procedure for catchment investigation that includes (1) a review of mapping and historic plans and records for the catchment; (2) a manhole inspection methodology; and (3) procedures to isolate and confirm sources of illicit discharges, as set forth below.

(i) For each catchment being investigated, the permittee shall review relevant mapping and historic plans and records to the extent available, including but not limited to plans related to the construction of the storm drain and of sanitary sewers in the catchment, prior work performed on the storm drain or sanitary sewers, local health official or other municipal data on septic system failures or required upgrades, and complaint records related to SSOs, sanitary sewer surcharges, and septic system breakouts. This review shall be used to identify areas within the catchment with higher potential for illicit connections and System Vulnerability Factors that indicate a risk of sanitary or septic system inputs to the MS4 under wet weather conditions. Consultation with local or state health officials is strongly encouraged. The permittee shall identify and record the presence of any of the following specific System Vulnerability Factors:

- History of SSOs, including, but not limited to, those resulting from wet weather, high water table, or fat/oil/grease blockages;
- Sewer pump/lift stations, siphons, or known sanitary sewer restrictions where power/equipment failures or blockages could readily result in SSOs;
- Inadequate sanitary sewer level of service (LOS) resulting in regular surcharging, customer back-ups, or frequent customer complaints;
- Common or twin-invert manholes serving storm and sanitary sewer alignments;
- Common trench construction serving both storm and sanitary sewer alignments;
- Crossings of storm and sanitary sewer alignments;
- Sanitary sewer alignments known or suspected to have been constructed with an underdrain system;
- Sanitary sewer infrastructure defects such as leaking service laterals, cracked, broken, or offset sanitary infrastructure, directly piped connections between storm drain and sanitary sewer infrastructure, or other vulnerability factors identified through Inflow/Infiltration Analyses, Sanitary Sewer Evaluation Surveys, or other infrastructure investigations.
- Areas formerly served by combined sewer systems;
- Any sanitary sewer and storm drain infrastructure greater than 40 years old in medium and densely developed areas;
- Widespread code-required septic system upgrades required at property transfers (indicative of inadequate soils, water table separation, or other physical constraints of the area rather that poor owner maintenance);
- History of multiple local health department or sanitarian actions addressing widespread septic system failures (indicative of inadequate soils, water table separation, or other physical constraints of the area rather that poor owner maintenance);

The permittee shall document the presence or absence of System Vulnerability Factors for each catchment, retain this documentation as part of its IDDE program, and report this

information in Annual Reports. Where System Vulnerability Factors are present, the catchment shall be investigated pursuant to subparagraph (ii)b., below.

(ii) The manhole inspection methodology shall describe a storm drain network investigation that involves systematically and progressively observing, sampling (as required below) and evaluating key junction manholes in the MS4 to narrow the location of suspected illicit discharges or SSOs to an isolated pipe segment between two manholes, locate evidence of illicit discharges or SSOs that may not be evident at the outfall under all circumstances, and confirm or identify potential system vulnerability factors. The written catchment investigation procedures shall detail how the permittee will further isolate and identify potential illicit discharges as indicated by field kit detections equal to or greater than the threshold values listed in subparagraph (d)(vi), above. The permittee is responsible for selecting key junction manholes in a manner such that the distance between key junction manholes is appropriate to ensure a thorough assessment of its system.

The manhole inspection methodology may either start from the outfall and work up the system or start from the upper parts of the catchment and work down the system or be a combination of both practices. Either method must, at a minimum, include an investigation of each key junction manhole within the MS4, even where no evidence of an illicit discharge is observed at the outfall. The Catchment Investigation Procedure must describe the method the permittee will use.

a. Dry weather investigation

Key junction manholes shall be opened and inspected for visual and olfactory evidence of illicit connections (e.g. excrement, toilet paper, gray filamentous bacterial growth, or sanitary products present). If flow is observed, the permittee shall sample the flow at a minimum for ammonia, chlorine and surfactants and can use field kits for these analyses. Additional indicator sampling may assist in determining potential sources (e.g. bacteria for sanitary flows, conductivity to detect tidal backwater, etc.). Where sampling results or visual or olfactory evidence indicate potential illicit discharges or SSOs, the area draining to the junction manhole shall be flagged for further investigation, through upstream junction manhole investigation and/or isolation and confirmation of sources pursuant to subsection (e)(ii), above.

Manhole inspections in all areas shall also include identifying System Vulnerability Factors including common (twin invert) manholes, directly piped connections between storm drains and sanitary sewer infrastructure, common weir walls, sanitary sewer underdrain connections and other structural vulnerabilities where sanitary discharges could enter the storm drain system during wet weather. Where present, such System Vulnerability Factors shall be investigated pursuant to paragraph (b) below.

b. Wet weather investigation

Where the review of mapping and historic plans and records and/or manhole inspections indicate the presence of one or more System Vulnerability Factors as listed in subsection (e)(i), above, the permittee shall also inspect and sample under wet weather conditions to the extent necessary to determine whether wet weather-induced high flows in sanitary sewers or high groundwater in areas served by septic

systems result in discharges of sanitary flow to the MS4. The permittee shall conduct at least one wet weather screening and sampling at the outfall for any catchment where one or more System Vulnerability Factors are present. This sampling can be done upon completion of any dry weather investigation but must be completed before catchment investigation is marked as complete. All data shall be recorded and reported in each annual report.

(iii) Isolation and Source Verification Procedures

The permittee shall develop procedures to be used to isolate and confirm sources where manhole investigations or other physical evidence or screening has identified MS4 alignments to be influenced by illicit discharges or SSOs. These shall include isolation of the drainage area for implementation of more detailed investigations, inspection of additional manholes along the alignment to refine the location of potential contaminant sources, and methods such as caulk damns, targeted internal plumbing inspections, dye testing, video inspections, or smoke testing to isolate and confirm the sources.

(f) Removal and Confirmation

When the source of an illicit discharge or SSO is identified and confirmed, the permittee shall exercise its authority as necessary to require its removal pursuant to subsections (2) or (3), above. For each confirmed source the permittee shall include in the annual report the following information: the location of the discharge and its source(s), a description of the discharge, the method of discovery, date of discovery, date of elimination, mitigation or enforcement action; and estimate of the volume of flow removed.

Within one year of removal of all identified illicit discharge and SSO sources within a catchment area, confirmatory outfall or interconnection screening shall be conducted. The confirmatory screening shall be conducted in dry weather unless System Vulnerability Factors have been identified in the catchment pursuant to subsection (e)(i), above, in which case both dry weather and wet weather confirmatory screening shall be conducted. If confirmatory screening indicates evidence of additional illicit discharges, the catchment shall be scheduled for additional investigation. Confirmatory screening is not required in catchments where no illicit discharges or system vulnerability factors have been identified and no previous screening indicated suspicious flows.

(g) Follow-up Screening

Upon completion of catchment investigation pursuant to subsection (e), above, and illicit discharge removal and confirmation (if necessary) pursuant to subsection (f), above, the catchment outfall or interconnection shall be scheduled for follow-up screening within five years, or sooner as determined by the permittee based on the catchment's illicit discharge priority. Follow-up screening shall consist of dry weather screening and sampling except that wet weather screening and sampling shall also be required in catchments where wet weather screening was required by subparagraph (e)(ii)b., above.

(h) Illicit Discharge Prevention Procedures

The permittee shall develop and implement mechanisms and procedures designed to prevent illicit discharges and SSOs, such as: spill response and prevention procedures including identification of spills, reporting procedures, containment procedures, and documentation;

public awareness (this may be a part of the education program required by subsection (2), above); reporting (hotlines) and training of public employees involved in the IDDE program on ways to identify potential illicit discharges and SSOs.

(8) IDDE Program Implementation Goals and Milestones

The permittee shall implement the IDDE Program to meet the following goals and milestones:

(a) The permittee shall complete dry weather screening and sampling (where flowing) of every MS4 outfall and interconnection (except Excluded and Problem Catchments) no later than three years from the permit effective date for existing 2004 MS4 permittees and by the end of the permit term for new MS4 permittees. Existing 2004 MS4 permittees may rely on screening conducted under the previous permit issued January 9, 2004, pursuant to an enforcement action, or by the Commissioner to the extent that it meets the requirements of subsection (7), above. New MS4 permittees shall complete dry weather screening and sampling of every MS4 outfall and interconnection (except Excluded and Problem Catchments) no later than the end of the permit term. All data shall be reported in each annual report. Permittees that have conducted substantially equivalent monitoring to that required by subsection (7)(d), above, as part of an enforcement action can request an exemption from the requirements of subsection (7)(d), above, by submitting a written request to the Commissioner and retaining exemption approval from the Commissioner as part of the Plan. Until the permittee receives formal written approval of the exemption from subsection (7)(d), above, from the Commissioner the permittee remains subject to all requirements of subsection (7)(d), above.

(b) Existing 2004 MS4 permittees shall begin investigations using the procedure developed in accordance with subsection (7)(d), above, within three months of investigation procedure finalization and no later than 15 months (1 year and 3 months) from the effective date of the permit. New MS4 permittees shall begin these investigations no later than 2 years and 3 months from the effective date of the permit. All permittees shall make continued progress each year toward meeting the milestones of subsection (8)(c), below. The permittee shall continue investigation, including Problem Catchments, using its existing IDDE program until such time as the procedure under subsection (7)(e), above, is developed.

(c) The permittee shall implement the Catchment Investigation Procedure in every catchment of the MS4, even where dry weather screening does not indicate evidence of illicit discharges. The permittee shall begin implementation of the procedure in Problem Catchments and those catchments with the highest ranking in the Assessment of Priority Catchments pursuant to subsection (7)(c), above, Implementation of the Catchment Investigation Procedure shall comply with the following milestones. For purposes of these milestones, a catchment investigation is considered complete if a permittee has completed all elements of subsection (7)(e), above.

i. The permittee shall complete the Catchment Investigation Procedure in a minimum of 80% of the MS4 area served by Problem Catchments within three years of the permit effective date and 100% of Problem Catchments within five years of the permit effective date.

ii. The permittee shall complete the Catchment Investigation Procedure in every catchment of the MS4 where information indicates sewer input including outfall/interconnection screening that indicates sewer input based on olfactory/visual evidence or sampling results (ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and bacteria levels greater than the water

quality criteria applicable to the receiving water; or ammonia ≥ 0.5 mg/l, surfactants ≥ 0.25 mg/l, and detectable levels of chlorine) within five (5) years of the permit effective date.

iii. The permittee shall complete the Catchment Investigation Procedure in 40% of the area served by all MS4 catchments within five (5) years of the permit effective date, and in 100% of the area served by all MS4 catchments within ten (10) years of the permit effective date. The permittee may count the area of low priority catchments only if the Catchment Investigation has been started in all other MS4 catchments. For the purposes of this section, catchment investigations that have been started include those where provisions of subsections (7)(e)(i) and (ii), above, have been completed.

d. Where catchments do not contain junction manholes, the dry weather screening and sampling shall be considered as meeting the manhole inspection requirement. In these catchments, dry weather screenings that indicate potential presence of illicit discharges shall be further investigated pursuant to subsection (7)(e)(iii), above. Investigations in these catchments may be considered complete where dry weather screening reveals no flow; no evidence of illicit discharges or SSOs is indicated through sampling results or visual or olfactory means; and no wet weather System Vulnerability Factors are identified.

e. The permittee shall track progress towards these milestones in each annual report.

(9) Indicators of IDDE Program Progress

The permittee shall define or describe indicators for tracking program success. At a minimum, indicators shall include measures that demonstrate efforts to locate illicit discharges, the number of SSOs and illicit discharges identified and removed, the percent and area in acres of the catchment area served by the MS4 evaluated using the catchment investigation procedure, and volume of sewage removed. The permittee shall evaluate and report the overall effectiveness of the program based on the tracking indicators in the annual report.

(10) Training

The permittee shall, at a minimum, annually provide training to employees involved in IDDE program about the program, including how to recognize illicit discharges and SSOs. The permittee shall report on the frequency and type of employee training in the annual report.

Appendix C

AQUIFER PROTECTION AREAS AND OTHER GROUNDWATER DRINKING SUPPLY AREAS

GUIDANCE INFORMATION

The Stormwater Management Plan ("the Plan") should consider measures to reduce or mitigate potential impacts to both ground water (aquifers) and surface waters, taking into consideration both quantity and quality of the runoff. The emphasis should be to minimize, to the extent possible, changes between pre-development and post-development runoff rates and volumes. Coordination and discussion with the local water company is strongly encouraged.

The basic stormwater principals for Aquifer Protection Areas (and other groundwater drinking supply areas) are to prevent inadvertent pollution discharges/releases to the ground, while encouraging recharge of stormwater where it does not endanger groundwater quality. The permittee should review Sections 19-13-B32(h) and (i) of the Regulations of Connecticut State Agencies for additional information. Measures include:

- prevent illicit discharges to storm water, including fuel/chemical pollution releases to the ground;
- minimize DCIA and disconnect large areas of DCIA with natural or landscape areas;
- direct paved surface runoff to aboveground type land treatment structures – sheet flow, surface swales, depressed grass islands, detention/retention and infiltration basins, and wet basins. These provide an opportunity for volatilization of volatile organic compounds to the extent possible before the stormwater can infiltrate into the ground;
- provide necessary impervious pavement in high potential pollutant release areas. These "storm water hot spots" include certain land use types or storage and loading areas, fueling areas, intensive parking areas and roadways (see table below);
- only use subsurface recharge structures such as dry wells, galleries, or leaching trenches, to directly infiltrate clean runoff such as rooftops, or other clean surfaces. These structures do not adequately allow for attenuation of salts, solvents, fuels or other soluble compounds in groundwater that may be contained in runoff; and
- restrict pavement deicing chemicals, or use an environmentally suitable substitute such as sand only, or alternative de-icing agents such as calcium chloride or calcium magnesium.

Infiltration of stormwater should be **restricted** under the following site conditions:

- ***Land Uses or Activities with Potential for Higher Pollutant Loads:*** Infiltration of stormwater from these land uses or activities (refer to Table 7-5 below), also referred to as stormwater "hotspots," can contaminate public and private groundwater supplies. Infiltration of stormwater from these land uses or activities may be allowed by the review authority with appropriate pretreatment. Pretreatment could consist of one or a combination of the primary or secondary treatment practices described in the Stormwater Quality Manual provided that the treatment practice is designed to remove the stormwater contaminants of concern.

- ***Subsurface Contamination:*** Infiltration of stormwater in areas with soil or groundwater contamination such as brownfield sites and urban redevelopment areas can mobilize contaminants.

- ***Groundwater Supply and Wellhead Areas:*** Infiltration of stormwater can potentially contaminate groundwater drinking water supplies in immediate public drinking water wellhead areas.

Land Uses or Activities with Potential for Higher Pollutant Loads
Table 7-5 of the 2004 Stormwater Quality Manual

Land Use/Activities	
• Industrial facilities subject to the DEEP Industrial Stormwater General Permit or the U.S. EPA National Pollution Discharge Elimination System (NPDES) Stormwater Permit Program • Vehicle salvage yards and recycling facilities • Vehicle fueling facilities (gas stations and other facilities with on-site vehicle fueling) • Vehicle service, maintenance, and equipment cleaning facilities • Fleet storage areas (cars, buses, trucks, public works) • Commercial parking lots with high intensity use (shopping malls, fast food restaurants, convenience stores, supermarkets, etc.) • Public works storage areas	• Road salt storage facilities (if exposed to rainfall) • Commercial nurseries • Flat metal rooftops of industrial facilities • Facilities with outdoor storage and loading/unloading of hazardous substances or materials, regardless of the primary land use of the facility or development • Facilities subject to chemical inventory reporting under Section 312 of the Superfund Amendments and Reauthorization Act of 1986 (SARA), if materials or containers are exposed to rainfall • Marinas (service and maintenance) • Other land uses and activities as designated by the review authority

For further information regarding the design of stormwater collection systems in Aquifer Protection Areas, contact the Aquifer Protection Area Program at (860) 424-3020 or visit www.ct.gov/deep/aquiferprotection.

Appendix D – Impaired Waters Guidance

Surface Waters and Associated Stormwater Pollutants of Concern			
Stormwater Pollutant of Concern	Waterbodies included within a TMDL or Waters Included in Pollution Control Strategy Developed by CT DEEP	Impaired waters without a TMDL	
		Impaired Designated Use	Cause
Phosphorus	Any water body subject to a TMDL pollutant load reduction for Phosphorus or any waterbody included in the Interim Phosphorus Reduction Strategy for Connecticut Freshwater Non-tidal Receiving Rivers and Streams Technical Support Document (2014 or as amended) , including but not limited to the Bantam River Watershed, Blackberry River Watershed, Factory Brook Watershed, Farmington River Watershed, Fivemile River Watershed, Hockanum River Watershed, Housatonic River Main Stem Watershed, Limekiln Brook Watershed, Naugatuck River Watershed, Norwalk River Watershed, Pequabuck River Watershed Pomperaug River Watershed, Pootatuck River Watershed, Quinebaug River Watershed, Quinnipiac River Watershed, Shetucket River Watershed or Willimantic River Watershed	Habitat for Fish, Other Aquatic Life and Wildlife or Recreation	Phosphorus, Nutrient/ Eutrophication Biological Indicators, Dissolved Oxygen, Chlorophyll-a, or Excess Algal Growth
Nitrogen	Any water body subject to a TMDL pollutant load reduction for Nitrogen, including but not limited to the Long Island Sound TMDL for Dissolved Oxygen (entire state of CT)	Habitat for Marine Fish, Other Aquatic Life and Wildlife	Dissolved oxygen saturation, Nitrogen (Total), Nutrient / Eutrophication Biological Indicators, Oxygen, Dissolved
Bacteria	Any water body subject to a TMDL pollutant load reduction for Total Coliform, Escherichia coli, Fecal coliform or Enterococci	Recreation, Existing or Proposed Drinking Water, Commercial Shellfish Harvesting Where Authorized or Shellfish Harvesting for Direct Consumption Where Authorized	Total Coliform, Escherichia coli, Fecal coliform or Enterococci
Mercury	Any water body subject to a TMDL pollutant load reduction for Mercury (Entire state of Connecticut)	Habitat for Fish, Other Aquatic Life and Wildlife or Fish Consumption	Mercury

Water Quality Targets for Waters for Which Bacteria is a Stormwater Pollutant of Concern				
Water Quality Classification	**E. Coli (Freshwater Rec) (cols/100mls)**	**Enterococci (Marine Rec) (cols/100mls)**	**Fecal Coliform (Marine Shellfishing) (cols/100mls)**	**Total Coliform (Freshwater Drinking) (cols/100mls)**
AA	Instantaneous designated swimming 235 / Non designated Swimming 410 / All other Recreation 576 Geomean 126	N/A	N/A	Monthly Moving average <100 / Single Sample Maximum 500
A	Same as AA	N/A	N/A	N/A
B	Same as AA	N/A	N/A	N/A
SA (Direct Consumption)	N/A	Instantaneous Designated Swimming 104 / Instantaneous All other Uses 500 / Geomean 35	Geomean 14 / 90% of samples <31	N/A
SB (Indirect Consumption)	N/A	Same as SA waters	Geomean 88 / 90% of samples < 260	N/A

APPENDIX B: NATURAL DIVERSITY DATA BASE AREAS MAP

DRAFT

Natural Diversity Data Base Areas

WEST HAVEN, CT

December 2016

State and Federal Listed Species & Significant Natural Communities

Town Boundary

NOTE: This map shows general locations of State and Federal Listed Species and Significant Natural Communities. Information on listed species is collected and compiled by the Natural Diversity Data Base (NDDB) from a number of data sources . Exact locations of species have been buffered to produce the general locations. Exact locations of species and communities occur somewhere in the shaded areas, not necessarily in the center. A new mapping format is being employed that more accurately models important riparian and aquatic areas and eliminates the need for the upstream/downstream searches required in previous versions.

This map is intended for use as a preliminary screening tool for conducting a Natural Diversity Data Base Review Request. To use the map, locate the project boundaries and any additional affected areas. If the project is within a shaded area there may be a potential conflict with a listed species. For more information, complete a Request for Natural Diversity Data Base State Listed Species Review form (DEP-APP-007), and submit it to the NDDB along with the required maps and information. More detailed instructions are provided with the request form on our website.

www.ct.gov/deep/nddbrequest

Use the CTECO Interactive Map Viewers at www.cteco.uconn.edu to more precisely search for and locate a site and to view aerial imagery with NDDB Areas.

QUESTIONS: Department of Energy and Environmental Protection (DEEP)
79 Elm St., Hartford CT 06106
Phone (860) 424-3011

Connecticut Department of Energy & Environmental Protection
Bureau of Natural Resources
Wildlife Division



WOODARD
&CURRAN

woodardcurran.com

COMMITMENT & INTEGRITY DRIVE RESULTS